

# Final Scoping Memorandum

Bremerton Gas Works Site

Prepared for: Cascade Natural Gas Corporation

Aspect Project No. 080239-005 • Anchor QEA Project No. 131014-01.01

March 5, 2015

Prepared by



Aspect Consulting, LLC  
401 Second Avenue South, Suite 201  
Seattle, Washington 98104



Anchor QEA, LLC  
720 Olive Way, Suite 1900  
Seattle, Washington 98101

# **Final Scoping Memorandum**

Bremerton Gas Works Site

Prepared for: Cascade Natural Gas Corporation

Aspect Project No. 080239-005 • Anchor QEA Project No. 131014-01.01

March 5, 2015

Aspect Consulting, LLC & Anchor QEA, LLC

# Contents

|          |                                                                   |           |
|----------|-------------------------------------------------------------------|-----------|
| <b>1</b> | <b>Introduction .....</b>                                         | <b>1</b>  |
| 1.1      | Scoping Objectives .....                                          | 1         |
| 1.2      | Document Organization .....                                       | 2         |
| <b>2</b> | <b>Site History and Description .....</b>                         | <b>4</b>  |
| 2.1      | Site Location and Description .....                               | 4         |
| 2.2      | Site Uses Prior to 1930 .....                                     | 5         |
| 2.3      | Current and Historical Use and Operations .....                   | 5         |
| 2.3.1    | Operations on McConkey and Sesko Properties.....                  | 5         |
| 2.3.2    | Adjoining Properties.....                                         | 14        |
| 2.3.3    | Aquatic Parcels.....                                              | 16        |
| <b>3</b> | <b>Environmental Setting .....</b>                                | <b>18</b> |
| 3.1      | Climate and Meteorology .....                                     | 18        |
| 3.2      | Topography and Drainage .....                                     | 18        |
| 3.3      | Geology and Hydrogeology .....                                    | 18        |
| 3.3.1    | Regional Geologic Setting .....                                   | 18        |
| 3.3.2    | Site Geology .....                                                | 19        |
| 3.3.3    | Hydrogeology .....                                                | 21        |
| 3.3.4    | Geology and Hydrogeology Data Needs and Collection Strategy ..... | 21        |
| 3.4      | Human Populations and Land Use .....                              | 22        |
| 3.4.1    | Tribal Use .....                                                  | 22        |
| 3.4.2    | Drinking Water Use.....                                           | 22        |
| 3.4.3    | Land Use Data Needs and Collection Strategy .....                 | 23        |
| 3.5      | Port Washington Narrows and Dyes Inlet .....                      | 23        |
| 3.6      | Natural Resources .....                                           | 24        |
| 3.6.1    | Upland Areas.....                                                 | 24        |
| 3.6.2    | Aquatic Habitats .....                                            | 24        |
| 3.6.3    | Natural Resources Data Needs and Collection Strategy .....        | 25        |
| 3.7      | Cultural Resources .....                                          | 25        |
| 3.7.1    | Archaeological Sites and Historic Structures.....                 | 25        |
| 3.7.2    | Cultural Resources Data Needs and Collection Strategy .....       | 26        |
| <b>4</b> | <b>Previous Investigations and Remedial Actions .....</b>         | <b>27</b> |
| 4.1      | Initial Study Area Investigations.....                            | 27        |
| 4.1.1    | Ecology Field Inspection (1995).....                              | 27        |
| 4.1.2    | Preliminary Upland Assessment (2007) .....                        | 27        |
| 4.1.3    | Targeted Brownfield Assessment (2008) .....                       | 28        |
| 4.2      | Initial Study Area Removal Actions.....                           | 28        |

|          |                                                                                   |           |
|----------|-----------------------------------------------------------------------------------|-----------|
| 4.2.1    | Time Critical Removal Action (2010).....                                          | 28        |
| 4.2.2    | Time Critical Removal Action (2013).....                                          | 29        |
| 4.3      | Other Upland Investigations and Remedial Actions.....                             | 31        |
| 4.3.1    | Former SC Fuels Property Investigations and Remedial Actions (1997 to 2007) ..... | 31        |
| 4.4      | Other Sediment Investigations and Remedial Actions .....                          | 32        |
| <b>5</b> | <b>Preliminary Conceptual Site Model.....</b>                                     | <b>34</b> |
| 5.1      | Potential Sources of Contamination.....                                           | 34        |
| 5.1.1    | Former Gas Works Property Sources .....                                           | 34        |
| 5.1.2    | Other Operations Sources – Adjacent Properties .....                              | 37        |
| 5.2      | Contaminant Migration and Transformation.....                                     | 38        |
| 5.2.1    | Migration Pathways .....                                                          | 38        |
| 5.2.2    | Transformation Processes .....                                                    | 40        |
| 5.2.3    | Contaminant Transport and Transformation Data Needs and Collection Strategy ..... | 40        |
| 5.3      | Exposure Pathways and Receptors.....                                              | 40        |
| <b>6</b> | <b>Project Planning.....</b>                                                      | <b>45</b> |
| 6.1      | Applicable or Relevant and Appropriate Requirements .....                         | 45        |
| 6.2      | Remedial Action Objectives .....                                                  | 46        |
| 6.3      | Preliminary Remediation Goals .....                                               | 47        |
| <b>7</b> | <b>Existing Data and Data Usability.....</b>                                      | <b>50</b> |
| 7.1      | Data Quality Characterization.....                                                | 50        |
| 7.1.1    | Minimum Data Acceptability Criteria .....                                         | 50        |
| 7.1.2    | Data Usability .....                                                              | 52        |
| 7.2      | Existing Site-Related Data.....                                                   | 53        |
| 7.2.1    | Soil Data.....                                                                    | 54        |
| 7.2.2    | Groundwater Data .....                                                            | 58        |
| 7.2.3    | Sediment Data.....                                                                | 60        |
| 7.2.4    | Surface Water Data (None) .....                                                   | 61        |
| 7.2.5    | Tissue Data (None).....                                                           | 61        |
| 7.3      | Existing Data from Other Cleanup Sites .....                                      | 61        |
| 7.4      | Data for Port Washington Narrows and Dyes Inlet .....                             | 61        |
| 7.4.1    | Sediment Quality Data.....                                                        | 62        |
| 7.4.2    | Tissue Quality Data .....                                                         | 62        |
| 7.4.3    | Water Quality Data .....                                                          | 62        |
| <b>8</b> | <b>RI/FS Approach .....</b>                                                       | <b>63</b> |
| 8.1      | Contaminants of Potential Concern .....                                           | 63        |
| 8.2      | Initial Study Area .....                                                          | 65        |
| 8.2.1    | Upland Portion of Initial Study Area .....                                        | 65        |
| 8.2.2    | Sediment Portion of Initial Study Area.....                                       | 66        |
| 8.3      | Investigation Methods.....                                                        | 66        |



|           |                                             |           |
|-----------|---------------------------------------------|-----------|
| 8.4       | Risk Assessment Methodology.....            | 68        |
| 8.4.1     | Human Health Risk Assessment.....           | 68        |
| 8.4.2     | Ecological Risk Assessment .....            | 70        |
| 8.5       | Potential Remedial Approaches .....         | 73        |
| 8.5.1     | Remedial Technologies .....                 | 73        |
| 8.5.2     | Remedial Approaches at Other MGP Sites..... | 74        |
| <b>9</b>  | <b>Summary and Data Gaps.....</b>           | <b>75</b> |
| <b>10</b> | <b>References.....</b>                      | <b>77</b> |

## List of Tables

---

|     |                                                                                 |
|-----|---------------------------------------------------------------------------------|
| 3-1 | Monitoring Well Construction Information and Groundwater Elevation Measurements |
| 6-1 | Potential ARARs, Contaminant-Specific                                           |
| 6-2 | Potential ARARs, Location-Specific                                              |
| 6-3 | Potential ARARs, Action-Specific                                                |
| 6-4 | Development of Initial PRGs for Soil                                            |
| 6-5 | Development of Initial PRGs for Groundwater                                     |
| 6-6 | Development of Initial PRGs for Sediment                                        |
| 6-7 | Development of Initial PRGs for Surface Water                                   |
| 7-1 | Summary of Data Quality Review for Existing Site Data                           |
| 7-2 | Summary of Data Quality Review for Existing Sediment and Tissue Data            |
| 7-3 | Statistical Summary of Soil Data                                                |
| 7-4 | Statistical Summary of Groundwater Data                                         |
| 7-5 | Statistical Summary of Sediment Data                                            |
| 8-1 | Nationwide MGP Site Summary                                                     |
| 8-2 | Summary of Preliminary Contaminants of Potential Concern                        |
| 8-3 | Remedial Technologies for NAPL                                                  |
| 8-4 | Remedial Technologies for Soil                                                  |
| 8-5 | Remedial Technologies for Groundwater                                           |
| 8-6 | Remedial Technologies for Sediment                                              |
| 9-1 | Summary of Existing Information and Data Gaps – Uplands                         |
| 9-2 | Summary of Existing Information and Data Gaps – Sediments                       |

## List of Figures

---

- 1-1 Site Location Map
- 2-1 Property Location and Area Zoning
- 2-2 Summary of Carbureted Water-Gas Process
- 2-3 MGP Operations and Potential Source Areas
- 2-4 Other Historical Operations and Potential Source Areas
- 2-5 Other Historical Industrial Processes
- 3-1 Surficial Geology and Regional Cross Section Location
- 3-2 Conceptual Regional Geologic Cross Section AA-AA'
- 3-3 Site Exploration and Cross Section Location Map
- 3-4 Generalized Geologic Cross-Section A-A'
- 3-5 Generalized Geologic Cross-Section B-B'
- 3-6 Generalized Geologic Cross-Section C-C'
- 3-7 Generalized Geologic Cross-Section D-D'
- 3-8 Monitoring Well Locations and Generalized Groundwater Flow Direction
- 3-9 Dyes Inlet and Port Washington Narrows Bathymetry and Outfall Locations
- 4-1 Upland Analytical Constituent Map
- 4-2 2010 and 2013 TCRA
- 5-1 Preliminary Conceptual Site Model
- 5-2 Conceptualized CSM Cross Section
- 5-3 Human Health Conceptual Site Model
- 5-4 Aquatic-Dependent Wildlife Conceptual Site Model
- 5-5 Terrestrial Wildlife Conceptual Site Model
- 7-1 Benzene Concentrations in Surface Soil (0 to 10 Feet)
- 7-2 Benzene Concentrations in Subsurface Soil (below 10 Feet)
- 7-3 Naphthalene Concentrations in Surface Soil (0 to 10 Feet)
- 7-4 Naphthalene Concentrations in Subsurface Soil (below 10 Feet)

- 7-5 Total cPAHs Concentrations in Surface Soil (0 to 10 Feet)
- 7-6 Total cPAHs Concentrations in Subsurface Soil (below 10 Feet)
- 7-7 Arsenic Concentrations in Surface Soil (0 to 10 Feet)
- 7-8 Arsenic Concentrations in Subsurface Soil (below 10 Feet)
- 7-9 Copper Concentrations in Surface Soil (0 to 10 Feet)
- 7-10 Copper Concentrations in Subsurface Soil (below 10 Feet)
- 7-11 Nickel Concentrations in Surface Soil (0 to 10 Feet)
- 7-12 Nickel Concentrations in Subsurface Soil (below 10 Feet)
- 7-13 Benzene Concentrations in Groundwater
- 7-14 Total cPAHs Concentrations in Groundwater
- 7-15 Naphthalene Concentrations in Groundwater
- 7-16 Arsenic Concentrations in Groundwater
- 7-17 Hexavalent Chromium Concentrations in Groundwater
- 7-18 Surface Sediment Benzo(a)pyrene Concentrations
- 7-19 Surface Sediment LPAH Concentrations
- 7-20 Surface Sediment HPAH Concentrations
- 7-21 Surface Sediment Sum of cPAH Concentrations
- 7-22 Surface Sediment cPAH TEQ Concentrations
- 7-23 Estimated Extent of Detected TPH/BTEX in Groundwater – Former SC Fuels Property
- 7-24 Locations of Existing Tissue and Sediment Data
- 7-25 Total Benzo(a)pyrene Concentrations in Existing Sediment Data
- 7-26 Total cPAH Concentrations in Existing Sediment Data
- 7-27 Total LPAH Concentrations in Existing Sediment Data
- 7-28 Total HPAH Concentrations in Existing Sediment Data
- 7-29 Total cPAH Concentrations in Existing Tissue Data (Wet Weight Basis)
- 7-30 Total cPAH Concentrations in Existing Tissue Data (Lipid-Normalized Basis)
- 8-1 Initial Study Area – Upland

### **List of Appendices**

---

- A Historical Records
- B DNR Lease History Documents
- C Boring and Well Logs
- D Soil, Groundwater, and Sediment Data

## Acronyms

---

|            |                                                                                                       |
|------------|-------------------------------------------------------------------------------------------------------|
| Anchor QEA | Anchor QEA, LLC                                                                                       |
| AOC        | Administrative Settlement Agreement and Order on Consent for Remedial Investigation Feasibility Study |
| ARAR       | applicable or relevant and appropriate requirement                                                    |
| Aspect     | Aspect Consulting, LLC                                                                                |
| AST        | aboveground storage tank                                                                              |
| BTAG       | Biological Technical Assistance Group                                                                 |
| BTEX       | benzene, toluene, ethylbenzene, and xylenes                                                           |
| Cascade    | Cascade Natural Gas Corporation                                                                       |
| CERCLA     | Comprehensive Environmental Response, Compensation, and Liability Act                                 |
| CFR        | Code of Federal Regulations                                                                           |
| City       | City of Bremerton                                                                                     |
| COC        | contaminant of concern                                                                                |
| COPC       | contaminant of potential concern                                                                      |
| cPAH       | carcinogenic polycyclic aromatic hydrocarbon                                                          |
| CSM        | conceptual site model                                                                                 |
| CSO        | combined sewer overflow                                                                               |
| DNAPL      | dense non-aqueous phase liquid                                                                        |
| DNR        | Washington State Department of Natural Resources                                                      |
| DQO        | data quality objective                                                                                |
| DU         | data usability                                                                                        |
| E&E        | Ecology & Environment                                                                                 |
| Ecology    | Washington State Department of Ecology                                                                |
| EcoSSL     | ecological soil screening level                                                                       |
| ENVVEST    | Environmental Investment Project                                                                      |
| EPA        | U.S. Environmental Protection Agency                                                                  |

|        |                                                       |
|--------|-------------------------------------------------------|
| ERA    | ecological risk assessment                            |
| ER-L   | effect range-low                                      |
| ER-M   | effect range-medium                                   |
| FS     | Feasibility Study                                     |
| HHRA   | human health risk assessment                          |
| HPAH   | high-molecular-weight polycyclic aromatic hydrocarbon |
| ISA    | Initial Study Area                                    |
| KPHD   | Kitsap Public Health District                         |
| Lent's | Lents and Blombergs                                   |
| LNAPL  | light non-aqueous phase liquid                        |
| LPAH   | low-molecular-weight polycyclic aromatic hydrocarbon  |
| MCL    | maximum contaminant level                             |
| µg/kg  | microgram(s) per kilogram                             |
| µg/L   | microgram(s) per liter                                |
| MDAC   | minimum data acceptability criteria                   |
| mg/kg  | milligram(s) per kilogram                             |
| MGP    | manufactured gas plant                                |
| MTCA   | Washington State Model Toxics Control Act             |
| NAPL   | non-aqueous phase liquid                              |
| NOAA   | National Oceanographic and Atmospheric Administration |
| NPL    | National Priorities List                              |
| NRHP   | National Register of Historic Places                  |
| Order  | Administrative Order for a Pollution Incident         |
| PAH    | polycyclic aromatic hydrocarbon                       |
| PCB    | polychlorinated biphenyl                              |

|       |                                               |
|-------|-----------------------------------------------|
| PCP   | pentachlorophenol                             |
| PHS   | Priority Habitats and Species Program         |
| PQL   | practical quantitation limit                  |
| PRG   | preliminary remediation goal                  |
| PSAMP | Puget Sound Assessment and Monitoring Program |
| RAO   | remedial action objectives                    |
| RCRA  | Resource Conservation and Recovery Act        |
| RI    | Remedial Investigation                        |
| RSL   | regional screening level                      |
| SCO   | sediment cleanup objective                    |
| Site  | Bremerton Gas Works Site                      |
| SMS   | Sediment Management Standards                 |
| SOW   | Statement of Work                             |
| SVOC  | semivolatile organic compound                 |
| TBA   | Targeted Brownfields Assessment               |
| TBC   | to be considered                              |
| TCRA  | time critical removal action                  |
| TEQ   | toxic equivalent                              |
| TOC   | total organic carbon                          |
| TPH   | total petroleum hydrocarbons                  |
| Tribe | Suquamish Tribe                               |
| TS    | total solids                                  |
| USCG  | U.S. Coast Guard                              |
| UST   | underground storage tank                      |
| VOC   | volatile organic compound                     |
| WDFW  | Washington Department of Fish and Wildlife    |



# 1 Introduction

Cascade Natural Gas Corporation (Cascade) is conducting a Remedial Investigation (RI) and Feasibility Study (FS) at the Bremerton Gas Works Site (Site) in Bremerton, Washington, under the direction of the U.S. Environmental Protection Agency (EPA). The work is being conducted in accordance with the Administrative Settlement Agreement and Order on Consent for Remedial Investigation Feasibility Study (AOC; Comprehensive Environmental Response, Compensation, and Liability Act [CERCLA] Docket No. 10-2013-0104). Consistent with the AOC, the Site includes the area where the gas works was formerly located (Figure 1-1), the adjacent beach, and the associated areal extent of contamination.

In November 2010, Cascade performed a time critical removal action (TCRA) at the Site with oversight from the EPA and the U.S. Coast Guard (USCG). EPA placed the Site on the National Priorities List (NPL) on May 10, 2012, and the AOC was executed on May 1, 2013. In accordance with the AOC, a Removal Evaluation and a Removal Action were performed in 2013 to assess and mitigate potential threats to human health, human welfare, and the environment attributable to site-related contaminants prior to completion of the RI/FS. That work is documented in the Removal Evaluation Report (Anchor QEA and Aspect Consulting 2013c) and the Time-Critical Removal Action Report (Anchor QEA and Aspect Consulting 2014).

Scoping is the initial planning phase of the RI/FS, as described in the Guidance for Conducting Remedial Investigations and Feasibility Studies under CERCLA (EPA 1988a). In accordance with the AOC, this Scoping Memorandum summarizes existing information to identify the scope of data collection needed to complete the RI/FS. After completion of the Scoping Memorandum, detailed project planning, including proposal of specific work to address data gaps, will be conducted and documented in the RI/FS Work Plan.

The objectives of the scoping process and the content and organization of this Scoping Memorandum are described below.

## 1.1 Scoping Objectives

---

The goal of scoping is to present and evaluate known information to identify the scope of data/information gathering necessary to conduct the RI and FS for the Site. Specific objectives of the scoping process are as follows:

- Identify and compile applicable historical information and data that are of acceptable quality for use during the RI/FS process;
- Identify relevant existing studies regarding the characteristics of environmental media and the condition of receptor populations at the Site;

- Identify usable information and data from current and historical studies for use in developing a conceptual site model (CSM);
- Identify an Initial Study Area (ISA) for both the upland area and the sediment area of the Site;
- Identify Site-specific objectives of the RI/FS, including initial preliminary remediation goals (PRGs), to help evaluate the adequacy of the existing information and to identify any data gaps;
- Establish a preliminary list of applicable and relevant and appropriate requirements (ARARs);
- Identify potential remedial approaches or technologies that may be applied, to determine potential data needs associated with remedial alternative development; and
- Document the need for additional information and data to the extent practicable to support the RI/FS.

## 1.2 Document Organization

---

The remainder of this Scoping Memorandum is organized as follows:

- **Section 2 — Site History and Description** describes the Site location, ownership, zoning, and operational history.
- **Section 3 — Environmental Setting** describes the Site physical conditions including topography and surface drainage, geology and hydrogeology, ecological environment (terrestrial and aquatic), cultural resources, land use, and existing infrastructure.
- **Section 4 — Previous Investigations and Remedial Actions** describes the previous investigations and cleanup actions conducted at the Site and on surrounding properties.
- **Section 5 — Preliminary Conceptual Site Model** identifies the potential sources of contaminants, their potential migration pathways, the environmental media in which their presence is suspected or has been confirmed, and the potential contaminant exposure pathways and receptors.
- **Section 6 — Project Planning** identifies potential ARARs for the Site, initial PRGs for potential contaminants in environmental media, and preliminary remedial action objectives (RAOs).
- **Section 7 — Existing Data and Data Usability** summarizes data collected during previous Site investigations and evaluates the quality and usability of that data.

- **Section 8 — RI/FS Approach** identifies preliminary contaminants of potential concern (COPCs), defines the ISA to be investigated, provides an overview of the risk assessment approach, and identifies potential remedial approaches.
- **Section 9 — Summary and Data Gaps** compiles the principal data needs for the RI/FS as defined in this Scoping Memorandum and defines the anticipated sequence of investigation activities.
- **Section 10 — References** lists documents used as sources of information and referenced in this Scoping Memorandum.

## 2 Site History and Description

This section describes the property upon which the former gas works was located and the properties surrounding the former gas works and discusses the operational and regulatory history of those properties.

### 2.1 Site Location and Description

---

The former gas works was located between Thompson Drive and Pennsylvania Avenue (Figure 2-1) on approximately 2.8 acres of property along the south shore of Port Washington Narrows in Bremerton, Washington. The historical street addresses for the former gas works included 1720 and 1800 Thompson Drive.

The real property upon which the former gas works was located (Former Gas Works Property) relative to current parcel boundaries is shown on Figure 2-1. Due to a boundary line adjustment in 1992, the Former Gas Works Property includes portions of two existing tax parcels:

- **Kitsap County Parcel No. 3711-000-0010-0409 (McConkey Property).** This parcel is owned by the McConkey Family Trust. The former gas works covered the entire parcel. No current or historical street address has been identified for this parcel.
- **Kitsap County Parcel No. 3741-000-022-0101 1701 Pennsylvania Avenue (Sesko Property).** This parcel is owned by Natasha Sesko. The former gas works covered the northwestern portion of this parcel.

The following properties are located near the Former Gas Works Property and have had either suspected or confirmed releases of contaminants from historical operations unrelated to the former gas works:

- **1723 Pennsylvania Avenue (Penn Plaza Property).** This property is owned by Penn Plaza Storage, LLC. There are multiple street addresses associated with this property, but it is listed in the Kitsap County assessor's database as 1723 Pennsylvania Avenue.
- **1701 Thompson Drive (Former ARCO Property).** This property is owned by Pipeworks Mechanical & Service, Inc. It is located southwest of the Former Gas Works Property, across Thompson Drive.
- **1702 Pennsylvania Avenue (Former SC Fuels Property).** This property is owned by NFS Properties 2, LLC. It is located east of the Sesko Property, across Pennsylvania Avenue.

The Port Washington Narrows is located north of the McConkey, Sesko, and Former SC Fuels Properties. The Port Washington Narrows consists of aquatic lands owned by the

State of Washington and managed by the Washington State Department of Natural Resources (DNR).

## **2.2 Site Uses Prior to 1930**

---

The Port Washington Narrows and the adjacent uplands are located in the traditional territory of the Suquamish Tribe (Tribe), a Southern Coast Salish community speaking a dialect of the Southern Lushootseed language (Suttles and Lane 1990). Shoreline locations in Dyes Inlet would have been available after stabilization of sea levels in the mid-Holocene (Thorson 1980); therefore, Native American use of the area may date back more than 5,000 years. A variety of traditional activities took place in the general vicinity. In 1855, the Tribe signed the Treaty of Point Elliott, which ceded lands and established the reservation at Port Madison. The Tribe retained “the right of taking fish at usual and accustomed grounds and stations” (Treaty of Point Elliott 1855), and the Port Washington Narrows is within the Tribe’s adjudicated Usual and Accustomed area.

## **2.3 Current and Historical Use and Operations**

---

Historical use and operations on the properties and aquatic lands are based on historical records, including aerial photographs, interviews with current and former workers, owners, area residents, historical maps, deeds, Washington State Department of Ecology (Ecology) records, City of Bremerton (City) records, and DNR lease records. A number of historical documents are included in previous assessments of historical Site use (TechLaw 2006; Hart Crowser 2007). Available and relevant historical records are provided in Appendix A for reference.

Historical and current operations on the Former Gas Works Property (which consists of the entire McConkey Property and a portion of the Sesko Property) as well as historical and current operations on the other portion of the Sesko Property are described in Section 2.3.1. Historical and current operations on adjoining properties are described in Section 2.3.2.

### ***2.3.1 Operations on McConkey and Sesko Properties***

#### **2.3.1.1 Former Gas Works Operations**

In 1930, the Former Gas Works Property was developed as a gas works (a.k.a., manufactured gas plant, or MGP). Gas works were a common industry in large and small towns throughout the United States and Europe from approximately the mid-1800s to the mid-1900s. At a gas works, coal, coke, and/or petroleum products were heated in furnaces to produce manufactured gas, which was subsequently distributed via a gas piping network to the surrounding homes and businesses for heating, cooking, and lighting. Gas works used or generated a number of products and byproducts, including non-aqueous phase liquids (NAPLs) such as oils and tars, aqueous waste streams, and solid materials containing chemicals that may pose a risk to human health or the

environment because they are toxic or carcinogenic (resulting in cancer effects). These contaminants include hydrocarbons such as benzene, toluene, ethylbenzene, and xylenes (BTEX) and polycyclic aromatic hydrocarbons (PAHs), which can persist for a long time in the environment. Contaminant releases from historical gas works operations at other locations have resulted in sites where contamination remains in the subsurface as NAPLs, sorbed to soil or sediments or dissolved in the groundwater.

Because of the potential hazards posed by historical gas works facilities, these facilities are often the focus of state-led or federally led efforts to investigate and clean up contamination to protect human health and the environment. To characterize and remediate these facilities, it is important to understand traditional gas works operations, the types of contaminants that may be present, and where contaminants may have been released. This section provides a summary of what is known about operations at the former gas works based on historical documentation and what is assumed based on typical gas works operations. This section also identifies the contaminants usually associated with gas works feedstocks, fuels, and byproducts that may be present at the Site. Uncertainties about historical practices and potential releases will be addressed in the RI through field investigations. Further discussion of potential release mechanisms and transport of contaminants in the subsurface is provided in Section 5, Preliminary Conceptual Site Model.

The operational history of the former gas works is as follows:

- **1930 to 1931.** The former gas works was constructed by the Western Gas and Utilities Corporation.<sup>1</sup> It included a dock on aquatic lands initially leased from DNR on November 25, 1930 (Former Gas Works Dock).
- **1931 to 1955.** Manufactured gas was produced using the carbureted water-gas process, from feedstocks of coal, coke briquettes, and petroleum products.<sup>2</sup> In the 1940s, a standby plant for producing natural gas by blending liquefied petroleum (butane or propane) and air was installed. Gas produced at the Former Gas Work Property in the 1940s and 1950s was from manufactured gas and from butane-air. In approximately 1955 (Simonson 1997b), manufactured gas operations ceased, and all gas was produced from butane-air mixing.

---

<sup>1</sup> In 1931, the Western Gas and Utilities Corporation changed its name to the Western Gas Company of Washington. The Western Gas and Utilities Corporation and the Western Gas Company of Washington are collectively referred to as “Western” herein.

<sup>2</sup> Typically, diesel-range fuel oils were used for petroleum feedstock for the carbureted water-gas process (Hatheway 2012). However, one historical map (Sanborn 1946) indicates gasoline and fuel oil were stored in the northeast corner of the Former Gas Works Property.

- **1955 to 1963.** Natural gas was produced from butane-air mixing. In 1963, with the completion of a natural gas pipeline to the region, gas production ceased.
- **1963 to 1972.** Some of the structures and tanks were removed between 1964 and 1965, and the concrete piers supporting the tanks were jackhammered and hauled away (White 1998). The former plant building was reportedly used for pipe storage and, for a short time, magnesium mining research (*Bremerton Sun* 1972). In 1972, the remaining structures, including the former plant building, were sold and dismantled.

In 1972, the Former Gas Works Property was acquired by Harold D. and L. Irene Lent and Theodore and Marian J. Blomberg, doing business as “Lent, Blomberg, Lent.” The Lent and Blomberg families operated several businesses in the vicinity of the Former Gas Works Property, including an oil distribution business on the Sesko Property under the name Lents, Inc. (see further discussion in Section 2.3.1.3). All entities and individuals associated with the Lents and Blombergs are referred to in this Scoping Memorandum as “Lent’s.”

In 1979, Paul and Margaret McConkey acquired the majority of the Former Gas Works Property. The McConkeys acquired the remainder of the Former Gas Works Property in 1985. A portion of the Former Gas Works Property was sold to William Sesko in 1992.

The summary of gas works operations provided in this section combines available historical information about the layout and operations of the former gas works with information compiled from multiple sources regarding the operations of typical manufactured gas facilities, including generated byproducts and likely sources of releases of hazardous substances. Whereas this summary provides an overview of operations at the former gas works, it likely does not provide a complete picture of all sources, disposal areas, and spills and/or releases that may have occurred, which will be investigated primarily through the collection and evaluation of data during the RI. Chemical feedstocks and potential byproducts typical of carbureted water-gas production<sup>3</sup> include the following:

- **Feedstock and Fuels: Gasoline, Diesel, Coal, or Coke Briquettes.** The contaminants potentially associated with feedstock and fuels include the following:
  - BTEX;

---

<sup>3</sup> Two byproducts typically generated at coal and/or oil gas plants, ammoniacal liquor and lampblack (carbon soot), were generally not generated in significant quantities by the carbureted water-gas process (Hatheway 2012).

- Naphthalenes; and
- PAHs.
- **Byproducts: Light Oil, Carbureted Water-Gas Tar, Ash, Clinker, Slag, Soot, and Spent Purifier Filter Media.** The contaminants potentially associated with byproducts include the following:
  - BTEX;
  - Naphthalenes;
  - PAHs;
  - Phenols; and
  - Other semivolatile organic compounds (SVOCs), including creosol, carbazole, and dibenzofuran.

Section 8.1 provides further discussion of the Site-specific COPCs.

Production of natural gas using liquefied petroleum (butane or propane) blended with air is not anticipated to have resulted in contamination of the subsurface because butane and propane are gases at atmospheric conditions.

A flow chart showing the gas works process as understood at the Site (based on available plant maps and typical carbureted water-gas operations), including the production of byproducts, is presented on Figure 2-2. The locations of key plant features are shown on Figure 2-3. The general sequence of operations is as follows:

- **Product Delivery and Storage.** Solid feedstocks (coal and coke briquettes) were transported to the Site by barge and offloaded via a winch to a storage slab located in the northwest corner of the Former Gas Works Property. Petroleum products were also delivered to the former gas works via barge and conveyed via a pipeline up the Former Gas Works Dock to storage tanks located in the northeast corner of the Former Gas Works Property.
- **Gas Generation and Purification.** These operations were located in the north-central portion of the Former Gas Works Property (Figure 2-3). Two generator sets (furnaces) were located in the main plant building: one in the northern portion of the building and one in the middle of the building (Simonson 1997b). The main plant building had a concrete floor (Simonson 1997b). Coal and coke were placed in the generators and heated, and fuel oil was sprayed into the generators to produce gas. The resulting gas stream was then passed through a series of devices to cool the gas and remove impurities. These devices are described below:



- **Scrubber.** After gas generation comes clarification, in which tar is separated from the gas using a scrubber or similar equipment. These devices are typically located adjacent to the generator sets. A historical plant map shows the scrubber located directly west of the generator sets. A former plant worker indicated that the scrubber consisted of a tank with wooden slots and water to “wash out” the gas (Simonson 1997b). An engineer’s report (Tymstra 1942) indicates that wood chips and excelsior (i.e., wood shavings) were used to remove tar from the gas.

The clarification process typically produced tar, tar-soaked wood chips or shavings, gas liquor (aqueous solutions containing dissolved and suspended tar particles), and tar-water emulsions. Light oils may also have been produced in the scrubbing process. Tar-water emulsions from scrubbers were typically removed from clarification equipment and transported to residual management areas to separate tar from the water (Hatheway 2012). The fate of byproducts and residuals is discussed in the bullet “Residuals Management.”

- **Gas Holder.** A large gas holder was located south of the scrubber, west of the main plant building. The bottom of the gas holder was reportedly 15 feet deep and contained tar and water (Simonson 1997a). The materials used to construct the base of the gas holder are not known.
- **Purifier.** Gas was passed through a bed of filter media to remove impurities such as sulfide from the gas. Typical filter media included wood chips and/or iron oxide. An engineer’s report (Tymstra 1942) indicated that iron-oxide-covered chips were used at the gas works to remove sulfur compounds from gas. Multiple purifiers in parallel were typically installed to allow changeout of purifier media without interrupting the process (Hatheway 2012). Three purifiers were located at the Former Gas Works Property south of the large gas holder. In addition to the generation of spent purifier media, which included some accumulated tar (Tymstra 1942), some liquid streams (including tar, gas liquor, and light oil) may have condensed during purification and were typically manually removed from the purifier box (Hatheway 2012). The fate of these byproducts is discussed in the following bullet.
- **Residuals Management.** In addition to the gas produced by the manufactured gas process, residual materials were also produced and separated from the gas at several steps during the process. These residuals were intermediate waste streams typically managed on-site and further processed to create byproducts for disposal or reuse. Residuals from the manufactured gas process included the following:

- **Tar-Water Emulsion.** Tar removed from the gas stream, particularly from the condenser, was often a tar-water emulsion. Tar required a low water content to be saleable. Tar-water emulsions were typically removed from clarification equipment and transported to residual management areas to separate the tar from the water (Hatheway 2012). Tar and water were typically separated by placing the emulsion in pits, cisterns, or tar wells (typically shallow boxes that may be lined or unlined) and allowing the tar to settle out. A former plant map shows tar wells and a residue cistern located west of the purifiers near the edge of the ravine adjacent to the former gas works (Former Ravine). A former resident recalled a tar pit located on the southwest corner of the Former Gas Works Property (Judd 2014), and an engineer's report (Tymstra 1942) noted, "The tar emulsion is dumped in shallow pits dug at random in the ground." A historical journal (Perry 2002) indicated that the former gas works "had a pond for dumping surplus creosote-type fluids. This would overflow and the material would go into the channel." It is unknown how tar-water emulsions were transported to these areas or how tar was transported from these areas to the tar storage tank, which was located on the south side of the Former Gas Works Property.
- **Storage, Distribution, and Disposal of Gas and Byproducts.**
  - **Finished Gas.** Gas that had passed through the scrubbers and purifiers was pumped through compressors located in the engine room (south of the main plant building) and stored in finished gas storage tanks located south of the main operations area. Gas was piped from the finished gas tanks to the gas distribution system along an 8-inch-diameter gas main located in Thompson Avenue. Typically in manufactured gas distribution systems, a minor amount of oil would condense within the initial section of distribution piping, which would be collected in a drip tank located near the facility (Hatheway 2012). A drip tank located just south of the Former Gas Works Property (Figure 2-3) is shown on a historical plant sketch.
  - **Light Oil.** Light oils typically contain one- or two-ring aromatic compounds, such as BTEX, and naphthalenes and have a density less than that of water (i.e., light, non-aqueous phase liquids [LNAPLs]). Light oils were sometimes reused in the carbureted water-gas process. According to a former worker, light oils were produced in small quantities at the former gas works and stored in a tank south of the finished gas storage tanks, and they were occasionally sprayed to control weeds in the southwest corner of the Former Gas Works Property or as automotive fuel for workers' vehicles (Simonson 1997b).

- **Carbureted Water-Gas Tar.** This tar typically contains both light aromatics (e.g., BTEX) and semivolatile hydrocarbons. Semivolatiles in coal tar primarily consist of PAHs but also include phenols and heterocyclic aromatics (i.e., carbazole or dibenzofuran). Coal tar is typically more dense than water (i.e., dense non-aqueous phase liquids [DNAPLs]). According to a former worker (Simonson 1997b), tar was a saleable product that was collected, stored in a tank on the south side of the Former Gas Works Property, and piped to barges at the Former Gas Works Dock. However, it is unlikely that all tar generated over the entire life span of the former gas works was recovered and sold in this manner.
- **Gas Liquor.** Gas liquor is water containing dissolved and suspended tar and oil constituents. According to the 1942 report (Tymstra 1942), this stream was discharged to “the bay” (i.e., the Port Washington Narrows) through a drainpipe.<sup>4</sup>
- **Ash, Clinker, and Slag (Mineral Residue of Fuel and Feedstocks) from the Furnaces.** Ash is generally powdery, whereas clinker is partially fused, and slag is fused. These materials were reportedly placed on the bluff along the shoreline (Judd 2014) north of the Former Gas Works Property and may have also been deposited in the Former Ravine.<sup>5</sup>
- **Soot from the Furnaces.** This material was reportedly placed in the Former Ravine near the oil storage tanks (Tymstra 1942).
- **Spent Scrubber and Purifier Media.** When scrubber and purifier media such as tar-soaked wood chips and shavings were saturated, they were removed and replaced. Spent scrubber media contains tar, and spent purifier media often contains tar, sulfide, and cyanide compounds removed during purification, including Prussian Blue (an iron-cyanide compound) (Hatheway 2012). During a period of gas works operations, tar-soaked wood chips and excelsior produced on-site were reportedly placed in the Former Ravine near the oil storage tanks (Tymstra 1942). However, an individual who worked at the former gas works between

---

<sup>4</sup> It is suspected that the drain pipe referred to in the 1942 report corresponds to the former outfall that was removed and plugged as part of the 2010 TCRA (see Section 4.2.1).

<sup>5</sup> Boring logs for SP01 and MW04, which were located in the Former Ravine, indicate ash.

1953 and 1955 indicated that the spent purifier media were hauled off-site.

#### **2.3.1.2 Post-1972 Operations on the McConkey Property**

Operations on the McConkey Property after the former gas works discontinued operations have included activities by Lent's between approximately 1972 and 1982 and industrial park operations by others from approximately 1982 to the present.<sup>6</sup>

Operations on the McConkey Property have included metal fabrication and sandblasting on the southern portion of the property and parking and equipment storage across the other portion of the property. Two buildings are located in the southern portion of the McConkey Property. Historical and current operations on the McConkey Property are shown on Figure 2-4. A generalized process flow diagram of the metal fabrication process is shown on Figure 2-5.

Ecology inspected industrial park operations on the McConkey Property in 1992, 1993, 1994, and 1995 and observed the following activities during that period that may have resulted in contaminant releases:

- Improper storage of sandblast grit, solvents, and paint sludge at a metal-fabricating shop; and
- Debris and drums containing oily substances scattered around the industrial park.

#### **2.3.1.3 Operations on the Sesko Property**

The Sesko Property was used for bulk petroleum storage and distribution from as early as 1946 to no later than 1993, when the aboveground storage tanks (ASTs) were removed. Lent's was the primary operator of the tank farm on the Sesko Property. Former AST locations are shown on Figure 2-4. A process flow diagram of petroleum storage and distribution operations is provided on Figure 2-5. Since 1993, the Sesko Property has been used for boat maintenance, automobile salvage, equipment and debris storage, parking, and metal reclamation. The owner of the Sesko Property was involved in legal disputes with the City over nonconforming use of the Sesko Property (as a junkyard), violations of the Shoreline Management Act, and, in 2003, improper decommissioning of an underground storage tank (UST). Ecology spill records also indicate that approximately 25 gallons of gasoline were released from the Sesko Property to surface water in January 2003. The majority of the equipment and debris has been removed, and the Sesko Property is currently vacant.

---

<sup>6</sup> Based on City directory information, Lent's continued operating on the McConkey Property for at least 3 years after the McConkeys acquired the majority of the McConkey Property in 1979.

The Sesko Property includes remnants of the Former Ravine, which has been filled over the years. Fill activities have included the following:

- **Before 1930.** No records documenting fill activities before operation of the former gas works have been identified. However, based on a comparison of the 1919 shoreline (Figure 2-4) with an aerial photograph dated 1946 and sewer maps dated 1939, it appears that a portion of the Former Ravine was likely filled by the late 1930s, before construction of a historical residence located on the Sesko Property and before construction of the Lent's tank farm.
- **1931 to 1955.** Aerial photographs and recorded observations (Tymstra 1942 and Judd 2014) indicate that the western portion of the Former Ravine was filled between 1931 and 1955. Recorded observations indicate that people unaffiliated with the former gas works dumped miscellaneous garbage, trash, and fill in the Former Ravine before 1942. Residual materials from former gas works operations (i.e., soot, ashes, cinders, and tar-laden wood chips and shavings) were also reportedly dumped in the Former Ravine during this period (see Section 2.3.1).
- **1941 to 1974.** An easement granted by Western to the City gave the City the right to dump refuse, garbage, and ashes from an incinerator into the Former Ravine. The easement reserved the right for Western to dump ashes and cinders in the easement area, which included the eastern 25 feet of the Former Gas Works Property (most of which lies on the current Sesko Property). According to the City, the historical records that partially document this time period were destroyed in a fire, and any documents regarding construction of the incinerator or dumping of refuse, garbage, or incinerator ash into the Former Ravine would have been lost in that fire.
- **1968.** A DNR inspection reported that concrete and piping debris were placed in the Former Ravine (DNR 1968).

Petroleum transfer lines that connected a dock located on the north edge of the Sesko Property (Former Sesko Dock) to the Former ARCO Property and the Lent's tank farm were formerly located on the Sesko Property and may still be in place. An employee of the owner of the Sesko Property indicated that he had removed a portion of underground petroleum transfer piping he encountered in the northern portion of the Sesko Property. Petroleum transfer lines also reportedly connected the Former Sesko Dock to the Former SC Fuels Property to the east. Approximate pipeline locations, shown on Figure 2-4, were identified on construction plans for City sewer improvements (CH2MHill 1982; MH&A 1982).

#### **2.3.1.4 Historical Operations Data Needs and Collection Strategy**

Uncertainties regarding historical operations of the former gas works include the following:

- Historical locations where tarry residuals were managed or placed; locations identified in historical records are approximate, and the specific locations of tar pits identified by Tymstra (1942) were not identified, although they may correspond with the tar pit identified by a former resident in the same time period (Judd 2014);
- Location of transfer lines from storage tanks to the generators; methods of conveyance/locations of pipelines of tar, oil, and gas liquor to residual management areas or byproduct storage tanks; and location of transfer lines from byproduct storage tanks to the Former Gas Works Dock; and
- Presence of subsurface structures (sumps, tar wells, and gas holder foundation) that may harbor process residuals.

Resolution of these uncertainties would assist in identifying locations of potential contaminant releases. Investigation methods to identify underground structures or former tar pits include geophysical survey and subsurface explorations such as test pits or trenches.

## ***2.3.2 Adjoining Properties***

Surrounding properties include: (1) the Penn Plaza Property, which is located to the south of the McConkey Property, (2) the Former ARCO Property, which is located to the west of the McConkey Property across Thompson Drive, and (3) the Former SC Fuels Property, which is located to the east of the Sesko Property across Pennsylvania Avenue (Figure 2-1). Historical and current operations on these properties are discussed in the following subsections.

### **2.3.2.1 Penn Plaza Property**

There are five buildings on the Penn Plaza Property, which is used as an industrial park. Multiple tenants occupy the industrial park. Based on available records, the Penn Plaza Property has been used for commercial and/or industrial uses since the late 1930s or early 1940s. Prior to this time, an intermittent stream ran northeast across the Penn Plaza Property toward the Former Ravine on the Sesko Property. This stream was reportedly used by area residents for dumping refuse and was filled in by 1942 (Judd 2014).

Operations on the Penn Plaza Property have included Lent's operations from the 1940s to approximately 1985 and industrial park operations from approximately 1985 to the

present.<sup>7</sup> Lent's operations on the Penn Plaza Property included spray painting, metal plating, a pipe shop, truck repair, and parking for petroleum distribution.<sup>8</sup> A former employee of Cascade, who worked in Bremerton in 1968 and 1969, recalled that wood treating may also have occurred as part of Lent's operations (Clapp 1997). Since the cessation of Lent's operations, multiple tenants have used the Penn Plaza Property for industrial uses, including sheet metal fabrication, floating pier and acrylic septic tank manufacturing, concrete pipe/manhole manufacturing, heating and air conditioning repair, and marine propeller repair (TechLaw 2006; Hart Crowser 2007).

Ecology inspected operations at the Penn Plaza Property in 1992, 1993, 1994, and 1995 and identified the following activities that may have resulted in contaminant releases:

- A tenant reported to Ecology that an electroplating operation had made illegal discharges to a storm drain that resulted in a sewer backup.
- Ecology observed improper storage of waste concrete and waste oil at one of the tenant locations.
- Ecology observed diesel staining on the ground at another tenant location.
- Ecology observed debris and drums containing oily substances scattered around the industrial park.

On the north end of the Penn Plaza Property are oil and gasoline supply pipelines that connected the Former Sesko Dock with the Former ARCO Property to the west. The approximate location of these pipelines, based on a utility locate conducted during the 2010 TCRA, is shown on Figure 2-4.

### **2.3.2.2 Former ARCO Property**

The Former ARCO Property was used for bulk petroleum storage and distribution from the mid-1940s to the late 1980s or early 1990s. Initially, 4 ASTs were present, with 2 added prior to 1956, 5 added in the late 1970s, and 4 added in the early 1980s for a total of 15 ASTs. Loading racks were located in the southeast corner of the Former ARCO Property. All tanks were removed by 1993. Property records indicate storage of gasoline, diesel, and oil. Product lines connected the ASTs on the Former ARCO Property with the Former Sesko Dock. Piping from the Former ARCO Property crossed the adjacent property to the north and ran west along the waterfront to a former dock (Former ARCO Dock) located approximately where the Port Washington Marina is today (see Section

---

<sup>7</sup> Based on City directory information, Lent's continued operating on the McConkey Property for at least 3 years after the property was sold in 1979.

<sup>8</sup> Petroleum for Lent's petroleum distribution was stored on what is now the Sesko Property.

2.3.3). According to a former resident, the piping to the Former ARCO Dock was located above ground (Judd 2014).

Since the early 1990s, the Former ARCO Property has been sporadically occupied by various tenants, including a tenant that conducted furniture refinishing and repair. The Former ARCO Property is currently being used for commercial use by Pipeworks Mechanical and Service, Inc.

#### **2.3.2.3 Former SC Fuels Property**

The Former SC Fuels Property was used for bulk petroleum storage and distribution from the mid-1940s to the present. Operations on the Former SC Fuels Property are currently inactive. Initially, five ASTs were present, with one AST added prior to 1963, for a total of six ASTs. Four USTs were removed in 2003. Property records indicate storage of gasoline, diesel, and waste oil.

The Former SC Fuels Property is registered in Ecology's Voluntary Cleanup Program. A series of environmental investigations and remedial actions performed between 1997 and 2007 have confirmed releases of petroleum products and associated constituents, including gasoline, diesel, oil, BTEX, and PAHs. Additional information about the investigations and remedial actions is provided in Section 4.3.1.

Stormwater at the Former SC Fuels Property is collected in a series of catch basins, piped to an oil-water separator located at the top of the bluff, and discharged through an outfall to the Port Washington Narrows (Figure 2-4). Ecology conducted a site visit in 2006 and noted a "gasoline odor" along the shoreline of the Former SC Fuels Property close to the stormwater outfall.

Pipes supplying petroleum to the Former SC Fuels Property tank farm ran from the Former SC Fuels Dock (see Section 2.3.3). An unknown number of petroleum transfer pipes also reportedly ran from the Former Sesko Dock to the tank farm on the Former SC Fuels Property, although their alignment is unknown (see Section 2.3.1.3).

#### **2.3.2.4 Adjoining Properties Data Needs and Collection Strategy**

The data needs associated with the adjoining properties consist of the following:

- Investigation of the drip tank associated with the former gas works distribution piping, which was located on the north end of the Penn Plaza Property, as a potential source of contamination; and
- Determining whether releases of hazardous substances that may have occurred on the adjoining properties may be migrating onto the Former Gas Works Property and commingling with gas works-related contamination.

### **2.3.3 Aquatic Parcels**

Four docks were constructed in the aquatic parcels located adjacent (or closest to) to the properties described in Sections 2.3.1 and 2.3.2 (Figure 4-2). These aquatic parcels were



leased from DNR. A description and brief history of each dock is included in the following paragraphs, and a detailed lease history prepared by DNR is provided in Appendix B.

#### **2.3.3.1 Former Gas Works Dock**

The Former Gas Works Dock was constructed by Western on November 25, 1930, as part of the development of the former gas works. It was located on the aquatic parcel adjacent and to the north of the Former Gas Works Property. The Former Gas Works Dock was used to offload coal, briquettes, and oil (via a 3-inch-diameter pipeline). Records indicate that the Former Gas Works Dock was also used to transfer heavy-end byproducts. In 1948, as part of the propane blending retrofit, the Former Gas Works Dock was updated to allow offloading of propane gas. Based on review of aerial photography, the Former Gas Works Dock was removed sometime between 1971 and 1974.

#### **2.3.3.2 Former ARCO Dock**

The Former ARCO Dock was constructed by the Richfield Oil Corporation in approximately 1942. It was located on the aquatic parcel immediately adjacent and to the west of the aquatic parcel operated by the former gas works. The Former ARCO Dock served as both boat moorage and support for the pipelines associated with upland ARCO operations. It was removed by Richfield Oil's successor in the mid-1980s.

#### **2.3.3.3 Former Sesko Dock**

The Former Sesko Dock was constructed by Lent's in approximately 1942. It was located on the aquatic parcel immediately adjacent and to the east of the aquatic parcel operated by the former gas works. The Former Sesko Dock was used to support supply pipelines for barge delivery of diesel and stove oil, which were stored on the Sesko Property. During the 1970s and 1980s, the Former Sesko Dock was also used to supply the tank farm on the Former ARCO Property and the tank farm on the Former SC Fuels Property. In 1993, the pipelines on the Former Sesko Dock were removed. The Former Sesko Dock was removed in September 2001 pursuant to a DNR order.

#### **2.3.3.4 Former SC Fuels Dock**

The Former SC Fuels Dock was constructed by General Petroleum Corporation of California in 1942. It was located on the aquatic parcel immediately adjacent and to the east of the aquatic parcel where the Former Sesko Dock was located. The Former SC Fuels Dock was constructed for the purpose of handling petroleum products. The Former SC Fuels Dock was removed in 1967 by Mobil Oil Corporation when barge deliveries of petroleum products were discontinued.

## 3 Environmental Setting

### 3.1 Climate and Meteorology

---

The Bremerton, Washington, area is dominated by a marine temperate climate with cool and comparatively dry summers and mild, wet, and cloudy winters (WRCC 2014). The average annual high temperature for Bremerton is 60 degrees Fahrenheit (°F), and the average annual low temperature is 43°F (WRCC 2014). Average annual precipitation is 52 inches, with nearly half of that occurring in November, December, and January (WRCC 2014). During this wet season, rainfall is usually light to moderate in intensity and continuous over a period of time, rather than brief, heavy downpours. During the driest months of July and August, it is not unusual for 2 to 4 weeks to pass with only a few showers (WRCC 2014). The prevailing wind direction in the region is south or southwest during the wet season and northwest in summer, with an average wind velocity of less than 10 miles per hour (WRCC 2014).

### 3.2 Topography and Drainage

---

The Former Gas Works Property is located on a bluff on the south shore of the Port Washington Narrows. The Former Gas Works Property generally slopes gently to the north and is covered with buildings or pavement. At the northern edge of the Former Gas Works Property, a vegetated bluff slopes steeply down to the beach. Over time, the bluff has expanded to the north with the placement of fill material. Remains of the Former Ravine along the eastern edge of the Former Gas Works Property can be seen as a cove located at the northern edge of the Sesko Property. Stormwater drainage characteristics on the Former Gas Works Property and adjacent properties are as follows:

- **McConkey and Penn Plaza Properties.** Pavement covers most of the McConkey and Penn Plaza Properties, and the properties have catch basins connected to the City stormwater drainage system. A City stormwater and combined sewer overflow (CSO) outfall is located offshore, north of Pennsylvania Avenue. A catch basin in the northwest corner of the McConkey Property is connected to an outfall on the beach below the bluff.
- **Sesko Property.** Most of the Sesko Property is unpaved. Stormwater either infiltrates or runs off, presumably to the north toward the Port Washington Narrows.

### 3.3 Geology and Hydrogeology

---

#### 3.3.1 Regional Geologic Setting

The Site lies within the Puget Lowland, an area that has alternated between glacial and interglacial environments during the last 2 million years. The result has been a stacked and imperfectly preserved sequence of glacial and nonglacial strata. This irregular

stratification has been further impacted by the tectonics of the Seattle fault, a regional thrust fault system that extends through the area, including a strand through Oyster Bay. The impacts of the fault system include uplift and tilting of bedrock and Quaternary strata in some areas and subsidence in others.

Interglacial climates produced sediments much like the forested Puget Lowland before extensive development, with broad floodplains and gently sloping uplands. These deposits include silty to sandy floodplain sediments, scattered gravelly channel deposits, and peat and lacustrine (lake) sediments. Glacial climates resulted in rapid accumulation of glacial sediments and scour of preexisting landforms and deposits. These deposits include advance glacial lake (glaciolacustrine) deposits, advance outwash (glacial river deposits), glacial till (subglacial deposits), and recessional glacial deposits.

Bedrock crops out on the northern end of the peninsulas between Phinney Bay and Ostrich Bay, and elsewhere generally north and west of the Site. Map data and limited deep well data suggest that bedrock generally dips to the south and west below the Site area. This bedrock dip forms a regional basement aquitard. Some of the older sediments above bedrock are also likely tipped in this direction due to regional rotation along the Seattle fault. Younger deposits, including those encountered in explorations for this project, are expected to be generally more horizontal but will include a number of discontinuous and irregularly shaped lenses of fine- and coarse-grained sediments that will impact the velocity and direction of groundwater flow. A conceptual geologic model of the Site area, including surficial geology (Figure 3-1) and subsurface geology (Cross Section AA-AA' on Figure 3-2) has been developed using regional map and well log data. Areas below the known exploration depths are shown as "undifferentiated."

The conceptual regional hydrogeologic model is one of rainfall and infiltration on an upland covered generally with till and glacial outwash. Some of this water runs off as stormwater, while a portion infiltrates. The water that infiltrates (groundwater) will migrate more quickly through more-permeable strata and will be generally retarded by less-permeable strata. The migration of water through these strata is influenced by the location and dip of the low-permeability strata (aquitards), as well as the location of waterways and other low-lying areas, which are often points of groundwater discharge. Regional patterns indicate that uplands are generally recharge areas, and slopes near sea level are discharge points. Groundwater also migrates from deeper strata and discharges upward into waterways.

### **3.3.2 Site Geology**

Four principal geologic units have been identified based on previous explorations: fill, natural glacial deposits of the Vashon Drift, nonglacial deposits from one or more of the interglacial events that preceded the Vashon glaciation, and deposits from an older glaciation. The characteristics and distribution of these major sequences are described in this section, from the stratigraphic top (generally younger) to the bottom. Note that these geologic interpretations are based on logs prepared by multiple geologists over the

course of the prior investigations. Subsurface interpretations from these earlier explorations (e.g., fill characteristics or extent) may be refined later based on future observations.

The locations of the cross sections are shown on Figure 3-3, and four geologic cross sections, are provided on Figures 3-4 through 3-7. Soil boring logs are provided in Appendix C. A description of the soils observed at the Site is provided in the following text.

Although fill was not specifically identified in many of the soil boring logs, it was apparently present in the majority of the previous explorations at the Site, in thicknesses ranging from a foot or less to about 15 feet. The thickest fill is present in the Former Ravine area on the Sesko Property. Fill is generally composed of brown to black, loose to very dense, or stiff to very stiff variable mixtures of silt and sand with variable amounts of gravel, coal fragments, asphaltic concrete, and other debris. The density and consistency of the fill was generally high for nonstructurally placed fills and may be due to inclusion of ash in the fill soils, which can produce slight cementation of soils.

Over the majority of the Site, glacial deposits were encountered beneath the surficial fill. The geologic maps of the Site indicate the glacial unit is the Vashon Drift. The soils encountered in the explorations generally consisted of clean (fines are absent) to silty fine- to medium-grained sand with trace to minor amounts of gravel and scattered interbeds of sandy silt. These glacial deposits were observed to be dense to very dense and were generally brown to gray. The gradation and density of this unit suggests that it is primarily Vashon advance glacial outwash. This unit has moderate permeability and, where saturated, will form an aquifer.

Pre-Fraser nonglacial deposits (predating the Vashon Glaciation) are present in the bluffs and uplands in the northeastern portion of the Site. Explorations encountered olive to gray and brown, stiff to hard silt to sandy silt with interbeds of very dense silty sand. Thin interbeds or lenses of clay and silty clay and scattered gravelly layers may be present. This unit generally has low permeability; however, cleaner sandy layers may become saturated.

An older glacial sequence is present below the Vashon outwash and the pre-Fraser nonglacial deposits. The older glacial sequence consists of lenses or discontinuous layers of glacial till within an outwash-like brown to gray, very dense slightly silty to silty sand. The lenses of till are composed of brown to gray very dense silty gravel with sand and silty sand with gravel. The till lenses are generally considered an aquitard, but the outwash-like silty sand component was noted to be wet below about the 5 to 10 foot elevation, which probably reflects the regional water table. Additional investigations will be conducted to determine whether till acts as an aquitard at the Site, as described in Section 3.3.4.

### **3.3.3 Hydrogeology**

Groundwater on the McConkey Property and Sesko Property was encountered at depths between 15 and 41 feet. Groundwater elevations have ranged between 3 and 10 feet above mean sea level, with an estimated flow direction to the north-northwest (to the Port Washington Narrows) during one sampling event (GeoEngineers 2007b). Monitoring well construction details and groundwater elevation measurements are summarized in Table 3-1. Well construction logs are included in Appendix C.

Groundwater on the Former SC Fuels Property has been encountered at depths between 4 and 15 feet, with an estimated flow direction to the northwest. Groundwater on the Former SC Fuels Property appears to be perched within sandy zones present in generally low-permeability nonglacial soils.

The estimated directions of groundwater flow on the McConkey, Sesko, and Former SC Fuels Properties, based on previous studies, are shown on Figure 3-8. However, groundwater studies to date have not evaluated the effect of tidal influence on-site groundwater levels and flow direction. One-time groundwater elevation measurements are prone to error if tidal effects are significant.

### **3.3.4 Geology and Hydrogeology Data Needs and Collection Strategy**

Data needed to further characterize Site geology and hydrogeology include the following:

- Identification of aquifer zones impacted by Site contamination. This would be determined by soil and groundwater sampling to characterize subsurface lithology and determine the nature and extent of contamination (see Section 7).
- Identification of aquitards underlying or between impacted aquifer zones. This would be determined through a combination of data collection methods, including characterization of subsurface lithology, evaluation of physical soil characteristics, and evaluation of hydraulic conductivity and gradients.
- Soil characteristics of aquifer and aquitard materials, including grain size, density, porosity, and organic carbon content. A subset of soil samples collected for chemical analysis would be tested for physical parameters.
- Hydraulic conductivity of aquifer materials. This would be measured using slug testing of Site wells.
- Hydraulic gradients and groundwater flow direction, including characterization of tidal influences and seasonal variability. These would be measured using a network of pressure transducers installed in wells over tidal cycles and during different seasons.

## 3.4 Human Populations and Land Use

---

The Former Gas Works Property is located in Bremerton, which is the largest city on the Kitsap Peninsula and home to Puget Sound Naval Shipyard and the Bremerton Annex of Naval Kitsap Base. According to the 2010 census, the population of Bremerton is 37,729 people with 1,328 inhabitants per square mile. The racial makeup of Bremerton is predominantly white/Caucasian (74%) with the rest of the population classified as “other” or two or more races (10.4%), African American (6.7%), Asian (5.5%), Native American (2.0%), and Pacific Islander (1.3%)<sup>9</sup>. According to the 2000 census, the total population of the Suquamish Tribe is 616 people.

The Former Gas Works Property is in an area of industrial-zoned properties that includes the Former ARCO Property and Former SC Fuels Property. Surrounding this industrial property core are residential properties and a marina. A zoning map is included on Figure 2-1.

### 3.4.1 Tribal Use

Tribal commercial, subsistence, and ceremonial fisheries have historically occurred in Dyes Inlet and the Port Washington Narrows. The Tribe has stated that “Suquamish tribal members fully intend to continue to fish these areas for cultural, subsistence and commercial purposes” (Suquamish Tribe 2014). “The Tribe uses the Washington Commercial Shellfish Growing Area Classification to determine the suitability of bivalve harvests (i.e., clams, oysters)” (Suquamish 2011). The marine area adjacent to the Former Gasworks Property is designated as “Unclassified,” due to proximity to CSOs, which precludes shellfish harvesting. However, the harvest of finfish and other marine invertebrates (i.e., crab and sea cucumber) are not restricted adjacent to the Former Gas Works Property (Suquamish 2011).

### 3.4.2 Drinking Water Use

Water services at the Site and surrounding area are supplied by the City. The closest public water supply wells are located over one mile from the Site. The use of private wells within the Bremerton Water Service Area is not allowed, and there are no drinking water wells near the Site listed in Ecology’s database.

---

<sup>9</sup>All work conducted during the RI/FS will be conducted in a manner consistent with EPA’s Environmental Justice principles. EPA defines Environmental Justice as: “*The fair treatment and meaningful involvement of all people regardless of race, color, sex, national origin, or income with respect to the development, implementation and enforcement of environmental laws, regulations, and policies.*”

The Site is located adjacent to the Port Washington Narrows, a saltwater body. The extent of saltwater intrusion and the potability of Site groundwater and its potential future use as a drinking water source have not been evaluated.

### **3.4.3 Land Use Data Needs and Collection Strategy**

Data needed to further characterize land use include the following:

- Evaluation of potential beneficial use of impacted aquifers. This would be evaluated by characterizing the extent of impacted groundwater and the physical and geochemical characteristics of the impacted aquifers, including hydraulic conductivity and salinity.

No data needs are currently identified for the use of the Port Washington Narrows. Through the RI/FS process, the Suquamish Tribe may provide additional information pertaining to historical and current tribal land use in the vicinity of the Site.

## **3.5 Port Washington Narrows and Dyes Inlet**

---

The Former Gas Works Property is located along the Port Washington Narrows, which is a tidal channel connecting Dyes Inlet to Sinclair Inlet and Puget Sound. Dyes Inlet is a terminal estuary, comprising five embayments (Phinney, Mud, Ostrich, Oyster, and Chico Bays) and the Port Washington Narrows (Figure 3-9).

The waters of Port Washington Narrows are relatively shallow, with average depths of less than 30 feet. Depths within Dyes Inlet range up to 100 feet but are typically less than 50 feet. Area bathymetry is shown on Figure 3-9.

The shorelines of the Port Washington Narrows and Dyes Inlet have been extensively developed. These shorelines include the cities of Bremerton and Silverdale as well as the community of Tracyton. Other significant features include several former U.S. Navy facilities and regional transportation networks, including State Routes 3 and 303. The Warren Avenue and Manette Bridges are located across the Port Washington Narrows east of the Former Gas Works Property.

Hydrologic inputs to the Port Washington Narrows and Dyes Inlet include the tidal exchange with Sinclair Inlet and freshwater inflows from both stream and piped flows. Figure 3-9 summarizes compiled information from Kitsap County and the City regarding identified stormwater outfalls, CSO discharge points, and surface water inputs. Additional private and municipal outfalls may be present in addition to those identified by these information sources.

Hydraulic exchange between Dyes Inlet, the Port Washington Narrows, and the balance of Puget Sound is limited by the geography and the resulting hydrodynamics. In addition to tide and current data available from public sources (e.g., National Oceanographic and Atmospheric Administration [NOAA]), the waters of Dyes Inlet and the Port Washington Narrows have been studied as part of regional water quality programs. Total maximum

daily load studies and a contaminant mass balance evaluation have been performed for Dyes Inlet and may provide useful data for the RI/FS. Hydrodynamic modeling of the area has been performed as part of regional studies of Puget Sound. The results of additional studies are available to characterize environmental quality within Sinclair Inlet, immediately south of Dyes Inlet and the Port Washington Narrows. The Sinclair Inlet studies include extensive testing that has been performed in association with the Bremerton Naval Shipyard, as well as other regional study programs.

Additional data may be needed to evaluate the feasibility of remedial alternatives as discussed in Section 9.

## **3.6 Natural Resources**

---

This section describes the natural resources of the upland areas, aquatic habitats, and related data needs for the RI/FS.

### **3.6.1 Upland Areas**

The upland areas of the Former Gas Works Property and surrounding areas have been developed for industrial uses consistent with zoning provisions. However, some terrestrial and riparian habitat is present, particularly on the bank adjacent to the Port Washington Narrows, the Former Ravine, and the shoreline areas of the McConkey and Sesko Properties. The Washington Department of Fish and Wildlife (WDFW) manages a Priority Habitats and Species Program (PHS). Preliminary queries of WDFW's PHS system did not identify any priority terrestrial natural resources on the parcels associated with the Former Gas Works Property.

### **3.6.2 Aquatic Habitats**

Aquatic habitats at the Site include those in the beach and subtidal areas within and near the Former Gas Works Property. Shoreline and aquatic habitat adjacent to the Former Gas Works Property are located within the Tribe's Usual and Accustomed area. Fish and shellfish resources are present within the waters of the Port Washington Narrows and Dyes Inlet. Fish and crab are known to be present and support commercial, recreational, and tribal fisheries. Shellfish harvesting within the Port Washington Narrows and Dyes Inlet has been restricted due to water-quality-related shellfish harvesting closures. However, efforts have been made by state and local governments, tribes, and other stakeholders to improve water quality in the area and reduce or lift these shellfish harvesting restrictions. A number of shellfish enhancement projects have been proposed within portions of Dyes Inlet. It is not known what measures have been undertaken by the Washington State Department of Health or the Kitsap Public Health District (KPHD) to monitor illicit shellfish harvesting within Dyes Inlet or the intertidal areas adjacent to the Site. Signage indicating the closure of the beach adjacent to the Former Gas Works Property was installed as part of the 2013 TCRA (see Section 4.2.2).

The query of the WDFW PHS identified two aquatic natural resources in the vicinity of the Former Gas Works Property: estuarine intertidal aquatic habitat along the northern



and southern shorelines of the Port Washington Narrows and hardshell clams along the northern shoreline of the Port Washington Narrows.

### **3.6.3 Natural Resources Data Needs and Collection Strategy**

Natural resources at the Former Gas Works Property need to be further defined and delineated in order to plan and accurately conduct a risk assessment for the RI/FS. Terrestrial and aquatic natural resources at the Former Gas Works Property, including threatened and endangered species, will be documented and described as part of the RI. Natural resource information for terrestrial and aquatic habitats at the Site will be developed based on information in scientific literature, data compilations from state and federal agencies, and information from the Suquamish Tribe, as well as Site surveys to be conducted during the RI/FS. This work will include an evaluation of shellfish harvesting.

## **3.7 Cultural Resources**

---

This section describes the archaeological sites and historic structures at and around the Site and discusses the cultural resources data needs and collection strategy.

### **3.7.1 Archaeological Sites and Historic Structures**

There are no recorded archaeological sites or historic structures at the Former Gas Works Property or in the immediate vicinity. However, no cultural resources surveys have been conducted on the Site or in the vicinity prior to the present project. The documented archaeological sites nearest to the Former Gas Works Property include the following:

- (b)(3)
- (b)(3)
- A number of ethnographic place names have been recorded at various locations along the Port Washington Narrows.

Kitsap County assessor's records (accessed January 2014) indicate that there is one building older than 50 years on the Penn Plaza Property—a warehouse constructed in 1955. The structure has not been evaluated for National Register of Historic Places (NRHP) eligibility. No impacts on this structure are anticipated during the RI/FS.

An Anchor QEA archaeologist visited the project area in August 2013 to make a preliminary assessment of current conditions. The project area has been extensively modified in the historic and modern eras, with placement of fill materials and debris, and development and redevelopment of the Site for industrial uses. No native sediments, other than active beach deposits, were visible in the project area.

### ***3.7.2 Cultural Resources Data Needs and Collection Strategy***

Despite historical disturbance and filling activity at the Site, the presence of documented archaeological sites within the vicinity indicates that there remains some potential for archaeological resources to be present in native upland soils beneath the fill deposits. RI/FS activities that penetrate these native soils will incorporate appropriate measures to protect potential archaeological resources, including potential archaeological monitoring and implementation of an incidental discovery plan. RI/FS activities will include coordination with the Suquamish Tribe and/or the State of Washington, consistent with the requirements of Section 106 of the National Historic Preservation Act.

## 4 Previous Investigations and Remedial Actions

### 4.1 Initial Study Area Investigations

---

Previous environmental field investigations at the Former Gas Works Property include the following:

- Sesko Property Field Inspection (Ecology 1995);
- Preliminary Upland Assessment, McConkey and Sesko Properties (GeoEngineers 2007b); and
- Targeted Brownfields Assessment (TBA), McConkey and Sesko Properties (E&E 2009).

The upland exploration locations and sampling depths by analyte group are provided on Figure 4-1. The scope and general conclusions of each study are described in the following subsections.

#### ***4.1.1 Ecology Field Inspection (1995)***

In 1995, Ecology collected three surface soil samples from the Sesko Property and one surface sediment sample from the tidelands just north of the Sesko Property. Samples were analyzed for metals and SVOCs. High concentrations of PAHs were detected. Ecology used the data in conducting a Site Hazard Assessment and ranked the Site a “1” (highest concern).

#### ***4.1.2 Preliminary Upland Assessment (2007)***

In 2007, on behalf of the City and funded by a brownfield grant from EPA, GeoEngineers conducted a preliminary assessment of the McConkey and Sesko Properties (GeoEngineers 2007a) that included the following:

- Advancing eight soil borings and collecting soil samples to a maximum depth of 45 feet;
- Installing monitoring wells at each of the eight soil boring locations and collecting groundwater samples; and
- Analyzing soil and groundwater samples for total petroleum hydrocarbons (TPH), VOCs, SVOCs, polychlorinated biphenyls (PCBs), and metals.

This work identified relatively high concentrations of gasoline- and diesel-range TPH, VOCs including benzene, and PAHs in soil and groundwater on the McConkey and Sesko Properties. VOCs and PAHs were detected in soil samples at depths up to 35 feet. Several metals, including arsenic, lead, and chromium (including chromium VI), were detected in groundwater at concentrations above potential drinking water cleanup standards.

### **4.1.3 Targeted Brownfield Assessment (2008)**

In 2008, on behalf of EPA, E&E conducted a TBA of the McConkey and Sesko Properties (E&E 2008) that included the following:

- Advancing seven soil borings and collecting soil samples to a maximum depth of 45 feet;
- Installing monitoring wells at two of the seven boring locations;
- Collecting groundwater samples from the two wells and from temporary screens placed at four of the seven soil boring locations;
- Collecting five surface sediment samples from the beach north of the properties;
- Analyzing soil, groundwater, and sediment samples for TPH, VOCs, SVOCs, and metals.

Similar to the Preliminary Upland Assessment, this work identified relatively high concentrations of gasoline- and diesel-range TPH, VOCs including benzene, and PAHs in soil and groundwater on the McConkey and Sesko Properties. The assessment also identified relatively high concentrations of PAHs in surface sediments. VOCs and PAHs were detected in soil samples at depths up to 45 feet.

## **4.2 Initial Study Area Removal Actions**

---

### **4.2.1 Time Critical Removal Action (2010)**

In August 2010, sheens on the surface water of the Port Washington Narrows were reported to KPHD. Upon further investigation, KPHD identified a 12-inch-diameter concrete pipe that appeared to be the source of the sheen. The pipe is believed to be an abandoned City CSO outfall. KPHD reported the release to EPA, which in turn notified USCG for a response because the pipe was within its jurisdiction. In 2010, at the request of EPA, Ecology & Environment, Inc. (E&E) conducted sampling and analysis as part of the EPA and USCG's initial response. The response sampling included the collection of 32 surface sediment samples from a depth of 0 to 6 inches. The sediment samples were analyzed for VOCs and SVOC, both of which were detected in some samples.

EPA, DNR, KPHD, and Ecology entered into a USCG-led coordinated response under a Unified Command Structure. Cascade became aware of the response in October of 2010 and informed the USCG that it was interested in contributing to the response. USCG subsequently added Cascade to the Unified Command Structure and issued Cascade an Administrative Order for a Pollution Incident (Order) to implement response actions at the Site under the oversight of USCG. Cascade accepted the Order in a letter dated October 29, 2010.

In response to the Order, Cascade developed a Work Plan for the Incident Action and 2010 TCRA (Anchor QEA and Aspect Consulting 2010), which outlined the scope and details of the 2010 TCRA. The 2010 TCRA included the following key elements:

- Investigation of the location and orientation of the abandoned pipe;
- Permanent plugging of the pipe as close as practicable to the shoreline;
- Removal of all portions of the pipe from the new plug to the terminus of the pipe;
- Backfilling of the excavation created by removal of the pipe with clean beach material;
- Placement of an organoclay mat over impacted sediments (with minimal disturbance) near the terminus of the pipe that were observed to generate sheen; and
- Continued maintenance of a containment system until field observations and inspections confirm the situation is stable (no sheen).

On November 5, 2010, USCG and the other members of the Unified Command Structure approved the Work Plan. Cascade commenced the TCRA immediately upon approval and completed the 2010 TCRA on November 8, 2010 (Anchor QEA 2011). The Removal Action satisfied the following objectives of the Work Plan:

- The pipe was located and traced to the shoreline.
- The pipe was plugged as close as practicable to the shoreline, at the location specified in the Work Plan.
- All pipe sections downgradient of the new plug were removed together with all overburden sediments.
- All excavations were filled to grade with clean beach material.
- The organoclay mat was placed over the area of impacted sediments specified in the Work Plan.

Inspections of the 2010 TCRA area were completed as specified in the Work Plan. No surficial sheens related to the 2010 TCRA have been observed to date. Figure 4-2 shows the constructed elements of the 2010 TCRA.

#### ***4.2.2 Time Critical Removal Action (2013)***

In 2013, Cascade completed a Removal Evaluation pursuant to the requirements of the AOC and the EPA-approved Removal Evaluation Work Plan (Anchor QEA and Aspect Consulting 2013a). The objective of the Removal Evaluation was to assess whether suspected migration pathways at the Site pose a threat to human health, welfare, or the environment if left unaddressed before completion of the RI/FS. The results of the

Removal Evaluation were reported in the EPA-approved Removal Evaluation Report (Anchor QEA and Aspect Consulting 2013c). The Removal Evaluation identified the following conditions that warranted action before completion of the RI/FS:

- **Stormwater intrusion into Manhole A.** Manhole A was believed to remain connected to the 12-inch-diameter concrete pipe that was plugged as part of the 2010 TCRA. Based on inspections conducted as part of the Removal Evaluation, stormwater could have been entering Manhole A through surface runoff or via a piping connection to Manhole A from a nearby sump. Stormwater entering Manhole A posed a risk of hydraulically surcharging the pipe plugged during the 2010 TCRA, which in turn could have increased the risk of a hazardous substances release to the Port Washington Narrows.
- **Hydrocarbon sheen and deposits of solid hydrocarbon material in the SG-04/SG-05 area.** Hydrocarbon sheens were observed in shallow subsurface sediments in the western area of the beach, near sampling stations SG-04 and SG-05. Surficial solid hydrocarbon material was also observed in the SG-04/SG-05 area. Both the sediments containing hydrocarbon sheen and the solid hydrocarbon material contained concentrations of PAH compounds that were elevated in comparison to those of the surrounding beach sediments.

The Removal Evaluation Report proposed the following removal actions in response to the identified conditions:

- **Plug the connections to Manhole A.** This action was intended to minimize the risk of hydraulic surcharge to the pipe plug and thereby minimize the risk of hydrocarbon releases from the pipe.
- **Remove the accessible solid hydrocarbon material and place a cap over the sediments containing hydrocarbon sheen in the SG-04/SG-05 area.** These actions were intended to minimize the risk of additional releases of hydrocarbons from this area to surface waters of the Port Washington Narrows and to prevent direct contact with these materials by beach users.
- **Install signage.** The purpose of the signs is to warn beach users regarding the presence of hydrocarbon contaminants in the beach sediments and provide agency contact information regarding the Site and the ongoing RI/FS process.

Upon completion of the Removal Evaluation, Cascade prepared a Removal Action Work Plan describing the proposed removal actions in more detail (Anchor QEA and Aspect Consulting 2013b). EPA approved the Final Work Plan and directed Cascade to perform the proposed removal actions (EPA 2013c). After EPA's approval, Cascade implemented the Removal Action (2013 TCRA), which met all of the objectives specified in the Work Plan including the following:

- Removing solid hydrocarbon material identified in the western beach area;

- Installing an organoclay mat and cover over the hydrocarbon sheen in subsurface sediments in the western beach area;
- Plugging Manhole A and the sump drain from the tank containment area;
- Completing beach monitoring inspections to confirm the effectiveness of the 2013 TCRA. Quarterly monitoring inspections are ongoing; and
- Installing required signage.

The work was completed in general accordance with the Work Plan and documented in the Removal Action Report (Anchor QEA and Aspect 2014). Three modifications to the scope of work specified in the Work Plan were made with EPA approval based on the observed conditions:

- The organoclay mat and cover in the northeastern portion of the designed mat and cover area was extended to cover sediments exposed by the removal of the solid hydrocarbon material from the intertidal area.
- Manhole A was plugged by means of a concrete ring extending above the ground surface capped with a bolted steel cover.
- Consistent with approvals from the City and pursuant to an access agreement with Penn Plaza Storage LLC, a catch basin draining into the tank containment area was rerouted to a City storm drain line to prevent accumulation of stormwater in the containment area.

Figure 4-2 shows the constructed elements of the 2013 TCRA.

## 4.3 Other Upland Investigations and Remedial Actions

---

This section describes work that has been conducted outside of the ISA (see Section 8.2) that is potentially relevant for characterizing Site and area-wide conditions.

### 4.3.1 *Former SC Fuels Property Investigations and Remedial Actions (1997 to 2007)*

Between 1997 and 2007, various consultants have performed soil and groundwater sampling at the Former SC Fuels Property (Pacific Environmental 1997; Noll 1999 and 2000; GeoEngineers 2002 and 2003; and GeoScience Management 2007), including the following:

- Advancing 13 hand-auger borings, 18 direct-push soil borings, and 15 hollow-stem-auger borings to a maximum depth of 22 feet;
- Installing 15 monitoring wells to a maximum depth of 20 feet;
- Collecting 12 soil confirmation samples during removal of four USTs; and
- Analyzing soil and groundwater samples for TPH, BTEX, and/or lead.

The investigations indicated the presence of TPH and BTEX in soil and groundwater on the Former SC Fuels Property and in the eastern portion of the Pennsylvania Avenue right-of-way. The TPH and BTEX concentrations exceeded Washington State Model Toxics Control Act (MTCA) Method A cleanup levels.

## **4.4 Other Sediment Investigations and Remedial Actions**

---

In addition to the sediment data developed as part of previous investigations and removal actions at the Site, other data sets have been compiled and studies completed within the Port Washington Narrows and Dyes Inlet that may provide information relevant to the RI/FS. Studies identified to date for these areas include the following:

- Chemical testing of sediments:
  - 2008 and 2009 Puget Sound Assessment and Monitoring Program (PSAMP 2005 and 2009) – Spatial/Temporal Monitoring, Central Sound;
  - 1989 to 2013 PSAMP Long-Term/Temporal Monitoring (PSAMP 2005 and 2011a);
  - 2009 PSAMP Urban Waters Initiative, Bainbridge Basin (PSAMP 2005, 2009, and 2011b); and
  - 2009 Ocean Survey Vessel Bold Summer 2008 Survey Data Report (USACE 2009).
- Chemical testing of fish or shellfish tissue:
  - 2010 and 2012 Environmental Investment Project (ENVVEST) (Johnston et al. 2010; Brandenberger et al. 2012 );
  - 2005 and 2007 NOAA Mussel Watch at station SIWP (NOAA 1993, 2006a, 2006b, and 2008); and
  - 2001 303d Ecology clam and crab sampling data (Ecology 2002).
- Studies of surface water quality:
  - An Integrated Watershed and Receiving Water Model for Fecal Coliform Fate and Transport in Sinclair and Dyes Inlets, Puget Sound, Washington (Johnston et al. 2009); and
  - Sinclair and Dyes Inlets Fecal Coliform Total Maximum Daily Load: TMDL and Water Quality Implementation Plan (Lawrence et al. 2012).
- Regional studies of contaminant source inputs to these water bodies:
  - Contaminant Mass Balance for Sinclair and Dyes Inlets, Puget Sound, Washington (Crecelius et al. 2003).



Additional studies may be identified later, during development of the RI/FS Work Plan and/or the implementation of the RI/FS. The evaluation of the above listed sediment and tissue data is discussed further in Section 7.

## 5 Preliminary Conceptual Site Model

This section presents a CSM based on available historical information, the current understanding of the environmental setting, and the findings of previous investigations (see Sections 2, 3, and 4). The CSM is a description of environmental conditions that includes sources of contamination, contaminant fate and transport in Site media, and potential routes of contaminant exposure for human and environmental receptors. A three-dimensional graphical CSM illustrating representative potential historical sources and migration of contaminants at the Site is shown on Figure 5-1. The nature and extent of specific contaminants is described in Section 7. The CSM will be further developed in the RI/FS Work Plan and during the RI and risk assessment as more Site-related information and data are gathered.

### 5.1 Potential Sources of Contamination

---

This section summarizes potential sources of contamination on the Former Gas Works Property and on surrounding properties. The potential sources and locations associated with known and documented operations (both MGP and other) are presented in the following sections; however, this discussion does not include undocumented or currently unknown potential source(s)/source areas, which may be identified through the collection and evaluation of data during the RI.

#### 5.1.1 Former Gas Works Property Sources

Potential sources of contamination on the Former Gas Works Property include historical activities associated with the former gas works, as well as other activities on the Former Gas Works Property but unrelated to gas works operations.

##### 5.1.1.1 Gas Works Operations

The potential primary sources associated with the production of manufactured gas are depicted on Figure 2-3. The area where the gas production process occurred is divided into potential source areas based on the predominant use and subsequent primary potential release mechanisms associated with each area. The primary potential source areas include the following:

- **Coal/Coke Briquettes Area.** As described in Section 2, solid feedstocks (coal and coke briquettes) were transported to the Former Gas Works Property by barge and offloaded and transported over the water, beach, and bluff to a concrete surface storage area in the northwest corner of the Former Gas Works Property. Coke briquettes have been observed on the beach and bluff, suggesting spills during the transport process. Additionally, coal/coke dust may have been swept off the concrete storage slab onto the surrounding ground surface.
- **Tar and Petroleum Transfer Area.** Petroleum products were delivered to the Former Gas Works Property and tar was removed from the Former Gas Works

Property by barge. Petroleum and tar from pipelines along the dock and at the connection to the barges may have been released directly to sediment or surface water. A pipeline presumably ran between the dock and the byproduct storage area to transport tar to the dock, but the location is unknown.

- **Petroleum Storage Area.** Petroleum products were stored in ASTs in the northeastern portion of the Former Gas Works Property. The products reported to have been stored in these tanks include gasoline and diesel fuel oil. Transfer piping presumably ran from the storage tanks to the furnaces, but the exact location of transfer piping is unknown. Petroleum may have been released from tanks and piping to soil at the surface or shallow subsurface in this area.
- **Gas Generation and Purification Area.** The main process area was located in the central portion of the Former Gas Works Property and included the furnaces, scrubber, gas holder, and purifier. The primary potential sources associated with the gas works process consist of spills, drips, and leaks of spent liquids, oils, gas liquor, tar, and tar-water mixtures from aboveground equipment, piping, and storage tanks to the ground surface.
- **Residuals Management Area.** A map of the former plant shows tar wells and a residue cistern to the east of the purifiers. These were likely used for separation of tar-water emulsions prior to resale of the tar. The details of the tar wells and residue cistern are unknown, but they likely extended into the shallow subsurface and may have been either lined or unlined at the base. A second area south of the main plant building was reportedly used for storage and/or separation of tar and tar-water emulsions in a tar pit. Oils and tar may have been released to the surface around these features or the subsurface beneath them.
- **Tar and Light Oil Storage Area.** The southern portion of the Former Gas Works Property was used for the storage of tar and light oil in ASTs. Tar and light oil may have leaked or been spilled onto the ground surface in the vicinity of the ASTs. Finished gas may have contained small amounts of oil that condensed in the distribution piping and were collected in the drip tank. Light oil may have been released to the shallow subsurface soil in the vicinity of the pipes and tank.
- **Former Drainage Line Area.** During the 2010 TCRA, a former drainage line on the Sesko Property that discharged to the Port Washington Narrows was identified. Tar-like hydrocarbons were identified in this drainage line, which was plugged during the 2010 TCRA (see Section 4.2.1). The drainage line is consistent with a former City CSO outfall documented in historical files. Wastewater and associated contaminants may have been discharged from this drainage line during operation of the former gas works.
- **Ravine Fill Area and Shoreline Fill Area.** Historical documents reference the surface disposal of gas works byproducts into the western portion of the Former

Ravine, to the east of the gas generation and purification area, and along the bluff to the north of the gas generation and purification area. Materials that were reportedly placed along the shoreline include ash, cinders, slag, and soot. Materials that were reportedly placed in the Former Ravine include ash, cinders, slag, soot, spent scrubber media (tar-laden wood chips and shavings), and spent purifier filter media (wood chips and/or iron oxide). Approximate areas of potentially gas-works-related fill are shown on Figure 2-3.

#### 5.1.1.2 Other Operations

Other potential primary sources are associated with activities conducted after the shutdown and demolition of the former gas works, or they were conducted in the immediate vicinity of the former gas works. These sources are depicted on Figure 2-4 and summarized as follows:

- **Bulk Petroleum Storage.** Petroleum products were delivered to Lent's at a dock offshore of the Sesko Property and stored in ASTs for distribution by fuel delivery vehicles. Petroleum may have been released from piping and storage tanks to the ground surface and/or the shallow subsurface.
- **Varied Light Industrial Use.** Since the shutdown of the former gas works, the McConkey Property has been used for miscellaneous light industrial activities, including vehicle parking, metals fabrication, and equipment storage. Ecology site inspections in 1992, 1993, and 1994 indicated poor housekeeping practices associated with some of these operations. These operations are potential sources of solvents, metals, and petroleum hydrocarbons, which may have been released to the ground surface as either solids (sandblast grit, paint sludges, etc.) or components of liquids.
- **Equipment Storage and Repair and Debris Filling.** In addition to the bulk petroleum storage described above, activities on the Sesko Property since the shutdown of the former gas works include boat maintenance and storage, automobile salvage, and equipment and debris storage. These activities may be sources of contaminants to soil, sediment, and surface water by direct discharge, dumping, or spills to the ground surface.
- **Other Operations.** Other operations have reportedly included filling of the Former Ravine and shoreline areas, particularly on the Sesko Property. These operations may have included disposal of incinerator refuse, garbage, and ashes; placement of concrete and piping debris; and/or placement of miscellaneous metal, concrete, and fiberglass debris associated with maintenance and salvage of boats and equipment. Fill placed along the shoreline and in the Former Ravine may have included materials that contained hazardous substances. Although the presence of fill material alone does not necessarily represent a contaminant

source, hazardous substances associated with the fill may subsequently migrate to surrounding subsurface soil or groundwater.

#### **5.1.1.3 Stormwater Discharge**

Stormwater discharging to the Port Washington Narrows may contain contaminants and is a potential source of contamination to sediments or surface water. The outfalls that historically or currently capture water at the Former Gas Works Property are the following:

- **Historical City Stormwater/CSO Outfall.** As noted in Section 5.1.1.1, a historical drainage line and outfall were located within and offshore of the Sesko Property. A section of the drainage line on the beach was reportedly removed by the City during installation of a force main in the 1990s. The drainage line was plugged and partially removed as part of the 2010 TCRA (see Section 4.2.1). An upland manhole and storm drainage lines believed to be connected historically to the drainage line were plugged as part of the 2013 TCRA.
- **McConkey Drainage Line.** A small drainage line discharges stormwater from a shallow catch basin on the McConkey Property to the Port Washington Narrows.

#### **5.1.2 Other Operations Sources – Adjacent Properties**

Potential primary sources on adjacent properties include the following:

- **Bulk Petroleum Storage.** Petroleum products were delivered to bulk fuel storage facilities by barge at the Former ARCO Dock, the Former Sesko Dock, and the former SC Fuels Dock and stored in ASTs or USTs for distribution by fuel delivery vehicles. These petroleum storage facilities included the Former ARCO Property located west of the former gas works and the Former SC Fuels Property. Petroleum may have been released from piping and storage tanks to the ground surface and/or the shallow subsurface while these operations were ongoing.
- **Varied Light Industrial Use.** The Penn Plaza Property has been used for miscellaneous light industrial activities, including spray painting, a pipe shop, vehicle parking for a petroleum distributor, truck repair electroplating, metals fabrication, and equipment storage. Ecology site inspections in 1992, 1993, and 1994 indicated poor housekeeping practices associated with some of these activities. These activities are potential sources of solvents, metals, and petroleum hydrocarbons, which may have been released to the ground surface as either solids (sandblast grit, paint sludges, etc.) or components of liquids.

##### **5.1.2.1 Stormwater Discharge**

As described in Section 3.5, a large number of documented stormwater and CSO outfalls are located within the Port Washington Narrows and Dyes Inlet, including the two

outfalls described in Section 5.1.1.3. Other nearby outfalls or discharge lines include the following:

- **Current City Stormwater/CSO Outfall.** An active City stormwater/CSO outfall is located along the Port Washington Narrows, offshore of the end of Pennsylvania Avenue. This outfall is located immediately adjacent to the 2010 TCRA area (Figure 4-2).
- **Drain Line.** A drain line from an oil-water separator on the Former SC Fuels Property discharges to the Port Washington Narrows.

## 5.2 Contaminant Migration and Transformation

---

Contaminants derived from the sources described in Section 5.1 may have been released to soil (surface and shallow subsurface), sediment, and/or surface water. Representative potential releases (e.g., leaks or spills from equipment, tanks, or piping; placement of contaminated fill materials; and discharges from outfalls) are shown conceptually on Figure 5-1. The released contaminants may have migrated from one location to another or from one medium to another. Contaminants may also undergo attenuation or transformation processes within media. The contaminant migration pathways and transformation processes are described in the following subsections.

### 5.2.1 Migration Pathways

Examples of potential contaminant migration pathways between media are shown conceptually on Figures 5.2, 5.3, and 5.4 and include the following:

- Migration of contaminants from surface soil to subsurface soil (e.g., leaching or product migration);
- Contaminant leaching or NAPL migration from soil/NAPL to groundwater;
- Groundwater/NAPL transport within the saturated zone;
- Groundwater discharges to surface water;
- Contaminant partitioning between groundwater and sediments (including sediment porewater);
- Migration of volatile NAPL/soil/groundwater contaminants to air;
- Migration of surface soil contaminants as fugitive dust;
- Release of surface soil contaminants to stormwater;
- Uptake of contaminants by terrestrial or aquatic biota; and
- Migration of contaminated sediments by sediment transport.

Based on the data collected to date (see Section 7), contaminants have been identified in soil, groundwater, and sediment. No Site-specific surface water, air, or tissue data are

available. Contaminant occurrences in these media may be due to direct releases or subsequent migration, for instance:

- Soil contamination may be the result of contaminated fill materials, downward flows of NAPL releases<sup>10</sup> through the subsurface and the coating of soil grains, or sorption of contaminants from other media (e.g., soil vapor, infiltrating stormwater, or groundwater).
- Groundwater contamination may be the result of direct discharge of contaminated aqueous materials and their migration downward through the subsurface and mixing with groundwater, leaching of NAPL in contact with groundwater, or stormwater infiltration of the subsurface, leaching of contaminants from NAPL or contaminated soil, and contaminant mixing with groundwater).
- Contaminants in sediment may be the result of direct releases to surface sediments (e.g., documented discharges from outfalls, undocumented spills, or leaks from dock piping and transfer operations); subsurface migration of contaminated groundwater or NAPL from the uplands, and migration through sediments; or a combination of sources. In particular, two sediment “hot-spot” areas were addressed by the 2010 and 2013 TCRA:
  - The 2010 TCRA addressed a drainpipe that contained residual NAPL and surrounding contaminated sediments, which appeared to be the primary source of contamination in this area. The historical and ongoing contribution to sediment contamination from other potential sources in this area, including groundwater discharge, stormwater runoff, and the City CSO, is unknown.
  - The 2013 TCRA addressed an area of heavy sheen located in shallow subsurface sediments and solid surficial material containing high PAH concentrations. It is likely that the solid surficial material, which would be immobile in the subsurface, was placed at or near its locations; however, the source of the material is unknown. The source of the subsurface sheen is also unknown. During the TCRA investigation, a sheen was observed up to the base of the bluff. However, there are insufficient data to determine whether this contamination is contiguous with contamination in the upland.

---

<sup>10</sup> Liquid releases generally will move downward, through the subsurface by means of gravity, but they may move laterally by preferential migration pathways if a barrier (e.g., low-permeability soils or, for NAPLs that are less dense than water, groundwater) is encountered.

Representative migration pathways, including subsurface migration pathways, are included on Figure 5-1.

### **5.2.2 Transformation Processes**

In addition to contaminant migration pathways, contaminant concentrations in media can be reduced or attenuated by various combinations of natural processes. Examples of such processes include the following:

- Chemical or biological degradation of contaminants in soils, groundwater, sediments;
- Tidally induced mixing of groundwater near the groundwater/surface water interface;
- Natural recovery of marine sediments by burial, mixing, and/or degradation processes; and
- Metabolic transformation or elimination of chemical contaminants from the tissues of upland or aquatic biota.

### **5.2.3 Contaminant Transport and Transformation Data Needs and Collection Strategy**

Additional data are needed to determine to what extent contaminants are migrating or could migrate in the subsurface. Sufficient data should be collected to aid in the assessment of contaminant transport. In particular, the data needs include characterization of the following:

- Soil lithology to identify potential subsurface migration pathways;
- Groundwater parameters governing transport rates and pathways (e.g., gradients and hydraulic conductivity to determine velocity; tidal effects; and salinity);
- Properties and extent of NAPLs in the subsurface;
- Extent of contaminants in environmental media;
- Groundwater chemistry along contaminant flow paths;
- Soil organic carbon content to evaluate leaching and sorption; and
- Natural attenuation parameters.

## **5.3 Exposure Pathways and Receptors**

---

Exposure pathways and receptors that may be most relevant to the RI and risk assessment are summarized on Figures 5-3, 5-4, and 5-5. These figures illustrate how certain human and ecological receptors may use the Site and the impacted media that they could reasonably contact. The information included in this section will be further expanded during development of the RI/FS Work Plan, including a more exhaustive



review of human and fish/wildlife uses of the Site and vicinity and the rationale for focusing the risk assessment activities on the receptors and pathways summarized in Figures 5-3, 5-4, and 5-5.

Figure 5-3 illustrates different exposure pathways that could affect people using the Site or nearby areas. The potential exposure of people to Site-related contaminants of concern (COCs) differs in terms of both how those people use the Site and which areas of the Site are used. (i.e., beach/aquatic areas and upland areas). Some land uses could also change over time. For example, the Site is not zoned for residential land use, but as part of risk assessment activities, it may be prudent to evaluate potential future residential land use to understand the implications of changes in land use or zoning. Similarly, shellfish harvesting in the Port Washington Narrows is restricted due to shellfish harvesting closures unassociated with the former gas works. However, it may be prudent to evaluate potential future shellfish harvesting to understand potential exposures should those shellfish harvesting restrictions be lifted.

Preliminary complete current and future human exposure pathways to contaminated media include dermal contact with and incidental ingestion of soil, inhalation of fugitive dust and vapors, and consumption of fish/shellfish that are potentially contaminated with bioavailable Site-related contaminants. Preliminary incomplete current and future human exposure pathways will be further evaluated as part of the RI. The preliminary human exposure scenarios relevant to the Site include the following:

- Human Use of Beach/Aquatic Site Areas:
  - Recreational Beach Users. The potential for limited recreational beach use exists for individuals residing in proximity to the Site. During recreational use of the beach these individuals may be exposed to Site sediment and surface water.
  - Consumers of Fish/Crab from the Port Washington Narrows. The portions of the Port Washington Narrows adjacent to the Former Gas Works Property currently support the collection and consumption of fish and crabs under WDFW regulations. The Port Washington Narrows is also a Usual and Accustomed area of the Suquamish Tribe. Consumers of fish and crabs may also be exposed through incidental sediment and surface water ingestion during harvesting activities.
  - Consumers of Shellfish at the Site (Currently Restricted by Shellfish Harvesting Closures). The portions of the Port Washington Narrows adjacent to the Former Gas Works Property are currently closed to shellfish harvesting (due to water quality concerns associated with CSOs and other non-Site-related concerns) by Washington State Department of Health; however, exposures associated with shellfish harvesting will be evaluated to understand potential risks should the shellfish harvest

restrictions be lifted. Consumers of shellfish may also be exposed through incidental sediment and surface water ingestion during harvesting activities.

- Beach Construction/Excavation Workers. This scenario relates to workers performing utility upgrades or maintenance or other activities that involve the disturbance of the beach/aquatic areas adjacent to the Former Gas Works Property. Beach construction workers could be exposed to Site surface and subsurface beach sediment.
- Human Use of Upland Site Areas:
  - Occupational Workers. The Former Gas Works Property and the properties in the vicinity are zoned for industrial uses. Occupational workers at the Site could be exposed to Site surface soil and vapor.
  - Upland Construction/Excavation Workers. This scenario relates to workers performing utility upgrades or maintenance or other activities that involve the disturbance of soil at the Former Gas Works Property and the properties in the vicinity. Upland construction workers could be exposed to Site surface and subsurface soils and vapor.
  - Potential Future Residential Users of the Site (Not a Current or Planned Use). The Former Gas Works Property and the properties in the vicinity are zoned for industrial uses; and this is expected to remain the case for the foreseeable future. However, the potential for exposures of future residents may be appropriate to evaluate as part of the risk assessment to understand potential implications should property use be converted to residential. On-site residents could be exposed to Site surface soil and vapor. Although no water supply wells are located on or near the Former Gas Works Property, consumption of groundwater is retained as a potential pathway for screening, pending further evaluation of groundwater beneficial uses.

Preliminary complete aquatic-dependent ecological exposure pathways to contaminated media include direct contact with and ingestion of sediment, porewater, and marine water; and consumption of benthic invertebrates, fish, and other potentially contaminated prey. The risk assessment will include an evaluation of aquatic receptors with differing modes of exposure. Preliminary incomplete aquatic ecological receptors will be further evaluated as part of the RI. Figure 5-4 provides examples of aquatic ecological receptors that are preliminarily identified for further evaluation during the risk assessment based on the current understanding of the Site and consideration of the results of other CERCLA risk assessments performed at nearshore cleanup sites in the region. Exposure pathways relevant to these species are indicated on Figure 5-4 and include the following:

- **Piscivorous Mammals (e.g., Harbor Seals).** The potential for limited exposure exists for piscivorous mammals foraging at the Site. Potentially complete exposures are associated primarily with consumption of aquatic biota, and to a lesser extent with exposure to sediment and surface water.
- **Piscivorous Raptors (e.g., Ospreys).** The potential for limited exposure exists for piscivorous raptors foraging at the Site. Potentially complete exposures are associated primarily with consumption of aquatic biota, and to a lesser extent with exposure to surface water.
- **Shore Birds (e.g., Herons and Sandpipers).** The potential for exposure exists for shore birds residing or foraging at the Site. Potentially complete exposures are associated primarily with consumption of aquatic biota, incidental ingestion of sediment and to a lesser extent with exposure to surface water.
- **Piscivorous Fishes (e.g., Rockfish).** The potential for exposure to Site sediments and surface water exists for piscivorous fishes residing or foraging at the Site.
- **Omnivorous Fishes (e.g., Sculpins).** Omnivorous fishes residing or foraging at the Site may potentially be exposed to Site sediments and surface water.
- **Benthivorous Fishes/Shellfish (e.g., Flatfish, Bivalves, and Crabs).** Benthivorous fish/shellfish residing or foraging at the Site may potentially be exposed to Site sediments and surface water at the Site.
- **Benthic Invertebrates (e.g., Benthic Infauna Community).** Benthic invertebrates residing at the Site may potentially be exposed to site sediments and pore-water.
- **Macrophytes (e.g., Algae and Kelp).** Macrophytes residing at the Site may potentially be exposed to site sediment and surface water.

Data needed to refine the exposure pathways and receptors are identified in Section 9. These data needs include sampling and analysis of upland soils, groundwater, sediments, and biological receptors.

The upland properties at the Site have historically been developed and used for industrial operations. However, portions of these properties include habitat that could be used by terrestrial ecological receptors. These areas primarily include the vegetated areas of the Former Ravine and the bank and the beach. The risk assessment will include an evaluation of terrestrial receptors with differing modes of exposures such as nesting, foraging, residence, and/or presence at the Site. Representative receptors will be selected to evaluate the different exposure pathways. Preliminary incomplete terrestrial ecological receptors will be further evaluated as part of the RI. Figure 5-5 provides examples of terrestrial ecological receptors, which are preliminarily identified for further evaluation during the risk assessment based on the current understanding of the Site and consideration of the results of other CERCLA risk assessments performed at nearshore

cleanup sites in the region. Exposure pathways relevant to these species are indicated on Figure 5-5 and include the following:

- **Avian Predators (e.g., Robins).** The potential for exposure exists for avian predators foraging or nesting at the Site. Primary exposure pathways for these receptors include the consumption of soil invertebrates and incidental ingestion of Site soil.
- **Carnivores (e.g., Coyotes).** The potential for limited exposure exists for carnivores foraging at the Site. Primary exposure pathways for these receptors include the consumption of soil invertebrates and small mammals and incidental ingestion of Site soil.
- **Omnivores (e.g., Raccoons).** The potential for limited exposure exists for omnivores foraging at the Site. Primary exposure pathways for these receptors include the consumption of plants and soil invertebrates and incidental ingestion of Site soil.
- **Herbivores (e.g., Voles).** The potential for exposure exists for herbivores residing at the Site. Primary exposure pathways for these receptors include the consumption of plants and incidental ingestion of Site soil.
- **Insectivores (e.g., Shrews).** The potential for exposure exists for insectivores residing on the Site. Primary exposure pathways for these receptors include the consumption of soil invertebrates and incidental ingestion of Site soil.
- **Upland Vegetation.** The potential for exposure to Site soil exists for plants growing on the Site.
- **Soil Invertebrates.** The potential for exposure to Site soil exists for earthworms and other biota living in Site soil.

## 6 Project Planning

This section identifies initial potential ARARs, PRGs, and RAOs for the purposes of project planning. Potential ARARs are identified to facilitate communications with support agencies, help plan potential field activities, and assist in the identification of RAOs and PRGs. Initial PRGs are identified to help evaluate existing data and assist in the selection of appropriate analytical methods. ARARs, PRGs, and RAOs will be further developed during the RI/FS process. Those ARARs, PRGs, and RAOs that are determined to be applicable to the Site-related decisions may include some, none, or all of those identified in this section. The ARARs, PRGs, and RAOs that are ultimately determined to be applicable to the Site-related decisions will be established in consultation and coordination with key stakeholders and the public during the RI/FS process.

### 6.1 Applicable or Relevant and Appropriate Requirements

---

The project must comply with CERCLA Section 121, which requires remedial actions to achieve ARARs. According to the National Contingency Plan (Code of Federal Regulations, Title 40, Section 300.5 [40 CFR 300.5]), applicable requirements are those cleanup standards, standards of control, and other substantive requirements, criteria, or limitations promulgated under federal environmental or state environmental and facility siting laws that specifically address a hazardous substance, pollutant, contaminant, remedial action, location, or other circumstance identified at a CERCLA site. Appropriate and relevant requirements are cleanup standards, standards of control, and other substantive requirements, criteria, or limitations promulgated under federal environmental or state environmental or facility siting laws that are not applicable to a hazardous substance, pollutant, contaminant, remedial action, location or other circumstances at a CERCLA site, but address problems or situations similar to those encountered at the site that their use is well suited to the particular CERCLA site.

Some federal, state, and local environmental and health agencies may develop criteria, advisories, guidance documents, and proposed standards that are not legally enforceable but contain useful information for selecting cleanup levels or implementing a cleanup remedy. These fall into the category of “to be considered” (TBC) elements. TBCs are not mandatory requirements but may complement the identified ARARs.

ARARs and TBCs potentially relevant to the RI/FS are presented in Tables 6-1 through 6-3 and organized in the following categories:

- Contaminant-specific requirements;
- Location-specific requirements; and
- Performance, design, or other action-specific requirements.

Some ARARs fit neatly into a single category, while others may fall into more than one category. The categories are described as follows:

- Contaminant-specific ARARs are laws and requirements that establish health- or risk-based numerical values or methodologies for developing such values (EPA 1988b). These ARARs are used to establish the acceptable concentration of a contaminant that may remain in or be discharged to the environment. As such, contaminant-specific ARARs are considered in identifying the PRGs. Contaminant-specific ARARs are listed in Table 6-1.
- Location-specific ARARs are requirements that are triggered on the basis of the location of the remedial action to be undertaken (EPA 1988b). Location-specific ARARs may restrict or preclude certain remedial actions or may apply only to certain portions of the Site. Some location-specific ARARs overlap with action-specific ARARs. Location-specific ARARs are listed in Table 6-2.
- Action-specific ARARs are performance, design, or other requirements that may place controls or restrictions on a particular remedial action (EPA 1988b). Action-specific ARARs are typically technology- or activity-based requirements or limitations on actions, and these requirements may include contaminant-specific standards or criteria that must be met as the result of an action. For remedial actions at the Site, these requirements are not necessarily triggered by the presence of specific contaminants in Site media, but rather by the specific actions that occur at the Site. Action-specific ARARs are listed in Table 6-3.

## 6.2 Remedial Action Objectives

---

RAOs consist of goals for protecting human health and the environment that are specific for each potentially contaminated environmental medium (e.g., soil, groundwater, and sediment). RAOs for protection of human receptors typically include both a contaminant level and an exposure route. RAOs for protection of environmental receptors typically seek to preserve or restore a resource and are typically expressed in terms of the medium of interest and target cleanup levels. The preliminary RAOs related to the protection of human health are as follows:

- **Groundwater.** Reduce risk to human health from direct contact with, and consumption of, groundwater contaminated with Site-related COCs to protective levels.
- **Sediment.** Reduce risk to human health from consumption of fish and shellfish containing Site-related COCs to protective levels.
- **Sediment.** Reduce risk to human health from incidental ingestion and/or dermal exposure to Site-related COCs during potential recreational use of the beach areas at the Site to protective levels.
- **Vapor.** Reduce risk to human health from inhalation of vapors from groundwater and/or soils contaminated with Site-related COCs to protective levels.

- **Soils (Surface and Subsurface).** Reduce risk to human health from direct contact with or incidental ingestion of Site-related COCs to protective levels.

The preliminary RAOs related to environmental protection are as follows:

- **Groundwater.** Reduce, to protective levels, risks to ecological receptors from direct contact with and consumption of groundwater contaminated with Site-related COCs, including indirect exposure from consumption of prey exposed to groundwater entering the Port Washington Narrows.
- **Upland Soil.** Reduce, to protective levels, risks to terrestrial wildlife exposed to Site-related COCs through direct contact with and incidental ingestion of Site soil or consumption of soil-dwelling invertebrates.
- **Sediment.** Reduce, to protective levels, risks to aquatic wildlife from exposure to Site-related COCs in surface sediments or in prey species at the Site.
- **Sediment.** Reduce, to protective levels, risks to the benthos from Site-related COCs in surface sediments.

The preliminary RAOs will be developed further throughout the RI/FS process, in consultation with key stakeholders and the public, and may be revised, refined, or replaced.

## 6.3 Preliminary Remediation Goals

---

PRGs are published, generic, and conservative values that consider human health and ecological toxicity using standard exposure parameter values and risk assumptions to estimate protective chemical concentrations. Generic PRGs do not consider Site-specific conditions, exposure pathways, or potential receptors. An exceedance of a general PRG is not an indication of risk but an indication that further evaluation is required to determine risk. As additional information is collected throughout the RI/FS process, the PRGs will be modified to be directly applicable to Site conditions, exposure pathways, and receptors. This section identifies the initial PRGs for the screening of existing soil, groundwater, and sediment data. Initial surface water PRGs have been identified to assist with development of the RI/FS Work Plan; however, no surface water data are available for the Site.

Potential PRGs include numerical values identified in ARARs, peer-reviewed risk-based values, or values identified in other screening benchmark sources. Potential PRGs include values from the following sources:

### ARARs:

- Soil: none available (except for those related to PCBs in the Toxic Substances Control Act);
- Groundwater: maximum contaminant levels (MCLs);

- Surface water: national recommended water quality criteria for human health (organism only) and aquatic life (chronic value); and
- Sediment: Washington State Sediment Management Standards (SMS).

**Peer-reviewed sources:**

- Soil: EPA human health regional screening levels (RSLs) and EPA ecological soil screening levels (EcoSSLs);
- Groundwater: EPA human health RSLs;
- Surface water: none available; and
- Sediment: NOAA effect range-low and effect-range-medium benchmarks (ER-L/ER-M) (Long et al. 1995).

**Other screening benchmark sources:**

- Soil: EPA Region 5 Resource Conservation and Recovery Act (RCRA) EcoSSLs;
- Groundwater: none available;
- Surface water: EPA Region 3 Biological Technical Assistance Group (BTAG) sediment ecological screening benchmarks and EPA Region 5 RCRA ecological surface water screening levels; and
- Sediment: EPA Region 3 BTAG sediment ecological screening benchmarks and EPA Region 5 RCRA sediment ecological screening levels.

Tables 6-4, 6-5, 6-6, and 6-7 summarize the potential PRGs from these sources for each medium (soil, groundwater, sediment, and surface water, respectively) and identify an initial PRG for each contaminant. The initial PRG for a given contaminant was selected as the lowest of the ARARs or peer-reviewed risk-based criteria. If a value from these first two sources is unavailable, the initial PRG was selected as the lowest value in the “other screening benchmark” category. For sediment, the regionally specific SMS value was used. If no SMS value exists for the contaminant, the peer-reviewed NOAA value was used.

Identified initial PRGs include the following:

- **Soil:**
  - EPA RSL – residential,
  - EPA RSL – industrial,
  - EPA EcoSSL – birds,
  - EPA EcoSSL – mammals,
  - EPA EcoSSL – invertebrates,



- EPA EcoSSL – plants, and
- EPA Region 5 RCRA – ecological screening levels for soil.
- **Groundwater:**
  - EPA MCL, and
  - EPA RSL – tap water.
- **Sediment:**
  - Washington State SMS sediment cleanup objective (SCO),
  - NOAA ER-L benchmarks (Long et al. 1995),
  - EPA Region 3 BTAG ecological marine sediment screening benchmarks, and
  - EPA Region 5 RCRA ecological sediment benchmarks.
- **Surface water:**
  - National recommended water quality criteria for aquatic life (EPA 2013a),
  - EPA Region 3 BTAG ecological marine surface water screening benchmarks, and
  - EPA Region 5 RCRA ecological surface water benchmarks.

For soil, two different initial PRGs were identified: one for surface soil (which includes consideration of screening levels for terrestrial ecological receptors) and one for subsurface soil at depths below potential ecological exposures.

## 7 Existing Data and Data Usability

Existing Site characterization data have been reviewed in terms of data usability for the RI/FS. The existing data include data for the Former Gas Works Property and also data for sediments and tissue within the Port Washington Narrows, Dyes Inlet, and nearby portions of Puget Sound.

### 7.1 Data Quality Characterization

---

Data quality review included the definition of minimum data acceptability criteria (MDAC). Relevant guidance was applied, including the following:

- EPA (1988a) Guidance for Conducting Remedial Investigations and Feasibility Studies Under CERCLA;
- EPA (1992) Guidance for Data Usability in Risk Assessment, Part A;
- EPA Contract Laboratory Program Function Guidelines for Data Review (variable dates for different analyte groups); and
- EPA (2009) Guidance for Labeling Externally Validated Laboratory Analytical Data for Superfund Use.

#### 7.1.1 Minimum Data Acceptability Criteria

The MDAC evaluations of historical soil, groundwater, and sediment investigations in the ISA are described for each sampling event in Table 7-1.<sup>11</sup> MDAC evaluations of existing sediment and tissue data are described in Table 7-2. This MDAC review considered the following criteria:

- Work Plan Documentation:
  - Documentation describing the sampling program or event, the methods used, and the parties involved in sample collection must be available.
  - Collection methods must be clearly defined and be adequate for obtaining representative and quantitative information.
  - The purpose of data collection should be available.
- Sample Location and Collection Methods:

---

<sup>11</sup> Investigations conducted under the Order and performed in accordance with EPA-approved Quality Assurance Project Plans (QAPPs) (i.e., the 2013 TCRA) are not included in the MDAC tables.

- Sample coordinates and a qualitative understanding of accuracy (i.e., knowledge of how the location was established or the method by which the coordinates were obtained) must be documented. The coordinate system must be documented.
- Sample collection method and matrix must be documented. For example, a water sample must be identified as to whether it is a surface water, porewater, or groundwater sample and whether it is whole water or filtered (i.e., total versus dissolved fraction). Temporal or spatial compositing and sample volume must be identified. For tissue samples, tissue preparation must be documented.
- Sample depths and, where applicable, start and end depths must be identified.
- Sample storage methods must be documented and consistent with approved methods, including holding time and preservation.
- Sample chain of custody must be documented.
- Laboratory Analysis:
  - Data tables are available (not summary format) with laboratory reports and data validation information.
  - Appropriate detection limits and quantitation limits are achieved so that the data meet the RI data quality objectives (DQOs) for environmental investigations:
    - Detection limits, units for each detection limit, and data qualifiers must be reported. Nondetected results must have the associated detection or reporting limits indicated. Data qualifiers must follow EPA guidance or be defined in documentation.
    - Analytical methods must be documented and acceptable based on EPA guidance.
    - Measurement instruments and calibration procedures must be documented.
    - Toxicity and bioaccumulation test methods must be documented, including any deviations from standard protocols. For risk assessment, test methods must follow standard protocols, including controls and reference tests. Proper documentation to assess methods and statistical treatment must be available. Where possible, statistical results should be recalculated from the raw test data.

- Taxonomic data must be reported to the lowest practicable taxonomic level on a sample-specific basis, with scientific nomenclature. Taxonomic levels must be sufficient to assess relevant metrics for ecological risk assessment, such as feeding guilds or stress-induced compositional changes in the community. Collection methods, sample preservation, and sample preparation methods must be documented.
  - Biological community metric calculations must be defined and documented.
- Quality Control and Data Validation:
  - Documentation of field and laboratory quality control samples (duplicates, blanks) must be present.
  - Analytical chemical data must have been validated and qualified consistent with EPA functional guidelines or EPA Region 10 validation practices.
  - Hard copies of laboratory data reports (e.g., Form 1 or Certificates of Analysis) must be available to verify that electronic or tabulated data were accurately transcribed or transmitted.

### **7.1.2 Data Usability**

Based on the results of the MDAC evaluation and considering the data representativeness for current Site conditions, the data were classified in one of the following data usability (DU) categories:

- **DU-1.** These data meet most or all of the MDAC requirements and are considered reasonably representative of Site conditions. DU-1 data are used in this Scoping Memorandum for COPC and source identification and preliminary evaluations of the nature and extent of contamination.
- **DU-2.** These data meet most of the MDAC requirements but have been superseded by more current or higher quality data for representation of the nature and extent of contamination. DU-2 data are used in this Scoping Memorandum for COPC and source identification.
- **DU-R.** These data do not meet the MDAC requirements and are not used in this Scoping Memorandum.

Of the existing data, the data were classified as follows:

- **DU-1:**
  - All data collected during the 2013 TCRA.

- Soil data, sediment data for analytes other than PAHs, and groundwater data from monitoring wells, collected during the 2008 TBA.
- Soil and groundwater data collected during the 2007 Preliminary Upland Investigation. These data met most of the MDAC criteria but underwent minimal data validation.
- Regional sediment monitoring data collected under the following programs:
  - 2008 and 2009 PSAMP – Spatial/Temporal Monitoring, Central Sound
  - 1989 to 2013 PSAMP Long-Term/Temporal Monitoring
  - 2009 PSAMP Urban Waters Initiative, Bainbridge Basin
  - 2009 Ocean Survey Vessel Bold Summer 2008 Survey
- 2010 and 2012 ENVVEST mussel data
- 2005 and 2007 NOAA Mussel Watch at station SIWP
- 2001 303d Ecology clam and crab sampling data
- **DU-2:**
  - Sediment data collected during the 2010 TCRA and sediment data for PAHs collected during the 2008 TBA. These data met most of the MDAC criteria but have been superseded by more recent data collected in 2013, after the 2010 TCRA was completed.
- **DU-R:**
  - Soil and sediment data collected during the 1995 Ecology Field Inspection. These data had limited documentation, including poorly documented sample locations, no documentation of collection or sample handling methods, and no chain of custody.
  - Groundwater data collected from temporary borings during the 2008 TBA. The samples were not filtered, and the data are not considered representative of groundwater conditions because of potential bias due to sample turbidity.

## 7.2 Existing Site-Related Data

---

This section summarizes the available data collected during previous investigations and removal actions conducted at the Site, relates that data to the CSM, and describes how the existing data might be used in the RI/FS. In this Scoping Memorandum, the existing data are used to develop a preliminary understanding of the nature and extent of contamination that will be further used in the RI/FS Work Plan to identify data gaps and

guide the Site investigation activities. Data identified in Section 7.1 as usable for this purpose, including data from the 2007 Preliminary Upland Investigation, selected data from the 2008 TBA, and data from the 2013 TRCA are presented below for Site media for which data are available (soil, groundwater, and sediment). Data classified as DU-1 (see Section 7.1) are included in the tables and figures in this section. Data summary tables for each medium that include all data classified as DU-1 or DU-2 are provided in Appendix D.

### **7.2.1 Soil Data**

As discussed in Section 4.1, soil samples were collected as part of investigations conducted in 2007, 2008, and 2013. Soil samples were collected and analyzed for TPH, metals, SVOCs (including PAHs), VOCs, and PCBs. Table 7-3 summarizes the number of samples collected for analysis of each constituent and an evaluation of detected concentrations to the initial PRG. Data for metals are also compared to natural background concentrations. The soil analytical data are summarized in tables that are included in Appendix D.

The constituents detected in soil at concentrations above the initial PRGs include the following:

- VOCs, including benzene, ethylbenzene, cis-1,3-dichloropropene, and trans-1,3-dichloropropene;
- PAHs; and
- Metals, including antimony, arsenic, cadmium, chromium, cobalt, copper, lead, manganese, nickel, thallium, vanadium, and zinc.

Other than PAHs, no SVOCs were detected at concentrations above the initial PRGs; however, the reporting limits for a subset of SVOCs exceed the initial PRGs at some locations (Table 7-3 and Appendix D). Practical quantitation limits (PQLs) for COPCs will be identified in the RI/FS Work Plan to determine if lower detection limits are achievable or if the PRGs need to be adjusted.

PCBs were not detected in soil; the reporting limits for PCBs in all samples were less than the initial PRGs (Appendix D).

No initial PRGs were identified for TPH, which is not a CERCLA contaminant of concern. However, in the RI/FS, identifying the nature and extent of different TPH products (e.g., gasoline or diesel) may be helpful in defining contaminant sources. TPH data should be used with caution at sites, such as MGP sites, where non-petroleum hydrocarbon mixtures are present (e.g., coal tar). Therefore, an understanding of the type of product by chromatogram or other forensic analysis is needed to correctly interpret TPH data. For the purposes of this memorandum, TPH distribution was not evaluated but may be evaluated in the RI.

A summary of VOCs, PAHs, and metals detected at concentrations above the initial PRGs is provided in the following subsections by analyte group. The maximum concentration

detected at each boring location and a comparison to the initial PRGs and/or natural background concentrations in surface and subsurface soil is provided for the primary constituents detected at concentrations above the initial PRGs<sup>12</sup> (Figures 7-1 through 7-12). As described in Section 6.2, initial PRGs for surface soil include a consideration of potential terrestrial ecological exposure, whereas initial PRGs for subsurface soil do not. For the purposes of this preliminary evaluation, surface soil is defined as soils from 0 to 10 feet in depth, and subsurface soil is defined as 10 feet in depth or greater.

#### **7.2.1.1 VOCs**

Two BTEX compounds, benzene and ethylbenzene, were detected at concentrations above the initial PRGs. The most frequent detections of benzene at concentrations above the initial PRG occurred at two locations: in surface soil collected at sample locations MW-3, in the vicinity of the former finished gas storage tanks, and SP03, near the edge of the Former Ravine fill area (Figure 7-1). Benzene was not detected in any subsurface soil samples at a concentration above the initial PRG (Figure 7-2).

Two halogenated VOCs, cis-1,3-dichloropropene and trans-1,3-dichloropropene, were detected at concentrations above the initial PRG in one sample. The source of these VOCs is unknown.

BTEX compounds are potentially an indicator of MGP-related releases but may result from other sources (e.g., gasoline-range TPH or industrial solvents). The existing data for BTEX in soil are used in this memorandum to help identify the upland ISA (see Section 8.2.1). The data will also be used in the RI to help assess the nature and extent of contamination. Additional data on the lateral and vertical extent of VOCs in soil are needed to evaluate potential source areas, delineate the extent of contamination, and determine risks to human health and the environment.

#### **7.2.1.2 PAHs**

Figures 7-3 and 7-4 depict the maximum concentrations of naphthalene in surface and subsurface soil, respectively. Figures 7-5 and 7-6 depict the concentrations of total carcinogenic PAHs (cPAHs)<sup>13</sup> in surface and subsurface soil, respectively. The vertical distribution of naphthalene concentrations in soil is illustrated along geologic cross sections A–A', B–B', C–C', and D–D' in Figures 3-4 through 3-7, respectively.

The concentrations of total cPAHs and naphthalene exceeding the initial PRGs were detected at sample locations that correspond to operational areas of the former gas

---

<sup>12</sup> Primary constituents shown on the figures include those detected with the greatest frequency or magnitude above the initial PRGs and natural background concentrations.

<sup>13</sup> Concentrations of total cPAHs are provided in benzo(a)pyrene toxicity equivalent concentrations.

works. In surface soil, the highest concentrations of both total cPAHs and naphthalene were detected at sample location MW-3, advanced in the vicinity of the storage tanks, which held light oil and coal tar (Simonson 1997b). Likewise, the highest concentrations of both total cPAHs and naphthalene in subsurface soil were detected at sample location MW-6, which was advanced at the location of the former gas holder.

Generally, concentrations of naphthalene and cPAHs on the Former Gas Works Property are highest in surface soil and decrease with depth (MW-3 and SP03, for example). However, at MW-6, advanced at the location of the former gas holder, PAH concentrations detected in subsurface soil were much higher than those in surface soil. Because the gas holder was reportedly at least 10 feet deep, this finding may indicate that the gas holder was filled with cleaner soil after it was demolished. Also, the concentrations of PAHs detected in deeper soil were greater than those in shallow soil at well MW-8, located hydraulically downgradient of the former gas works operational area.

The concentrations of total cPAHs exceeding the initial PRG have been detected in soil samples collected between depths of 3 and 40 feet. The highest concentrations of total cPAHs were detected in shallow soil, between the depths of 5 and 12 feet, at well MW-3, well MW-6, and boring SP03 and in deeper soil at a depth of 25 feet at well MW-8.

The presence of cPAHs and naphthalenes is a potential indicator of MGP-related releases.<sup>14</sup> The existing data for PAHs in soil are used in this memorandum to help identify the upland ISA (see Section 8.2.1). The data will also be used in the RI to help assess the nature and extent of contamination. Additional data on the lateral and vertical extent of PAHs in soil are needed to evaluate potential source areas, delineate the extent of contamination, and assess risks to human health and the environment.

#### **7.2.1.3 Metals**

The detectable concentrations or analytical reporting limits for a number of metals exceeded the initial PRGs. However, the concentrations of many of these metals did not exceed the natural background concentrations<sup>15</sup> (Ecology 1994):

- For manganese and antimony, all of the detected concentrations, and most of the reporting limits, are below the background concentrations.<sup>16</sup>

---

<sup>14</sup> Carcinogenic PAHs and naphthalenes can also originate from other sources, including petroleum hydrocarbons or creosote. Forensic analyses, such as PAH fingerprinting, may be useful in the RI to help distinguish and identify potential sources of contamination.

<sup>15</sup> Puget Sound background concentrations of metals were used for screening when available. When not available, Washington State background concentrations were used.

<sup>16</sup> The Puget Sound regional background concentration for antimony has not been researched. The background concentration referenced is based on regional data from the Spokane Basin.



- Cobalt and vanadium were detected in all of the soil samples analyzed for metals, with many concentrations exceeding the initial PRGs; however, the detected concentrations are generally within the range of regional background concentrations.
- Thallium was detected at concentrations above the initial PRGs in most of the soil samples analyzed; a natural background concentration for thallium was not identified for this evaluation.

Detected concentrations of cadmium, lead, and zinc are within the range of regional background concentrations at most sample locations, except for borings MW-5, MW-8, and SP03, which are located at the northeast corner of the Former Gas Works Property in the shoreline and Former Ravine fill areas.

Arsenic, chromium, copper, and nickel were detected at concentrations above the initial PRGs and background concentrations at several locations. Figures 7-7 through 7-12 depict the concentrations of arsenic, copper, and nickel<sup>17</sup> in surface and subsurface soil. Concentrations of these metals in subsurface soil do not exceed the initial PRGs, with the exception of arsenic, which was detected at a concentration in excess of the initial PRG but less than the natural background concentration. Concentrations of arsenic, copper, and nickel in surface soil exceed the initial PRGs and the natural background concentrations at several locations. Arsenic was detected at concentrations above the natural background concentration at two locations: SP03 (Former Ravine fill area) and MW-3 (within the footprint of former gas works operations and the current industrial park). Copper, chromium, and nickel were sporadically detected across the Former Gas Works Property at concentrations above the natural background concentrations, and the maximum concentrations of copper, chromium, and nickel were only slightly greater than their respective background concentrations (62.7 milligrams per kilogram [mg/kg] versus 38 mg/kg for copper; 60.8 mg/kg versus 48 mg/kg for chromium; and 60.9 mg/kg versus 48 mg/kg for nickel). The sources of these exceedances are unclear from the existing data. Possible sources include contaminated fill, historical industrial operations, or natural background variability.

The existing soil data are useful for a preliminary identification of COPCs and provide an initial understanding of metals occurrences in surface and subsurface soil. These data can likely be used in the RI to inform the nature and extent of contamination. Additional data, particularly in surface soils and fill areas, are needed to evaluate potential sources

---

<sup>17</sup> Arsenic, copper, and nickel were mapped in soil because these constituents were also most frequently detected in groundwater at concentrations above the surface water or groundwater initial PRGs.

and delineate the extent of specific metals in soil, including arsenic, cadmium, chromium, copper, lead, nickel, and zinc.

### **7.2.2 Groundwater Data**

As discussed in Section 4.1, groundwater samples were collected as part of the investigations conducted in 2007 and 2008. Groundwater samples were collected and analyzed for petroleum hydrocarbons, metals, SVOCs including PAHs, VOCs, and PCBs. Table 7-4 summarizes the number of samples collected for analysis of each constituent and the results of a comparison of detected concentrations to the screening criteria, which include concentrations protective of groundwater and surface water. The groundwater analytical data are provided in Appendix D.

The constituents detected in groundwater at concentrations above the initial PRGs include the following:

- **Metals:** arsenic, beryllium, chromium (both total and hexavalent), cobalt, copper, lead, manganese, nickel, thallium, vanadium, and zinc;
- **PAHs:** acenaphthene, benzo(g,h,i)perylene, dibenzofuran, phenanthrene, pyrene, naphthalenes, and total cPAHs;
- **Pentachlorophenol (PCP);** and
- **VOCs:** benzene, ethylbenzene, xylenes, 1,2,4-trimethylbenzene, 1,2-dichloroethane, carbon tetrachloride, chloroform, isopropylbenzene, n-hexane, and trichloroethene.

Other than the above-listed constituents, no SVOCs or VOCs were detected at concentrations above the initial PRGs; however, the reporting limits for a subset of SVOCs and VOCs exceed the initial PRGs at a number of locations (Table 7-4 and Appendix D). PCBs were not detected in groundwater; however, the reporting limits for PCBs in all samples were above the potential groundwater initial PRG (Appendix D).

The existing groundwater data are limited, with one sampling event at 10 locations and no groundwater data collected since 2008. The data are useful for the preliminary identification of COPCs, and they indicate where groundwater impacts may be located. These data can be used to support the development of the scope of work for the RI to evaluate the full lateral and vertical extent of COPCs in groundwater. The existing data, which were collected from wells that are still in place, can likely be used for future monitoring and may also be useful in the RI to evaluate long-term trends in groundwater quality.

VOCs, PAHs, PCP, and metals detected at concentrations above the initial PRGs are discussed in the following subsections by analyte group. The concentration detected at each monitoring well and a comparison to the groundwater initial PRGs are provided for

the primary constituents detected at concentrations above the initial PRGs<sup>18</sup> on Figures 7-13 through 7-17.

#### **7.2.2.1 VOCs**

One or more of the BTEX compounds were detected in groundwater samples collected at all of the monitoring wells except for wells MW-1 and SP02. The detected concentrations of benzene in groundwater are depicted on Figure 7-13. The highest concentrations were detected in wells MW-3, MW-6, and MW-8 (in and downgradient of the former gas works operation area).

#### **7.2.2.2 PAHs**

Detected concentrations of total cPAHs were above the initial PRGs in groundwater samples collected from wells MW-3 through MW-8 (Figure 7-14) located on the Former Gas Works Property. The highest concentration of total cPAHs in groundwater was detected at well MW-4. There were no detected concentrations of cPAHs in the groundwater samples collected from wells MP04, SP02, MW-1, and MW-2.

The results for other PAHs are the following:

- Dibenzofuran and pyrene were detected at concentrations above the initial PRGs in the groundwater sample collected from well MW-4; and
- Naphthalenes, including 1-methylnaphthalene and naphthalene, were detected in groundwater samples collected from wells SP02, MP04, MW-3, MW-4, MW-5, MW-6, MW-7, and MW-8 at concentrations exceeding the initial PRGs. The highest concentrations of naphthalene were detected at wells MW-4 and MW-8 (Figure 7-15).

#### **7.2.2.3 Pentachlorophenol**

PCP was detected in groundwater at a concentration exceeding the groundwater and surface water initial PRGs at well MW-8.

#### **7.2.2.4 Metals**

The highest concentrations of metals in groundwater were generally detected at wells MW-3 and MW-4. MW-3 is located in the central portion of the Former Gas Works Property in the vicinity of the former finished gas storage tanks and former metal finishing operations. MW-4 is located within the Former Ravine fill area in the central portion of the Sesko Property. Results for specific metals are the following:

---

<sup>18</sup> Primary constituents shown on the figures include those detected with the greatest frequency or magnitude above the groundwater initial PRGs.

- Arsenic was detected in all of the groundwater samples analyzed, at concentrations ranging from 0.6 to 26 micrograms per liter (µg/L), all of which exceed both the groundwater initial PRG and the surface water initial PRG. Figure 7-16 depicts the concentrations of arsenic in groundwater, which are highest in the central portion of the Former Gas Works Property, at wells MW-3 and MW-4.
- Hexavalent chromium was detected in groundwater samples collected from wells MW-1 and MW-3 through MW-8 at concentrations exceeding the groundwater initial PRG. The concentrations detected in wells MW-5 and MW-8 also exceed the surface water initial PRG. Figure 7-17 depicts the concentrations of hexavalent chromium in groundwater.
- Total chromium and lead were detected in groundwater at concentrations above both the groundwater initial PRGs and the surface water initial PRGs in the groundwater samples collected from wells MW-3 and MW-4.
- Copper and nickel were detected at concentrations exceeding surface water initial PRGs at most of the sample locations; none of the concentrations of copper and nickel exceeds the groundwater initial PRGs. The highest concentrations of copper and nickel were detected in groundwater samples collected from wells MW-3 and MW-4.
- Concentrations of cobalt, manganese, thallium, and vanadium exceeding the groundwater initial PRGs were detected in the groundwater sample collected from well MP04.

Potential sources of metals in groundwater include fill materials and historical industrial operations. More information is needed to determine the source and extent of metals in groundwater.

### **7.2.3 Sediment Data**

Available sediment data for the Site include those collected in 2008 as part of the TBA, in 2010 as part of the 2010 TCRA, and in 2013 as part of the 2013 TCRA. These data sets include the following:

- **2008.** Five surface sediment samples from the beach north of the Former Gas Works Property were analyzed for TPH, VOCs, SVOCs, and metals.
- **2010.** Thirty-two surface sediment samples collected during the 2010 TCRA area were analyzed for VOC and SVOCs.
- **2013.** Thirty-nine surface sediment samples collected during the intertidal sediment sampling program were analyzed for total solids (TS), total organic carbon (TOC), and SVOCs.
- **2013.** Seventeen subsurface sediment samples were collected by direct-push methodology at seven locations. Samples from 4 discrete intervals were analyzed

for VOCs, and samples from 17 subsurface intervals were analyzed for TS, TOC, and SVOCs.

Table 7-5 presents these sediment data and the initial PRGs identified in Section 6.2. Where applicable, reference values are also presented for natural background concentrations of contaminants in Puget Sound sediments or soils.

Figures 7-18 through 7-22 present the measured concentrations of PAHs in beach sediments at the Site. Data are presented on a dry-weight basis for benzo(a)pyrene, total low-molecular-weight PAHs (LPAHs), total high-molecular-weight PAHs (HPAHs), total cPAHs, and total cPAH toxic equivalent (TEQ) concentrations. The highest PAH concentrations were detected within and near the two removal action areas. East and west of these two areas, concentrations decrease rapidly.

#### **7.2.4 Surface Water Data (None)**

No surface water data for the Former Gas Works Property or adjacent areas were identified as of the preparation of this Scoping Memorandum.

#### **7.2.5 Tissue Data (None)**

No tissue data for the Former Gas Works Property or adjacent areas were identified as of the preparation of this Scoping Memorandum.

### **7.3 Existing Data from Other Cleanup Sites**

---

As described in Section 4.3.1, soil and groundwater data collected on the Former SC Fuels Property include TPH, BTEX, and lead. The majority of the soil data were collected prior to and during remedial actions (removal of USTs and surrounding contaminated soil), which occurred in 2002. The most recent groundwater monitoring data are from January 2007. During that sampling event, concentrations of benzene were detected in groundwater at concentrations up to 88 µg/L on the Former SC Fuels Property and up to 49 µg/L in the eastern portion of the Pennsylvania Avenue right-of-way (GeoScience Management 2007). The extent of benzene detected in groundwater (detection limit 1 µg/L) in 2007 is shown on Figure 7-23.

### **7.4 Data for Port Washington Narrows and Dyes Inlet**

---

A number of high-quality sediment and tissue studies were identified for the Port Washington Narrows and Dyes Inlet. The location of sediment and tissue data with measured PAH concentrations is shown on Figure 7-24. These data sets are not used for data screening or COPC evaluation (see Section 8.1) but provide valuable information about conditions in the vicinity of the Site.

### **7.4.1 Sediment Quality Data**

Figures 7-25 and 7-26 present measured concentrations of benzo(a)pyrene and total cPAHs in sediments, respectively. Data are presented on a dry-weight basis. Ecology's current Draft Sediment Cleanup User's Manual II (Ecology 2013) recommends the use of the 90<sup>th</sup> percentile from data sets to evaluate natural and regional background concentrations. The 90<sup>th</sup> percentile concentrations of benzo(a)pyrene and total cPAHs in surface sediment samples collected during the Bold Survey in 2008 (USACE 2009) are approximately 10 micrograms per kilogram [µg/kg] and 50 µg/kg, respectively. Relative to the 90<sup>th</sup> percentile of the 2008 data, the concentrations of benzo(a)pyrene and total cPAHs in sediments from within the Port Washington Narrows, Dyes Inlet, and Sinclair Inlet are elevated. The vast majority of the measured values exceed the 90<sup>th</sup> percentile values from the 2008 data set.

The measured dry-weight concentrations of LPAHs and HPAHs in sediment are presented in Figures 7-27 and 7-28, respectively. The 90<sup>th</sup> percentile concentrations of LPAHs and HPAHs in surface sediment samples collected during the 2008 Bold Survey are 10.9 µg/kg and 75.1 µg/kg, respectively. Relative to the 90<sup>th</sup> percentile of the 2008 data, the LPAH and HPAH concentrations measured in Port Washington Narrows, Dyes Inlet, and Sinclair Inlet show the same magnitude of elevated concentrations as that shown in the cPAH data.

Existing sediment data sets may be used during the RI/FS to document existing sediment quality within nearby portions of the Port Washington Narrows and Dyes Inlet. The data may be useful, along with the data collected during the RI/FS, in evaluating the recontamination potential for Site sediments.

### **7.4.2 Tissue Quality Data**

Figures 7-29 and 7-30 provide a synopsis of available existing PAH testing data for various aquatic organisms. Tested organisms include mussels, clams, and crabs. The data for total cPAHs are presented on both a wet-weight basis (Figure 7-29) and a lipid-normalized basis (Figure 7-30), respectively.

These tissue data sets may be useful during the RI/FS for evaluating how contaminant levels in tissues at the Site (predicted or empirically measured) compare to those in other seafood collected within the region.

### **7.4.3 Water Quality Data**

No current water quality data for chemical contaminants within the Port Washington Narrows have been identified as of the preparation of this Scoping Memorandum.

Several studies have been conducted to assess potential contaminant inputs to Dyes Inlet and adjacent waters (Crecelius et al. 2003). The results of these and other available studies may be used qualitatively for the evaluation of potential nonpoint sources of pollution but will not be relied upon for the baseline risk assessment.

## 8 RI/FS Approach

### 8.1 Contaminants of Potential Concern

---

This section identifies preliminary COPCs based on: (1) contaminants typically associated with the former gas works process (carbureted water gas); (2) contaminants associated with other potential historical sources within the ISA (see Section 8.2); (3) contaminants detected during previous Site investigations; and (4) other EPA contaminants of interest. The COPCs, and ultimately the COCs, that are determined to apply to the Site-related decisions may include some, none, or all of the contaminants identified in this section. The COCs that are ultimately determined to apply to the Site-related decisions will be established on the basis of data and information that is collected as part of the RI/FS process.

Contaminants typically associated with carbureted water-gas manufacturing processes include the following:

- Light aromatic hydrocarbons, such as BTEX compounds;
- Heavier aromatic hydrocarbons, including PAHs;
- Other SVOCs, such as tar acids (e.g., phenol and cresols) and heterocyclic aromatics (e.g., carbazole and dibenzofuran); and
- Cyanide and sulfides associated with spent purifier materials.

COCs identified at a number of other nationwide MGP sites<sup>19</sup> are summarized in Table 8-1. COCs typically associated with MGPs include PAHs, BTEX, and cyanide.

Other historical processes with the potential for releases within the ISA include petroleum transfer and storage, metal fabrication, and vehicle and equipment salvage and repair. Contaminants typically associated with these processes include solvents (VOCs), petroleum hydrocarbons (including BTEX and PAHs), and metals.

Available Site data for soil, groundwater, and sediment are compared to the initial PRGs in Section 7. Contaminants detected at concentrations above the initial PRGs (and natural background concentrations, for naturally occurring metals) include the following:

- VOCs, including benzene, ethylbenzene, xylenes, 1,2,4-trimethylbenzene, cis-1,3-dichloropropene, trans-1,3-dichloropropene, 1,2-dichloroethane, carbon tetrachloride, chloroform, and trichloroethene;

---

<sup>19</sup> Table 8-1 includes representative nationwide MGP sites at which the site conditions are similar and for which cleanup is in progress or has been completed (see Section 8.5).

- SVOCs, including PAHs and PCP; and
- Metals, including antimony, arsenic, cadmium, chromium, cobalt, copper, lead, manganese, nickel, thallium, vanadium, and zinc.

Other EPA contaminants of interest consist of polychlorinated biphenyls (PCBs) and pesticides. PCBs are man-made organic chemicals, manufactured between 1929 and 1979, and used in industrial and commercial applications including electrical, heat transfer, and hydraulic equipment; in paints, plastics and rubber products; and in pigments and dyes. PCBs may still be present in products and materials that were manufactured before 1979, including electrical transformers and capacitors, fluorescent light ballasts, adhesives, oil-based paint and caulking. Pesticides are substances, or mixtures of substances, intended for preventing, destroying, repelling, or mitigating any living organisms (e.g. insects, mice, weeds, fungi, microorganisms) that occur where they are not wanted or that cause damage to crops, humans or other animals. The term pesticide applies to insecticides, herbicides, fungicides, and various other substances used to control pests.

Table 8-2 provides a summary of the preliminary Site COPCs and includes the basis for their inclusion and why they are a concern. The preliminary Site COPCs include the following contaminant groups:

- VOCs, as identified and quantified by EPA Method 8260C.
- SVOCs, including carcinogenic- and non-carcinogenic PAHs, as identified and quantified by EPA Method 8270D/SIM.
- Metals, as identified and quantified by EPA Methods 200.8/6010/6020/7471B.
- PCBs, as identified and quantified by EPA Method 8082.
- Pesticides, as identified and quantified by EPA Method 8081B.
- Cyanide, as identified and quantified by EPA Method 9014.

Specific contaminants are listed on Table 8-2, by contaminant group, if information indicates they are confirmed or suspected to be present at the Site. However, the list of specific contaminants on Table 8-2 is not intended to be an exhaustive and complete list of preliminary Site COPCs. The scope of work for the RI/FS will include collection and analysis of samples from each media for the full standard list of contaminants for each contaminant group. Throughout the RI/FS process, the list of preliminary Site COPCs will be evaluated and revised as data is collected.



## 8.2 Initial Study Area

---

As described in the Statement of Work (SOW) for the AOC, the purpose of the ISA is to focus sampling and analysis in the first phase of the RI/FS.<sup>20</sup> The ISA is not intended to define the Site boundaries.<sup>21</sup>

The SOW anticipates “the ISA will encompass the area of operation of a former manufactured gas plant (MGP)..., including the area where contaminants from the area of operation have come to be located, which includes upland, beach and sediments.” The ISA has been developed following the guidelines established by the SOW. The rationale for the ISA is further explained in Sections 8.2.1 and 8.2.2.

### 8.2.1 Upland Portion of Initial Study Area

The upland portion of the ISA (Figure 8-1) includes the Former Gas Works Property and portions of neighboring properties where gas works operations, including byproduct storage and disposal, are documented or suspected to have occurred. The upland portion of the ISA also includes the northern portion of the Penn Plaza Property where a drip tank was located and the other portion of the Sesko Property where materials from the former gas works process may have been placed in the Former Ravine. The upland portion of the ISA also includes areas where contamination not associated with the former gas works could potentially be commingled with gas works contamination. These non-gas-works operations include the former Lent’s bulk petroleum storage tank farm on the Sesko Property, petroleum pipelines located in the northern portion of the Penn Plaza Property and the Sesko Property, and various light industrial operations on the McConkey and Penn Plaza Properties.

Consistent with the SOW, the proposed ISA encompasses all upland areas where contaminants associated with the former gas works are likely to be located. The existing data collected from areas near the boundaries of the ISA suggest that contamination associated with the former gas works may not extend beyond the ISA. More data are needed to determine if this is the case. The existing data include the results of soil and groundwater sampling from well MW-1 on the Penn Plaza Property, borings MP03 and MP02 within Thompson Drive, borings SP01 and SP02 on the Sesko Property, and explorations associated with the Former SC Fuels Property to the east of the ISA.

The first phase of the RI will characterize the nature and extent of contamination within the ISA and assess the subsurface characteristics that may influence the migration of contaminants. These data will be used to determine where additional investigation may

---

<sup>20</sup> SOW, Sections 1.1 and 3.1.11.

<sup>21</sup> SOW, Section 1.1.

be warranted. Investigations outside of the ISA, if needed, would then be specifically designed and implemented to focus on characterization of identified issues.

### **8.2.2 Sediment Portion of Initial Study Area**

The sediment portion of the proposed ISA (Figure 8-2) comprises intertidal and subtidal areas in the general vicinity of the Former Gas Works Property. The sediment ISA is described as follows:

- Historical potential source areas associated with the former gas works (including the Former Gas Works Dock and the former drainage line) have been included.
- All beach sediments adjacent to the Former Gas Works Property that exhibited elevated PAH concentrations during the 2013 TCRA have been included.
- The offshore boundary of the ISA extends out past midchannel in the Port Washington Narrows, well past the bathymetric low point in the channel. This addresses potential migration pathways associated with groundwater and/or NAPL migration and those associated with potential sediment transport.
- The eastern and western boundaries of the ISA extend between 500 and 1,000 feet in an east-west direction from the Former Gas Works Property, allowing documentation of the potential transport of sediments that may have resulted from the east-west tidal currents occurring within the Port Washington Narrows.

The ISA includes multiple potential sources that are unassociated with historical activities on the Former Gas Works Property: multiple historical petroleum transfer docks, multiple stormwater and CSO outfalls, and the Port Washington Marina.

As part of the RI/FS activities related to sediments, there is a need to understand trends in sediment quality or water quality that may affect either current Site conditions or could potentially result in future recontamination of the Site. Therefore, sampling activities for sediments and surface water will not be exclusively confined to the ISA. Some sampling during the RI/FS will occur outside the sediment portion of the ISA.

## **8.3 Investigation Methods**

---

Implementation of numerous investigation methods may be appropriate to fill the identified data gaps. The methods discussed herein are general approaches that will be considered for use during the RI. The RI/FS Work Plan will present the specific details of the investigation methods and approaches for the RI. The methods will include those that are appropriate to address the specific data needs and have been tested and demonstrated to be effective at similar sites with similar physical characteristics. Previous investigations in the ISA have included hollow-stem auger borings to collect soil samples and install wells to depths of 45 feet. Direct-push soil borings have been used for soil sampling in the upper 16 feet at the adjacent Former SC Fuels Property. A limited-access direct-push drilling rig encountered impenetrable native sediments at depths of 3 to 4 feet. Advancing into the dense native soils beneath the shallow fill material with the

use of direct-push drilling methods will likely be difficult. Impenetrable soil due to debris (e.g., wood or concrete) may also be encountered in fill areas such as the shoreline or the Former Ravine.

Fill soil and shallow native soils will likely be best characterized by means of a combination of exploration excavations (i.e., test pits or trenches using a backhoe or excavator) and direct-push soil borings where excavator access is limited (e.g., beneath buildings). Deeper native soils, in which soil borings are likely to be less effective at reaching the targeted exploration depths, will likely be best characterized by means of drilling methods that use heavier hammers and larger diameter augers (e.g. hollow-stem augers or sonic drills).

The methods for evaluating the presence and degree of contamination will include visual observation and chemical analytical results. Therefore, the collection of sufficient soil samples by means of competent drilling methods will be crucial to the success of the investigation. Likewise, properly constructed and developed monitoring wells will be necessary. Given the observed depth to groundwater during previous investigations, the wells can likely be installed using hollow-stem auger or sonic drilling methods. To minimize carrydown, use of a double-cased drill may be prudent for multilevel well installation in contaminated areas. The evaluation of groundwater flow, groundwater-surface water interaction, near-shore transition zone water, and migration of contaminants in groundwater will be performed with the use of a combination of investigation methods, which may include slug testing at upland monitoring wells and tidal studies.

The risk of vapor intrusion associated with volatile contaminants will be assessed using shallow soil, groundwater, and/or soil gas data. Soil gas may be evaluated using direct-push drilling methods to install shallow, temporary soil gas sampling points.

To meet the specific objectives, additional methods of assessing the presence, nature, and extent of contamination may be considered as the investigation activities progress. For example, the TarGOST® technology, which uses laser-induced fluorescence to delineate coal tar or creosote NAPL, could possibly be used to detect and characterize the extent of NAPL in fill and shallow native soils in areas where coal tar or creosote have been identified by other investigation methods. However, TarGOST® is specifically intended for use in delineating NAPL-contaminated zones and is appropriate only for sites where there is a confirmed presence of coal tar or creosote NAPL. A preliminary understanding of NAPL presence and occurrence in shallow or deeper soils would be needed to determine whether the use of TarGOST® would provide an advantage over more conventional exploration technologies. The use of electrical resistivity imaging may also be tool that could provide information about subsurface conditions at the Site. These and other assessment tools will be evaluated and potentially used during the RI/FS investigation.

## 8.4 Risk Assessment Methodology

---

Consistent with the AOC, a baseline ecological risk assessment (ERA) and a human health risk assessment (HHRA) will be performed to support RI/FS decision-making. The baseline risk assessments will be completed in parallel with the Draft RI Report. The RI/FS Work Plan will include additional details regarding the development of the ERA and HHRA. This section provides an overview of the exposure scenarios likely to be evaluated and the data needed to support those evaluations.

The preliminary CSM (Section 5) describes potentially complete exposure scenarios and pathways for human and ecological receptors. During the RI fieldwork, empirical data will be collected to quantitatively evaluate the level of risk for each receptor listed on Figures 5-3, 5-4, and 5-5. The needs related to risk assessment data, including both planned and contingent data collection needs, are identified in Sections 8.4.1 and 8.4.2.

### 8.4.1 Human Health Risk Assessment

HHRA methodology will be based on national and regional guidance designated by EPA, including, but not limited, to the following:

- Risk Assessment Guidance for Superfund (RAGS), Volume I – Human Health Evaluation Manual (Parts A through F);
- Interim Guidance: Developing Risk Based Clean-up Levels at Resource Conservation and Recovery Act Sites in Region 10 (January 1998);
- The 2011 Exposure Factors Handbook; and
- The 2007 Framework for Selecting and Using Tribal Fish and Shellfish Consumption Rates for Risk-Based Decision Making at CERCLA and RCRA Cleanup Sites in Puget Sound and the Strait of Georgia.

Toxicity data will be developed based on the EPA (2003) hierarchy of human health toxicity values.

Human exposure scenarios will be evaluated in the risk assessment for both beach/aquatic and upland areas of the Site. Scenarios to be evaluated for the beach/aquatic areas include the following:

- **Recreational Beach Use.** The potential for limited recreational beach use exists for individuals residing in proximity to the Site. Potential exposures to Site soil, sediment, and surface water will be addressed under this scenario.
- **Fish/Crab Collection for Consumption.** The portions of the Port Washington Narrows adjacent to the Former Gas Works Property currently support the collection and consumption of fish and crabs under WDFW regulations. In addition to the consumption of fish and crabs, potential exposure to Site sediment and surface water will be addressed under this scenario.

- **Shellfish Collection for Consumption.** The portions of the Port Washington Narrows adjacent to the Former Gas Works Property are currently listed as closed to shellfish harvesting (due to water quality concerns associated with CSOs and non-Site-related concerns) by the Washington State Department of Health; however, exposures associated with shellfish harvesting will be evaluated to understand potential risks should the shellfish harvesting restrictions be lifted. In addition to the consumption of shellfish, potential exposure to Site sediment and surface water will be addressed under this scenario.
- **Beach Construction/Excavation Worker.** Workers performing utility upgrades or maintenance or other activities may disturb sediments in the beach areas adjacent to the Former Gas Works Property. The potential risks resulting from exposures to Site surface and subsurface sediment and fugitive dust and vapor will be addressed under this scenario.

Human health risks associated with the upland areas of the Site will be evaluated as follows:

- **Occupational Worker.** The McConkey and Sesko Properties and the properties in the vicinity are zoned for industrial uses. The potential for limited exposures to Site surface soil and fugitive dust and vapor will be addressed under this scenario.
- **Upland Construction/Excavation Worker.** Workers performing utility upgrades or maintenance or other activities may disturb soils at the Site. The potential risks resulting from exposures to Site surface and subsurface soil and fugitive dust and vapor will be addressed under this scenario.
- **Residential.** The McConkey and Sesko Properties and the properties in the vicinity are zoned for industrial uses. However, exposures to residents will be evaluated to understand potential implications should these properties be converted to residential uses. The potential for limited exposures to Site surface soil and fugitive dust and vapor will be addressed under this scenario. Although no water supply wells are located on or near the former gas works, consumption of groundwater is retained as a pathway for screening, pending further evaluation of groundwater beneficial uses.

Data needed to support the HHRA, including both planned and contingent data collection needs, are the following.

- Definition of the nature and extent of Site-associated COCs in soils, groundwater, and sediment and potential concentrations of Site-associated COCs in surface water. Further testing and data screening are necessary to finalize the list of Site-associated COCs in these media, as necessary to quantify exposure estimates.
- Information regarding potential seafood resources available at and near the Former Gas Works Property. This information is needed to better support the

development of exposure estimates related to the human consumption of seafood. This information includes further compilation of fish and shellfish abundance in the Port Washington Narrows and Dyes Inlet, video surveys of submerged areas within the ISA, and shellfish abundance surveys in beach areas at and near the Former Gas Works Property.

- Estimation of the potential concentration of Site-associated COCs accumulating in seafood at and near the Former Gas Works Property. This evaluation will initially be performed using bulk sediment, porewater, and surface water COC concentrations and bioaccumulation estimates derived from previous studies in the literature. If necessary, Site-specific tissue samples may be collected from selected species to validate and refine the initial estimates. The potential need for this contingent tissue sampling will be evaluated in coordination with EPA. If sampling is determined to be warranted, the methods will be documented in an RI/FS Work Plan Addendum.

Upland risk estimates associated with air quality (dust and vapors) will be initially developed using soil and groundwater data and model-derived estimates of dust and vapor concentrations. If necessary, collection of Site-specific soil vapor data may be conducted. The potential need for this contingent sampling will be evaluated in coordination with EPA. If sampling is determined to be warranted, the methods will be documented in an RI/FS Work Plan Addendum.

### **8.4.2 Ecological Risk Assessment**

ERA methodology will address both terrestrial and aquatic ecological exposures. ERA methodology will be based on EPA guidance, including, but not limited to, the following:

- Ecological Risk Assessment for Superfund: Process for Designing and Conducting Ecological Risk Assessments, Interim Final, June 1997;
- Guidelines for Ecological Risk Assessment, 1998; relevant and appropriate updated EPA guidance material (e.g., EPA's Eco Updates); and
- EPA Region 10 Supplemental Ecological Risk Assessment Guidance for Superfund, 1997.

Toxicity data will be developed according to EPA guidance (e.g., EcoSSLs) and databases (e.g., ECOTOX), peer-reviewed scientific literature, and recent EPA-approved risk assessments.

Ecological exposure scenarios will be evaluated in the risk assessment for both aquatic and terrestrial ecological exposures. Terrestrial exposures to be evaluated include the following:

- **Avian Predator (e.g., Robins).** The potential for exposure exists for individuals foraging or nesting on the Site. Potential exposures to Site soil, terrestrial biota, and on-site water will be addressed under this scenario.
- **Carnivore (e.g., Coyotes).** The potential for limited exposure exists for individuals foraging on the Site. Potential exposures to Site soil, terrestrial biota, and on-site water will be addressed under this scenario.
- **Omnivore (e.g., Raccoons).** The potential for limited exposure exists for individuals foraging on the Site. Potential exposures to Site soil, plants and terrestrial biota, and on-site water will be addressed under this scenario.
- **Herbivore (e.g., Voles).** The potential for exposure exists for individuals residing on the Site. Potential exposures to Site soil, plants, and on-site water will be addressed under this scenario.
- **Insectivore (e.g., Shrews).** The potential for exposure exists for individuals residing on the Site. Potential exposures to Site soil, terrestrial biota, and on-site water will be addressed under this scenario.
- **Upland Vegetation.** The potential for exposure exists for plants growing on the Site. Potential exposures to Site soil will be addressed under this scenario.
- **Soil Invertebrate.** The potential for exposure exists for earthworms and other biota living in Site soil and will be addressed under this scenario.

The aquatic-dependent ecological exposure scenarios and key assumptions will include the following:

- **Piscivorous Mammal (e.g., Harbor Seals).** The potential for limited exposure exists for individuals foraging at the Site. Potential exposures to Site sediment, surface water, and aquatic biota will be addressed under this scenario.
- **Piscivorous Raptor (e.g., Ospreys).** The potential for limited exposure exists for individuals foraging at the Site. Potential exposures to Site surface water and aquatic biota will be addressed under this scenario.
- **Shore Birds (e.g., Herons and Sandpipers).** The potential for exposure exists for individuals residing or foraging at the Site. Potential exposures to Site sediment, surface water, and aquatic biota will be addressed under this scenario.
- **Piscivorous Fishes (e.g., Rockfish).** The potential for exposure exists for individuals residing or foraging at the Site. Potential exposures to Site sediment porewater, surface water, and aquatic biota will be addressed under this scenario.
- **Omnivorous Fishes (e.g., Sculpins).** The potential for exposure exists for individuals residing or foraging at the Site. Potential exposures to Site sediment

porewater, surface water, and aquatic biota will be addressed under this scenario.

- **Benthivorous Fishes/Shellfish (e.g., Flatfish, Bivalves, and Crabs).** The potential for exposure exists for individuals residing or foraging at the Site. Potential exposures to Site sediment, porewater, surface water, and aquatic biota will be addressed under this scenario.
- **Benthic Invertebrates (e.g., Benthic Infauna Community).** The potential for exposure exists for individuals residing at the Site. Potential exposures to Site sediment and sediment porewater will be addressed under this scenario.
- **Macrophytes (e.g., Algae and Kelp).** The potential for exposure exists for individuals residing at the Site. Potential exposures to Site sediment, sediment porewater, and surface water will be addressed under this scenario.

Toxicity data will be developed according to EPA guidance (e.g., EcoSSLs) and databases (e.g., Ecotox), peer-reviewed scientific literature, and recent EPA-approved risk assessments.

Data needed to support the ERA, including both planned and contingent data needs, are the following:

- Definition of the nature and extent of Site-associated COCs in soils and sediment and potential concentrations of Site-associated COCs in surface water. Further testing and data screening are necessary to finalize the list of Site-associated COCs in these media, as necessary to quantify exposure estimates.
- Information regarding potential fish and wildlife resources available at and near the former gas works. This information is needed to better support the development of exposure estimates for the ERA. This information includes further compilation of fish and shellfish abundance in the Port Washington Narrows and Dyes Inlet, video surveys of submerged areas within the ISA, and shellfish abundance surveys in beach areas at and near the former gas works.
- Estimation of the potential concentration of Site-associated COCs accumulating in aquatic organisms at and near the former gas works. This evaluation will initially be performed using bulk sediment, porewater, and surface water COC concentrations and bioaccumulation estimates derived from previous studies in the literature. If necessary, Site-specific tissue samples may be collected from selected species to validate and refine the initial estimates. The potential need for this contingent tissue sampling will be evaluated in coordination with EPA. If sampling is determined to be warranted, the methods will be documented in an RI/FS Work Plan Addendum.



## 8.5 Potential Remedial Approaches

---

An understanding of potential remedial approaches that may be implemented at the Site is helpful during the scoping process to begin identifying data gaps, particularly for data needed to evaluate particular remedial technologies. Data gaps related to remedial technologies principally include site characterization data but may include bench- or pilot-testing of potential technologies if a need is identified during the RI/FS process.

This section describes potential remedial technologies and identifies remedial approaches that have been used at similar sites. Specific data needs for developing and evaluating potential remedial approaches will be described in the RI/FS Work Plan.

### 8.5.1 Remedial Technologies

Site remediation to achieve RAOs typically occurs by implementation of a combination of remedial technologies. Depending on the Site-specific circumstances, the use of remedial technologies may result in the complete elimination or destruction of hazardous substances at the Site, the reduction of hazardous substances at the Site, the reduction or elimination of migrating hazardous substances at the Site, or some combination of these effects. These technologies may be used in combination with engineering controls (e.g., barriers such as fences or caps) or institutional controls (i.e., non-engineered controls such as land use restrictions) when hazardous wastes remain at the Site.

Remedial technologies are often categorized by the following general response actions:

- **Monitored Natural Attenuation.** Natural attenuation is the reduction of contaminant concentrations at the point of exposure over time by means of natural processes, such as sedimentation, sorption, dispersion, and/or biodegradation. Monitoring documents that the processes are occurring at the desired rates. For sediment, this general response action is referred to as monitored natural recovery.
- **In Situ Containment.** *In situ* containment involves confining hazardous substances in place by the placement of physical barriers or hydraulic controls. Containment technologies can be designed to prevent contact with and/or migration of hazardous substances.
- **In Situ Treatment.** *In situ* treatment technologies can potentially reduce the concentration, mobility, and/or toxicity of COCs.
- **Removal.** Contaminated materials can be physically removed from the Site and treated and/or disposed of at either an on-site or an off-site permitted disposal facility.
- **Ex Situ Treatment.** *Ex situ* treatment technologies destroy or immobilize contaminants in media that have been removed from the subsurface.

- **Disposal.** Disposal technologies include the placement of contaminated solid media in on-site or off-site landfills or the discharge of contaminated water to a publicly owned treatment works.

Preliminary lists of potential remedial technologies for NAPL, soil, groundwater, and sediment at the Site are provided in Tables 8-3 through 8-6.

### **8.5.2 Remedial Approaches at Other MGP Sites**

Hundreds of MGP sites around the country have been through or are undergoing an RI/FS and cleanup action. Table 8-1 identifies remedial approaches that have been fully or partially implemented at MGP sites with characteristics (e.g., geology and presence of adjacent surface water bodies) that are similar to the Bremerton Gas Works Site. Common actions have included combinations of removal with off-site disposal or on-site treatment, solidification/stabilization, and institutional and engineering controls. Other technologies have included pump-and-treat, bioremediation, *in situ* chemical oxidation, barriers, and NAPL collection.

## 9 Summary and Data Gaps

Tables 9-1 and 9-2 summarize the principal data needs for the RI/FS that were defined during the initial scoping process.

Table 9-1 presents the data needs relating to the upland areas of the Site, including the data needed to support the risk assessment and FS activities for these areas. Table 9-2 presents the data needs for the beach and aquatic areas of the Site.

Most data gaps are to be filled during a single phase of field investigations. Potential investigation methods are discussed in Section 8.3. Specific proposed sampling methods and target locations will be defined in the RI/FS Work Plan. The anticipated sequence of field activities for upland and sediment areas will be defined in the RI/FS Work Plan but is expected to include the following:

- **Upland investigations:**
  - Complete ground-penetrating radar and utility locating.
  - Conduct sampling of soils and fill material using direct-push borings, angled borings, test pits, trenches, and hand augers.
  - Characterize deep lithology and soil quality using deep borings.
  - Complete selected borings as monitoring wells.
  - Characterize Site hydrogeology, including performance of slug tests and a tidal study.
  - Conduct quarterly groundwater monitoring.
- **Sediment investigation sequencing:**
  - Conduct video surveys to identify substrate, habitat characteristics, and presence/abundance of aquatic resources near the Site.
  - Conduct beach surveys to evaluate the distribution of shellfish and other resources within and near the beach areas adjacent to the Former Gas Works Property.
  - Sample and analyze surface sediments within the ISA to define the nature and extent of Site-related COCs. A subset of samples will be analyzed for PAHs in porewater to evaluate bioavailability of these contaminants.
  - Sample and analyze surface sediments at selected locations beyond the ISA to supplement available data regarding sediment quality and potential recontamination sources within the Port Washington Narrows.

- Sample and analyze surface water at selected Site and background locations, including multiple sampling events to assess potential variability in surface water concentrations.
- Collect subsurface sediment core samples from the beach and subtidal areas sloping down into the Port Washington Narrows to evaluate the vertical distribution of Site-related COCs (including the potential presence of NAPL and hydrocarbon sheen) in subsurface sediments.
- Monitor near-bottom tidal currents within aquatic areas of the Site to assist in the evaluation of sediment stability.

After completion of the initial field program and consultation with EPA, some additional work may or may not be required to address contingent activities or to fully define the nature and extent of contamination at the Site. If applicable, these contingent or follow-up activities will be defined in an RI/FS Work Plan Addendum. Examples of work that might be defined as part of the RI/FS Work Plan Addendum include the following:

- Potential “step-out” sampling in the upland or sediment areas of the Site (if needed);
- Contingent sediment bioassay and/or seafood tissue testing if determined necessary for completion of the risk assessment; and
- Contingent sediment geochronology testing if determined necessary to support the evaluation of sediment stability and recovery processes.

Completion of treatability testing is not expected to be required to support the FS. However, this potential need will also be revisited after completion of the initial field program.

Preparation of the RI, risk assessment, and FS reports will be conducted in a manner that is consistent with the schedule requirements in the AOC.

## 10 References

- Anchor QEA, 2011, Final Completion Report: Former Bremerton MGP Site, Incident Action and Time Critical Removal Action, Prepared for U.S. Coast Guard Sector Puget Sound Incident Management Division on behalf of Cascade Natural Gas Corporation, January 2011.
- Anchor QEA, LLC and Aspect Consulting, LLC (Anchor QEA and Aspect Consulting), 2010, Final Work Plan: Former Bremerton MGP Site, Incident Action and Time Critical Removal Action, Prepared for U.S. Coast Guard Sector Puget Sound Incident Management Division on behalf of Cascade Natural Gas Corporation, November 4, 2010.
- Anchor QEA and Aspect Consulting, 2013a, Removal Evaluation Work Plan, June 2013.
- Anchor QEA and Aspect Consulting, 2013b, Removal Action Work Plan, September 2013.
- Anchor QEA and Aspect Consulting, 2013c, Final Removal Evaluation Report, December 2013.
- Anchor QEA and Aspect Consulting, 2014, Time-Critical Removal Action Report, April 2014.
- Brandenberger J.M., C.R. Suslick, L.J. Kuo, and R.K. Johnston, 2012, Ambient Monitoring for Sinclair and Dyes Inlets, Puget Sound, Washington: Chemical Analyses for 2012 Regional Mussel Watch, Prepared for the U.S. Department of Energy, PNNL-21862, September 2012.
- Bremerton Sun*, 1972, Cascade's Old Manufactured Gas Plant in Bremerton Sold at Auction, Denise Kalette, *Bremerton Sun*.
- CH2MHill, 1982, Overflow 10A Site Plan and Details, March 1982.
- Clapp, Melvin, 1997, John West Notes Regarding Conversation with Melvin C. Clapp, April 21, 1997.
- Crecelius, E.A., R.K. Johnston, J. Leather, J. Guerrero, M.C. Miller, and J.M. Brandenberger, 2003, "Contaminant Mass Balance for Sinclair and Dyes Inlets, Puget Sound, Washington," In 2003 Georgia Basin/Puget Sound Research Conference Proceedings, Vancouver, BC, March 31–April 3, 2003, ed. TW Droscher and DA Fraser, Puget Sound Action Team, Olympia, WA.
- Ecology & Environment, Inc. (E&E), 2008, Final Bremerton Gasworks Targeted Brownfields Assessment Sampling and Quality Assurance Project Plan, Prepared by E&E for EPA, March 5, 2008.

- Ecology & Environment, Inc. (E&E), 2009, Final Bremerton Gasworks Targeted Brownfields Assessment Report, Prepared by E&E for EPA, August 2009.
- GeoEngineers, 2002, Delineation Assessment Report, Former Tosco/Unocal Bulk Plant No. 1783, Prepared by GeoEngineers, Inc. for Tosco Corporation, October 8, 2002.
- GeoEngineers, 2003, Underground Storage Tank Removal Report, Former Tosco/Unocal Bulk Plant 1783, May 27, 2003.
- GeoEngineers, 2007a, Preliminary Upland Assessment Work Plan, McConkey/Sesko Site, June 1, 2007.
- GeoEngineers, 2007b, Preliminary Upland Assessment Report, McConkey/Sesko Brownfield Site, Prepared by GeoEngineers, Inc., for the City of Bremerton, October 26, 2007.
- GeoScience Management, Inc., 2007, Groundwater Monitoring Results for January 2007, SC Fuels Bulk Terminal Property, February 15, 2007.
- Hart Crowser, 2007, Historical Characterization and Data Gaps, Old Bremerton Gasworks Property, Prepared by Hart Crowser for Washington State Department of Ecology, May 2, 2007.
- Hatheway, A., 2012, Remediation of Former Manufactured Gas Plants and Other Coal-Tar Sites, CRC Press, 2012.
- Johnston, R.K., Wang, P.F., Loy, E.C., Blake, A.C., Richter, K.E., Brand, M.C., Skahill, B.E., May, C.W., Cullinan, V., Choi, W., Whitney, V.S., Leisle, D.E., and Beckwith, B. 2009, "An Integrated Watershed and Receiving Water Model for Fecal Coliform Fate and Transport in Sinclair and Dyes Inlets, Puget Sound, Washington," Space and Naval Warfare Systems Center, Technical Report 1977, Dec. 2, 2009.
- Johnston, R.K., G.H. Rosen, J.M. Brandenberger, J.M. Wright, E. Mollerstuen, J. Young, and T. Tompkins, 2010, Sampling and Analysis Plan for Ambient Monitoring and Toxicity Testing for Sinclair and Dyes Inlets, Puget Sound, Washington, Prepared for Project ENVVEST, Puget Sound Naval Shipyard & Intermediate Maintenance Facility, Bremerton, Washington, Revised September 18, 2010.
- Judd, Ralph, 2014, Summary of Interviews with Mr. Ralph Judd, Bremerton Gas Works Site, March 2014.
- Lawrence, S., Roberts, M., Erickson, K., 2012, Sinclair and Dyes Inlets Fecal Coliform Total Maximum Daily Load: TMDL and Water Quality Implementation Plan, Washington State Department of Ecology, rev. June 2012, Publication No. 11-10-051.

- Long, E.R., MacDonald, D.D., Smith, S.L., and Calder, F.D. 1995, Incidence of Adverse Biological Effects within Ranges of Chemical Concentrations in Marine and Estuarine Sediments, *Environmental Management*, 19, 81–97.
- Mustafa, Hong & Associates, Inc. (MH&A), 1982, Schedule A Plan and Profile West Bremerton Gravity Pressure Pipeline Sta.9+50 to Sta. 19+63, September 1982.
- National Oceanic and Atmospheric Administration (NOAA), 1993, Sampling and Analytical Methods of the National Status and Trends Program National Benthic Surveillance and Mussel Watch Projects 1984-1992, Volumes I through IV, NOAA Technical Memorandum NOS ORCA 71, G. G. Lauenstein and A. Y. Cantillo (Editors).
- National Oceanic and Atmospheric Administration (NOAA), 2006a, Kimbrough, K. L., and G. G. Lauenstein (Editors), 2006, Major and Trace Element Analytical Methods of the National Status and Trends Program: 2000-2006, Silver Spring, MD, NOAA Technical Memorandum NOS NCCOS 29, 19 pp.
- National Oceanic and Atmospheric Administration (NOAA), 2006b, Kimbrough, K. L., G. G. Lauenstein, and W. E. Johnson (Editors), 2006, Organic Contaminant Analytical Methods of the National Status and Trends Program: Update 2000-2006, NOAA Technical Memorandum NOS NCCOS 30, 137 pp.
- National Oceanic and Atmospheric Administration (NOAA), 2008, Kimbrough, K. L., W. E. Johnson, G. G. Lauenstein, J. D. Christensen, and D. A. Apeti, An Assessment of Two Decades of Contaminant Monitoring in the Nation's Coastal Zone, Silver Spring, MD, NOAA Technical Memorandum NOS NCCOS 74, 105 pp.
- Noll Environmental, Inc. (Noll), 1999, Report Submittal, Summary of Supplemental Site Assessment Activities, Former Tosco Bulk Plant No. 1783, May 25, 1999.
- Noll Environmental, Inc. (Noll), 2000, Additional Soil Sampling and Groundwater Monitoring Well Installations, Pacific Northwest Energy Company Bulk Plant No. 1783, June 5, 2000.
- Pacific Environmental Group, Inc. (Pacific Environmental), 1997, Soil Investigation, Pacific Coast Energy Company Facility, October 15, 1997.
- Perry, Fred, 2002. Bremerton & Puget Sound Navy Yard, 2002, p. 166.
- Puget Sound Assessment and Monitoring Program, (PSAMP), 2005, Temporal Monitoring of Puget Sound Sediments: Results of the Puget Sound Ambient Monitoring Program, 1989-2000, July 2005, Publication No. 05-03-016.
- Puget Sound Assessment and Monitoring Program, (PSAMP), 2009, Quality Assurance Project Plan, The Puget Sound Assessment and Monitoring Program: Sediment Monitoring Component, Publication No. 09-03-121, August 2009.

- Puget Sound Assessment and Monitoring Program, (PSAMP), 2011a, Addendum to Quality Assurance Project Plan, The Puget Sound Assessment and Monitoring Program: Sediment Monitoring Component, Publication No. 09-03-121-Addendum 2, August 2010.
- Puget Sound Assessment and Monitoring Program, (PSAMP), 2011b, Addendum to Quality Assurance Project Plan, The Puget Sound Assessment and Monitoring Program/Urban Waters Initiative: Sediment Monitoring in the San Juan Islands and Port Gardner/Everett Harbor, Publication No. 09-03-121-Addendum 3, December 2011.
- Simonson, Svavi, 1997a. Linda Baker Notes from Meeting at Site, October 7, 1997.
- Simonson, Svavi, 1997b. Video Deposition of Svavi Simonson (written transcript of videotape/audiotape), November 24, 1997.
- Suquamish Tribe, 2011, Letter providing additional information on the Bremerton Gasworks Site, Bremerton Washington. Dated July 27, 2011.
- Suquamish Tribe, 2014, Comments on August 1, 2014 Draft Scoping Memorandum – Bremerton Gasworks Site, Suquamish Tribe, Comments dated September 12, 2014.
- Suttles, Wayne, and Barbara Lane, 1990. Southern Coast Salish. In *Northwest Coast, Handbook of North American Indians, Vol. 7*, edited by W. Suttles. Washington, D.C.: Smithsonian Institution, 485-502.
- TechLaw, Inc. (TechLaw) 2006, Old Bremerton Gas Works Site, McConkey Properties Targeted Brownfield Assessment. Prepared by TechLaw, Inc. for EPA, November 10, 2006.
- Thorson, Robert M., 1980. Ice-sheet Glaciation of the Puget Lowland, Washington, During the Vashon Stade (late Pleistocene). *Quaternary Research* 13:303-312.
- Treaty of Point Elliott, 1855. Electronic document available from: <http://www.washington.edu/diversity/files/2013/03/treaty-point-elliott.pdf>.
- Tymstra, S., 1942, An Investigation of the Western Gas Company of Washington, Bremerton, Washington, Sybren Tymstra, University of Washington, 1942.
- U.S. Army Corps of Engineers (USACE), , 2009, OSV Bold Summer 2008 Survey Data Report, Final, June 25, 2009, Seattle District, Dredged Material Management Program (DMMP) Prepared by: the U.S. Environmental Protection Agency Region 10, Washington State Department of Natural Resources, and Washington State Department of Ecology.



- U.S. Environmental Protection Agency (EPA), 1988a, Guidance for Conducting Remedial Investigations and Feasibility Studies under CERCLA, U. S. Environmental Protection Agency, Office of Emergency and Remedial Response, Washington, DC, PE89-184626, EPA/540/G-89/004, OSWER Directive 9355.3-01, October 1988.
- U.S. Environmental Protection Agency (EPA), 1988b, CERCLA Compliance with Other Laws Manual: Interim Final, U. S. Environmental Protection Agency, Office of Emergency and Remedial Response, Washington DC, EPA/540/G-89/006, OSWER Directive 9234.1-01, August 1988.
- U.S. Environmental Protection Agency (EPA), 1992, Guidance for Data Usability in Risk Assessment (Part A), U.S. Environmental Protection Agency, Office of Emergency and Remedial Response, Publication 9285.7-09A, Final, April 1992.
- U.S. Environmental Protection Agency (EPA), 2003, EPA Region 5 Resource Conservation Recovery Act (RCRA) Ecological Screening Levels, August 22, 2003.
- U.S. Environmental Protection Agency (EPA), 2006, EPA Region 3 Biological Technical Assistance Group (BTAG) Screening Benchmarks, Marine Sediment Benchmarks, July 2006.
- U.S. Environmental Protection Agency (EPA), 2009, Guidance for Labeling Externally Validated Laboratory Analytical Data for Superfund Use, U.S. Environmental Protection Agency, Office of Solid Waste and Emergency Response, OSWER No. 9200.1-85/ EPA 540-R-08-005, January 13, 2009.
- U.S. Environmental Protection Agency (EPA), 2013a, National Recommended Water Quality Criteria, Updated August 22, 2013, Available online from: <http://water.epa.gov/scitech/swguidance/standards/criteria/current/index.cfm#altable>.
- U.S. Environmental Protection Agency (EPA), 2013b, Action Memorandum for a Time-Critical Removal Action at the Bremerton Gas Works Site, US EPA Region 10, September 30, 2013.
- Washington Department of Natural Resources (DNR), 1968. Inspector's Report, Application No. HA 2071, June 24, 1968.
- Washington State Department of Ecology (Ecology), 1994, Natural Background Soil Metals Concentrations in Washington State, Toxics Cleanup Program, Publication #94-115, October 1994.
- Washington State Department of Ecology (Ecology), 1995, Initial Investigation Inspection, Sesko Property, March 29, 1995.

Washington State Department of Ecology (Ecology), 2002, Results of Sampling to Verify 303(d) Listings for Chemical Contaminants in Shellfish from Dyes Inlet and Port Washington Narrows, March 2002, Publication No. 02-03-011.

Washington State Department of Ecology (Ecology), 2013, *Draft Sediment Cleanup User's Manual II*. Publication no. 12-09-057. December 2013.

Western Regional Climate Center (WRCC), 2014, accessed online at:  
<http://www.wrcc.dri.edu>, May 12, 2014.

White, E., 1998, John West Notes Regarding Conversation with Ed White. January 26, 1998.

# TABLES

**Table 3-1 - Monitoring Well Construction Information and Groundwater Elevation Measurements**

Bremerton Gas Works Site  
Bremerton, Washington

| Well Identification | Installed By | Date Installed | Surface Elevation<br>(Datum Unknown)  | Total Boring Depth<br>(Feet) | Depth to Top of<br>Screen (Feet) | Depth to Bottom<br>of Screen (Feet) | Depth to Water<br>(feet below TOC) | Groundwater Elevation<br>(feet NAVD88) |
|---------------------|--------------|----------------|---------------------------------------|------------------------------|----------------------------------|-------------------------------------|------------------------------------|----------------------------------------|
|                     |              |                |                                       |                              |                                  |                                     | 1-Jun-07                           | 1-Jun-07                               |
| MP-04               | E&E          | 5/13/2008      | 12.38                                 | 40                           | 30                               | 40                                  | --                                 | --                                     |
| SP-02               | E&E          | 5/12/2008      | 10.44                                 | 35                           | 25                               | 35                                  | --                                 | --                                     |
|                     |              |                | Surface Elevation in<br>feet (NAVD88) |                              |                                  |                                     |                                    |                                        |
| MW-1                | GeoEngineers | 5/21/2007      | 45.03                                 | 46.5                         | 30                               | 45                                  | 34.68                              | 10.35                                  |
| MW-2                | GeoEngineers | 5/21/2007      | 42.54                                 | 46.5                         | 30                               | 45                                  | 35.25                              | 7.29                                   |
| MW-3                | GeoEngineers | 5/22/2007      | 39.1                                  | 46.5                         | 30                               | 45                                  | 32.9                               | 6.2                                    |
| MW-4                | GeoEngineers | 5/23/2007      | 35.2                                  | 41.5                         | 20                               | 40                                  | 29.32                              | 5.88                                   |
| MW-5                | GeoEngineers | 5/24/2007      | 18.51                                 | 21.5                         | 5                                | 20                                  | 15.21                              | 3.3                                    |
| MW-6                | GeoEngineers | 5/22/2007      | 34.95                                 | 36.5                         | 15                               | 35                                  | 30.2                               | 4.75                                   |
| MW-7                | GeoEngineers | 5/23/2007      | 33.24                                 | 36.5                         | 15                               | 35                                  | 30.21                              | 3.03                                   |
| MW-8                | GeoEngineers | 5/22/2007      | 35.56                                 | 41.5                         | 20                               | 40                                  | 32.64                              | 2.92                                   |

Notes:

-- = not measured

E&E = Ecology and Environment

NAVD88 = North American Vertical Datum of 1988

TOC = top of casing

**Table 3-1**

Final Scoping Memorandum

Page 1 of 1

**Table 6-1 – Potential ARARs, Contaminant-Specific**

Bremerton Gas Works Site

Bremerton, Washington

| Act/Authority                   | Criteria/Issue                                                    | Citation                                 | Brief Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Applicability/Appropriateness                                                                                                                                                                  |
|---------------------------------|-------------------------------------------------------------------|------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Safe Drinking Water Act         | Federal Primary Drinking Water Standards – MCLs and MCLGs         | 42 USC 300f; 40 CFR 141, Subpart O       | Establishes drinking water standards for public water systems to protect human health. Includes standards for the following Site contaminants of potential concern: arsenic, benzene, and benzo(a) pyrene. The National Contingency Plan states that MCLs, not MCLGs, are ARARs for usable aquifers.                                                                                                                                                                                        | ARARs for groundwater that could potentially be used for drinking water, where the water will be provided directly to 25 or more people or will be supplied to 15 or more service connections. |
| Safe Drinking Water Act         | Federal Secondary Drinking Water Standards – Secondary MCLs       | 42 USC 300f; 40 CFR 143                  | Establishes drinking water standards for public water systems to achieve the aesthetic qualities of drinking water (secondary MCLs).                                                                                                                                                                                                                                                                                                                                                        | TBC for groundwater that could potentially be a drinking water source (i.e., achieved as practicable).                                                                                         |
| Clean Water Act                 | Federal Ambient Water Quality Criteria                            | 33 USC 1311–1317; 40 CFR 131             | Under Clean Water Act, Section 304(a), minimum criteria are developed for water quality programs established by states. Two kinds of water quality criteria are developed: one for protection of human health, and one for protection of aquatic life. The federal recommended water quality criteria are published on EPA's website: <a href="http://water.epa.gov/scitech/swguidance/standards/current/index.cfm">http://water.epa.gov/scitech/swguidance/standards/current/index.cfm</a> | ARARs for surface water if more stringent than promulgated state criteria.                                                                                                                     |
| Surface Water Quality Standards | State Ambient Water Quality Criteria                              | Chapter 90.48 RCW; Chapter 173-201A WAC  | Establishes water quality standards for protection of human health and for protection of aquatic life (for both acute and chronic exposure durations).                                                                                                                                                                                                                                                                                                                                      | ARARs for surface water where Washington State has adopted, and EPA has approved, water quality standards.                                                                                     |
| Model Toxics Control Act        | State Soil, Air, Groundwater, and Surface Water Cleanup Standards | Chapter 70.105D RCW; Chapter 173-340 WAC | Establishes cleanup levels for Site groundwater, surface water, soil, and air, including rules for evaluating cross-media protectiveness. MTCA cleanup levels cannot be set at concentrations below natural background.                                                                                                                                                                                                                                                                     | Promulgated numeric cleanup levels are ARARs for soil, air, groundwater, and surface water. Equations to develop cleanup levels are not ARARs.                                                 |

**Table 6-1**

Final Scoping Memorandum

3/5/2015

V:\080239 Bremerton Former MGP Site\Deliverables\Scoping Memorandum\Final\Tables\Table 6-1 Chemical Specific ARARs.docx

Page 1 of 2

## Table 6-1 – Potential ARARs, Contaminant-Specific

Bremerton Gas Works Site  
Bremerton, Washington

| Act/Authority                 | Criteria/Issue                  | Citation                                          | Brief Description                                                                                                                                                                                                                                                                                                                                                                              | Applicability/Appropriateness                                                          |
|-------------------------------|---------------------------------|---------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------|
| Sediment Management Standards | State Sediment Quality Criteria | Chapters 90.48 & 70.105D RCW; Chapter 173-204 WAC | Establishes both numerical and biological wasting-based standards for the protection of benthic invertebrates in marine sediments. The current rule also defines methods for establishing cleanup levels protective of human health, including protection from risks associated with seafood consumption, analytical considerations, and natural and regional background contamination levels. | SMS cleanup levels will serve as ARARs for the development of sediment cleanup levels. |

### Notes:

ARAR = applicable or relevant and appropriate requirement

CFR = Code of Federal Regulations

EPA = U.S. Environmental Protection Agency

MCL = maximum contaminant level

MCLG = maximum contaminant level goal

MTCA = Model Toxics Control Act

RCW = Revised Code of Washington

SMS = Sediment Management Standards

TBC = to be considered

USC = United States Code

WAC = Washington Administrative Code

3/5/2015

V:\080239 Bremerton Former MGP Site\Deliverables\Scoping Memorandum\Final\Tables\Table 6-1 Chemical Specific ARARs.docx

**Table 6-1**

Final Scoping Memorandum

Page 2 of 2

**Table 6-2 – Potential ARARs, Location-Specific**

Bremerton Gas Works  
Bremerton, Washington

| Act/Authority                                            | Criteria/Issue                                                                              | Citation                                                                       | Brief Description                                                                                                                                                                                                                                | Applicability/Appropriateness                                                                                                                                                                                                                                                                          |
|----------------------------------------------------------|---------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Endangered Species Act                                   | Effects on Endangered Species                                                               | 16 USC 1531 et seq.; 50 CFR 17                                                 | Actions authorized, funded, or carried out by federal agencies may not jeopardize the continued existence of endangered or threatened species or adversely modify or destroy their critical habitats, or must take appropriate mitigation steps. | ARAR for remedial actions that may adversely affect endangered or threatened species or critical habitat present at the Site.                                                                                                                                                                          |
| Safe Drinking Water Act                                  | Underground Injection Control, Sole Source Aquifer Program, and Wellhead Protection Program | 42 USC 300h–300h-8; 40 CFR 300.400(g)(4); Chapter 173-160 WAC; WAC 246-290-135 | Resource planning programs designed to prevent contamination of underground sources of drinking water.                                                                                                                                           | The requirements of the City’s wellhead protection program are TBCs as a performance standard for groundwater that is a potential drinking water source (i.e., achieved as practicable). (Note that there are no water supply wells near the Site that are currently regulated by the City’s program.) |
| Magnuson-Stevens Fishery Conservation and Management Act | Habitat Impacts                                                                             | 16 USC 1855(b); 50 CFR 600.920                                                 | Requires evaluation of impacts on EFH if activities may adversely affect EFH.                                                                                                                                                                    | ARAR if the remedial action may adversely affect EFH.                                                                                                                                                                                                                                                  |
| Executive Order for Wetlands Protection                  | Wetlands Impacts                                                                            | Executive Order 11990 (1977), 40 CFR 6.302(a); 40 CFR 6, App. A                | Requires measures to avoid adversely affecting wetlands whenever possible, to minimize wetland destruction, and to preserve the value of wetlands.                                                                                               | ARAR for assessing impacts on wetlands, if any, from the remedial action and for developing appropriate compensatory mitigation.                                                                                                                                                                       |

**Notes:**

ARAR = applicable or relevant and appropriate requirement

CFR = Code of Federal Regulations

City = City of Bremerton

EFH = essential fish habitat

TBC = to be considered

USC = United States Code

WAC = Washington Administrative Code

**Table 6-2**

Final Scoping Memorandum

3/5/2015

V:\080239 Bremerton Former MGP Site\Deliverables\Scoping Memorandum\Final\Tables\Table 6-2 Location Specific ARARs.docx

Page 1 of 1

**Table 6-3 – Potential ARARs, Action-Specific**

Bremerton Gas Works

Bremerton, Washington

| Remedial Activity                  | Act/Authority                                                                                                            | Criteria/Issue                                                                                                                         | Citation                                                                                                                                       | Brief Description                                                                                                                                                                                                                        | Applicability/Appropriateness                                                                                                                                                                                                                                                                                 |
|------------------------------------|--------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Soil Excavation and Upland Filling | Solid Waste Disposal Act                                                                                                 | Management and Disposal of Solid Waste                                                                                                 | 42 USC 6901–6917; 40 CFR 257–258                                                                                                               | Establishes requirements for the management and disposal of solid wastes.                                                                                                                                                                | ARAR for remedial actions that result in upland disposal of excavated or dredged material.                                                                                                                                                                                                                    |
|                                    | Resource Conservation and Recovery Act (RCRA); Washington Hazardous Waste Management Act and Dangerous Waste Regulations | Generation and Management (Transportation, Treatment, Storage, and Disposal) of Hazardous Waste; Off-Site Land Disposal Considerations | 42 USC 6921–22; 40 CFR 260, 261, and 268; Chapter 70.105 RCW; Chapter 173-303 WAC<br>(Chapter 173-307 WAC Pollution Prevention Plans is a TBC) | Defines solid wastes subject to regulation as hazardous wastes. Requires management of hazardous waste from “cradle to grave” unless exemption applies. MGP wastes are subject to certain exemptions (e.g., Bevill Amendment provisions) | ARAR for wastes and soils sediments excavated from the Site for off-site disposal, and a TBC for on-site stabilization or containment actions.                                                                                                                                                                |
|                                    | Hazardous Materials Transportation Act                                                                                   | Transport of Hazardous Materials                                                                                                       | 49 USC 5101 et seq.; 49 CFR 171–177                                                                                                            | Establishes requirements for transport of hazardous materials.                                                                                                                                                                           | ARAR for those hazardous materials (e.g., DNAPL) transported off site.                                                                                                                                                                                                                                        |
|                                    | Washington Hydraulics Code                                                                                               | Filling of Wetlands                                                                                                                    | Chapters 75.20 and 77.55 RCW; Chapter 220-110 WAC                                                                                              | Establishes requirements for performing work that would alter existing jurisdictional wetlands.                                                                                                                                          | ARAR if remedial actions such as excavation or capping affect existing jurisdictional wetlands. Remedial actions must result in no net loss of aquatic habitat and function after sequential consideration of avoidance and mitigation, allowing for site-specific evaluations of existing wetland functions. |

**Table 6-3**

Final Scoping Memorandum

3/5/2015

V:\080239 Bremerton Former MGP Site\Deliverables\Scoping Memorandum\Final\Tables\Table 6-3 Action Specific ARARs.docx

Page 1 of 5



**Table 6-3 – Potential ARARs, Action-Specific**

Bremerton Gas Works

Bremerton, Washington

| Remedial Activity                                  | Act/Authority                                                             | Criteria/Issue                                                                    | Citation                                                                                                                                                                                | Brief Description                                                                                                                                                                                           | Applicability/Appropriateness                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |
|----------------------------------------------------|---------------------------------------------------------------------------|-----------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Soil Excavation and Upland Filling (Continued)     | City of Bremerton Shoreline Master Program and Critical Areas Regulations | Shoreline of Statewide Significance; Fish and Wildlife Habitat Conservation Areas | Chapter 90.58 RCW; Chapter 173-14 WAC; City of Bremerton Ordinance #5299 (effective December 4, 2013); Critical Area Regulations (BMC 20.14) are incorporated into the SMP by reference | Establishes replacement requirements for FWHCAs affected by remedial actions to ensure no net loss of existing ecological function; also establishes requirements for buffers and setbacks from shorelines. | ARAR if remedial actions such as excavation or capping result in impacts within 200 feet of ordinary high water mark or designated FWHCAs. Remedial actions must result in no net loss of aquatic habitat and function after sequential consideration of avoidance and mitigation, allowing for site-specific evaluations of existing shoreline habitat and FWHCAs. Washington's vested rights rule governs which SMP requirements apply in a given circumstance. Substantive requirements of the SMP that were in effect when redevelopment project applications were filed may be ARARs for future redevelopment actions at the Site. |
| Dredging, Capping, and/or Discharge to Puget Sound | Clean Water Act                                                           | Federal Ambient Water Quality Criteria                                            | 33 USC 1311–1317; 40 CFR 131                                                                                                                                                            | Regulates activities that may result in discharges into navigable waters.                                                                                                                                   | ARAR for control of short-term impacts on surface water due to implementation of remedial actions that include dredging, capping, and discharge of treated water into Puget Sound. Incorporates the substantive provisions of relevant and appropriate Joint Aquatic Resources Permit Application (JARPA), Nationwide Permit, and stormwater regulation requirements.                                                                                                                                                                                                                                                                   |

**Table 6-3**

Final Scoping Memorandum

3/5/2015

V:\080239 Bremerton Former MGP Site\Deliverables\Scoping Memorandum\Final\Tables\Table 6-3 Action Specific ARARs.docx

Page 2 of 5

**Table 6-3 – Potential ARARs, Action-Specific**

Bremerton Gas Works

Bremerton, Washington

| Remedial Activity                                              | Act/Authority                      | Criteria/Issue                                                            | Citation                                | Brief Description                                                                                                                                                                                                              | Applicability/Appropriateness                                                                                                                                                                                                                                                                                                                           |
|----------------------------------------------------------------|------------------------------------|---------------------------------------------------------------------------|-----------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Dredging, Capping, and/or Discharge to Puget Sound (Continued) | Surface Water Quality Standards    | State Ambient Water Quality Criteria                                      | Chapter 90.48 RCW; Chapter 173-201A WAC | Regulates activities that may result in discharges into navigable waters.                                                                                                                                                      | ARAR for control of short-term impacts on surface water due to implementation of remedial actions that include dredging, capping, and discharge of treated water into Puget Sound. Incorporates the substantive provisions of relevant and appropriate requirements, where Washington State has adopted, and EPA has approved, water quality standards. |
|                                                                | Clean Water Act                    | Discharge of Materials into Puget Sound                                   | 33 USC 1344; 40 CFR 230                 | Regulates discharge of dredged and fill material into navigable waters of the United States.                                                                                                                                   | ARAR for dredging and capping activities in Puget Sound.                                                                                                                                                                                                                                                                                                |
|                                                                | Fish and Wildlife Coordination Act | Discharge of Materials, Impoundment or Diversion of Waters in Puget Sound | 16 USC 662 and 663; 40 CFR 6.302(g)     | Requires federal agencies to consider effects on fish and wildlife from projects that may alter a body of water and mitigate or compensate for project-related losses, which include discharges of pollutants to water bodies. | ARAR for in-water remedial actions or if treated water is discharged into Puget Sound.                                                                                                                                                                                                                                                                  |
|                                                                | River and Harbors Act              | Placement of Structures in Puget Sound                                    | 33 USC 401 et seq.; 33 CFR 320–330      | Prohibits the unauthorized obstruction or alteration of any navigable water. Establishes requirements for structures or work in, above, or under navigable waters.                                                             | ARAR for remedial actions in Puget Sound.                                                                                                                                                                                                                                                                                                               |

**Table 6-3 – Potential ARARs, Action-Specific**

Bremerton Gas Works

Bremerton, Washington

| Remedial Activity                                              | Act/Authority                                                                                 | Criteria/Issue                                       | Citation                                                                          | Brief Description                                                                                                                                                                                                                                                                                                                                                                | Applicability/Appropriateness                                                                                                                                                                           |
|----------------------------------------------------------------|-----------------------------------------------------------------------------------------------|------------------------------------------------------|-----------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Dredging, Capping, and/or Discharge to Puget Sound (Continued) | Washington Hydraulics Code                                                                    | Filling in Puget Sound                               | Chapter 75.20 and 77.55 RCW; Chapter 220-110 WAC                                  | Establishes requirements for performing work that would use, divert, obstruct, or change the natural flow or bed of Puget Sound.                                                                                                                                                                                                                                                 | ARAR for shoreline excavation, dredging, and/or capping actions. Remedial actions must result in no net loss of aquatic habitat or function after sequential consideration of avoidance and mitigation. |
| Other Remedial Activities                                      | Federal Clean Air Act; Washington Clean Air Act; Puget Sound Air Clean Air Agency Regulations | Air Emission Discharges                              | 42 USC 7401 et seq.; Chapter 70.94 RCW; Chapter 173-400 WAC; PSCAA Regulation III | Regulates air emission discharges.                                                                                                                                                                                                                                                                                                                                               | ARAR for remedial activities that generate fugitive dust or other air emissions, including treatment operations.                                                                                        |
|                                                                | Historic Preservation Act; Washington Historical Activities Act                               | Alteration of Historic Properties                    | 16 USC 470 et seq.; 36 CFR 800; Chapter 27 RCW                                    | Requires the identification of historic properties potentially affected by remedial actions, and ways to avoid, minimize, or mitigate such effects. Historic property is any district, site, building, structure, or object included in or eligible for the National Register of Historic Places, including artifacts, records, and material remains related to such a property. | ARAR if historic properties are affected by remedial activities. No historic properties have been identified at the Site to date but could potentially be identified during remedial design.            |
|                                                                | Archeological and Historic Preservation Act                                                   | Alteration of Historic and Archaeological Properties | 16 USC 469a-1                                                                     | Provides for the preservation of historical and archeological data that may be irreparably lost as a result of a federally approved project and mandates only preservation of the data.                                                                                                                                                                                          | ARAR if historical and archeological resources may be irreparably lost by implementation of remedial activities.                                                                                        |

**Table 6-3**

Final Scoping Memorandum

3/5/2015

V:\080239 Bremerton Former MGP Site\Deliverables\Scoping Memorandum\Final\Tables\Table 6-3 Action Specific ARARs.docx

Page 4 of 5

**Table 6-3 – Potential ARARs, Action-Specific**

Bremerton Gas Works

Bremerton, Washington

| Remedial Activity                        | Act/Authority                                        | Criteria/Issue                | Citation                    | Brief Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Applicability/Appropriateness                                                         |
|------------------------------------------|------------------------------------------------------|-------------------------------|-----------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------|
| Other Remedial Activities<br>(Continued) | Native American Graves Protection and Reparation Act | Alteration of American Graves | 25 USC 3001–3013; 43 CFR 10 | Requires federal agencies and museums that have possession of or control over Native American cultural items (including human remains, associated and unassociated funerary items, sacred objects, and objects of cultural patrimony) to compile an inventory of such items. Prescribes when such federal agencies and museums must return Native American cultural items. “Museums” are defined as any institution or state or local government agency that receives federal funds and has possession of, or control over, Native American cultural items. | ARAR if Native American cultural items are present in an excavation or dredging area. |

## Notes:

ARAR = applicable or relevant and appropriate requirements

BMC = Bremerton Municipal Code

DNAPL = dense non-aqueous phase liquid

EPA = U.S. Environmental Protection Agency

FWHCA = Fish and Wildlife Habitat Conservation Area

MGP = manufactured gas plant

PSCCA = Puget Sound Clean Air Agency

RCW = Revised Code of Washington

SMP = Shoreline Master Program

TBC = to be considered

USC = United States Code

WAC = Washington Administrative Code

**Table 6-3**

Final Scoping Memorandum

3/5/2015

V:\080239 Bremerton Former MGP Site\Deliverables\Scoping Memorandum\Final\Tables\Table 6-3 Action Specific ARARs.docx

Page 5 of 5

Table 6-4 - Development of Initial PRGs for Soil

Bremerton Gas Works Site  
Bremerton, Washington

| Analyte                                         | CAS Number | EPA Region 5 RCRA<br>Soil Ecological<br>Screening Levels | EPA Ecological<br>Soil Screening<br>Levels - Birds | EPA Ecological Soil<br>Screening Levels -<br>Invertebrates | EPA Ecological Soil<br>Screening Levels -<br>Mammals | EPA Ecological<br>Soil Screening<br>Levels - Plants | EPA Regional<br>Screening Levels<br>(RSLs) -<br>Residential Soil | EPA Regional<br>Screening Levels<br>(RSLs) - Industrial<br>Soil | Initial PRGs Used for Data<br>Screening |                               |
|-------------------------------------------------|------------|----------------------------------------------------------|----------------------------------------------------|------------------------------------------------------------|------------------------------------------------------|-----------------------------------------------------|------------------------------------------------------------------|-----------------------------------------------------------------|-----------------------------------------|-------------------------------|
|                                                 |            | EPA, 2003                                                | EPA, 2010                                          | EPA, 2010                                                  | EPA, 2010                                            | EPA, 2010                                           | EPA, 2013                                                        | EPA, 2013                                                       | Surface Soil<br>(0-10 feet)             | Subsurface Soil<br>(>10 feet) |
| Alkane Isomers (ug/kg)                          |            |                                                          |                                                    |                                                            |                                                      |                                                     |                                                                  |                                                                 |                                         |                               |
| n-Hexane (C6)                                   | 110-54-3   | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 570000                                                           | 2600000                                                         | 570000                                  | 570000                        |
| Conventionals (mg/kg)                           |            |                                                          |                                                    |                                                            |                                                      |                                                     |                                                                  |                                                                 |                                         |                               |
| Cyanide, WAD                                    | 57-12-5    | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 22                                                               | 140                                                             | 22                                      | 22                            |
| Cyanide, total                                  | 57-12-5    | 1.33                                                     | --                                                 | --                                                         | --                                                   | --                                                  | --                                                               | --                                                              | 1.33                                    |                               |
| Sulfide                                         | 18496-25-8 | 0.00358                                                  | --                                                 | --                                                         | --                                                   | --                                                  | --                                                               | --                                                              | 0.00358                                 |                               |
| Metals (mg/kg)                                  |            |                                                          |                                                    |                                                            |                                                      |                                                     |                                                                  |                                                                 |                                         |                               |
| Antimony                                        | 7440-36-0  | 0.142                                                    | --                                                 | 78                                                         | 0.27                                                 | --                                                  | 31                                                               | 410                                                             | 0.27                                    | 31                            |
| Arsenic                                         | 7440-38-2  | 5.7                                                      | 43                                                 | --                                                         | 46                                                   | 18                                                  | 0.61                                                             | 2.4                                                             | 0.61                                    | 0.61                          |
| Beryllium                                       | 7440-41-7  | 1.06                                                     | --                                                 | 40                                                         | 21                                                   | --                                                  | 160                                                              | 2000                                                            | 21                                      | 160                           |
| Cadmium                                         | 7440-43-9  | 0.00222                                                  | 0.77                                               | 140                                                        | 0.36                                                 | 32                                                  | 70                                                               | 800                                                             | 0.36                                    | 70                            |
| Chromium                                        | 7440-47-3  | 0.4                                                      | 26                                                 | --                                                         | 34                                                   | --                                                  | --                                                               | --                                                              | 26                                      | --                            |
| Chromium III                                    | 16065-83-1 | --                                                       | 26                                                 | --                                                         | 34                                                   | --                                                  | 120000                                                           | 1500000                                                         | 26                                      | 120000                        |
| Chromium VI                                     | 18540-29-9 | --                                                       | --                                                 | --                                                         | 130                                                  | --                                                  | 0.29                                                             | 5.6                                                             | 0.29                                    | 0.29                          |
| Cobalt                                          | 7440-48-4  | 0.14                                                     | 120                                                | --                                                         | 230                                                  | 13                                                  | 23                                                               | 300                                                             | 13                                      | 23                            |
| Copper                                          | 7440-50-8  | 5.4                                                      | 28                                                 | 80                                                         | 49                                                   | 70                                                  | 3100                                                             | 41000                                                           | 28                                      | 3100                          |
| Lead                                            | 7439-92-1  | 0.0537                                                   | 11                                                 | 1700                                                       | 56                                                   | 120                                                 | 400                                                              | 800                                                             | 11                                      | 400                           |
| Manganese                                       | 7439-96-5  | --                                                       | 4300                                               | 450                                                        | 4000                                                 | 220                                                 | 1800                                                             | 23000                                                           | 220                                     | 1800                          |
| Mercury                                         | 7439-97-6  | 0.1                                                      | --                                                 | --                                                         | --                                                   | --                                                  | 10                                                               | 43                                                              | 10                                      | 10                            |
| Nickel                                          | 7440-02-0  | 13.6                                                     | 210                                                | 280                                                        | 130                                                  | 38                                                  | 1500                                                             | 20000                                                           | 38                                      | 1500                          |
| Selenium                                        | 7782-49-2  | 0.0276                                                   | 1.2                                                | 4.1                                                        | 0.63                                                 | 0.52                                                | 390                                                              | 5100                                                            | 0.52                                    | 390                           |
| Silver                                          | 7440-22-4  | 4.04                                                     | 4.2                                                | --                                                         | 14                                                   | 560                                                 | 390                                                              | 5100                                                            | 4.2                                     | 390                           |
| Thallium                                        | 7440-28-0  | 0.0569                                                   | --                                                 | --                                                         | --                                                   | --                                                  | 0.78                                                             | 10                                                              | 0.78                                    | 0.78                          |
| Zinc                                            | 7440-66-6  | 6.62                                                     | 46                                                 | 120                                                        | 79                                                   | 160                                                 | 23000                                                            | 310000                                                          | 46                                      | 23000                         |
| Metals, Organic (ug/kg)                         |            |                                                          |                                                    |                                                            |                                                      |                                                     |                                                                  |                                                                 |                                         |                               |
| Tributyltin                                     | 688-73-3   | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 18000                                                            | 180000                                                          | 18000                                   | 18000                         |
| Polycyclic Aromatic Hydrocarbons (PAHs) (ug/kg) |            |                                                          |                                                    |                                                            |                                                      |                                                     |                                                                  |                                                                 |                                         |                               |
| 1-Methylnaphthalene                             | 90-12-0    | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 16000                                                            | 53000                                                           | 16000                                   | 16000                         |
| 2-Methylnaphthalene                             | 91-57-6    | 3240                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 230000                                                           | 2200000                                                         | 230000                                  | 230000                        |
| Acenaphthene                                    | 83-32-9    | 682000                                                   | --                                                 | --                                                         | --                                                   | --                                                  | 3400000                                                          | 33000000                                                        | 3400000                                 | 3400000                       |
| Acenaphthylene                                  | 208-96-8   | 682000                                                   | --                                                 | --                                                         | --                                                   | --                                                  | --                                                               | --                                                              | 682000                                  | --                            |
| Anthracene                                      | 120-12-7   | 1480000                                                  | --                                                 | --                                                         | --                                                   | --                                                  | 17000000                                                         | 170000000                                                       | 17000000                                | 17000000                      |
| Benzo(a)anthracene                              | 56-55-3    | 5210                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 150                                                              | 2100                                                            | 150                                     | 150                           |
| Benzo(a)fluoranthene                            | 203-33-8   | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | --                                                               | --                                                              | --                                      | --                            |
| Benzo(a)pyrene                                  | 50-32-8    | 1520                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 15                                                               | 210                                                             | 15                                      | 15                            |
| Benzo(b)fluoranthene                            | 205-99-2   | 59800                                                    | --                                                 | --                                                         | --                                                   | --                                                  | 150                                                              | 2100                                                            | 150                                     | 150                           |
| Benzo(b,j)fluoranthene                          | --         | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | --                                                               | --                                                              | --                                      | --                            |
| Benzo(b,j,k)fluoranthenes                       | --         | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | --                                                               | --                                                              | --                                      | --                            |

Table 6-4 - Development of Initial PRGs for Soil

Bremerton Gas Works Site  
Bremerton, Washington

| Analyte                                         | CAS Number | EPA Region 5 RCRA<br>Soil Ecological<br>Screening Levels | EPA Ecological<br>Soil Screening<br>Levels - Birds | EPA Ecological Soil<br>Screening Levels -<br>Invertebrates | EPA Ecological Soil<br>Screening Levels -<br>Mammals | EPA Ecological<br>Soil Screening<br>Levels - Plants | EPA Regional<br>Screening Levels<br>(RSLs) -<br>Residential Soil | EPA Regional<br>Screening Levels<br>(RSLs) - Industrial<br>Soil | Initial PRGs Used for Data<br>Screening |                               |
|-------------------------------------------------|------------|----------------------------------------------------------|----------------------------------------------------|------------------------------------------------------------|------------------------------------------------------|-----------------------------------------------------|------------------------------------------------------------------|-----------------------------------------------------------------|-----------------------------------------|-------------------------------|
|                                                 |            | EPA, 2003                                                | EPA, 2010                                          | EPA, 2010                                                  | EPA, 2010                                            | EPA, 2010                                           | EPA, 2013                                                        | EPA, 2013                                                       | Surface Soil<br>(0-10 feet)             | Subsurface Soil<br>(>10 feet) |
| Benzo(b,k)fluoranthene                          | --         | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | --                                                               | --                                                              | --                                      | --                            |
| Benzo(g,h,i)fluoranthene                        | 203-12-3   | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | --                                                               | --                                                              | --                                      | --                            |
| Benzo(g,h,i)perylene                            | 191-24-2   | 119000                                                   | --                                                 | --                                                         | --                                                   | --                                                  | --                                                               | --                                                              | --                                      | --                            |
| Benzo(j)fluoranthene                            | 205-82-3   | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 380                                                              | 1300                                                            | 380                                     | 380                           |
| Benzo(j,k)fluoranthene                          | --         | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | --                                                               | --                                                              | --                                      | --                            |
| Benzo(k)fluoranthene                            | 207-08-9   | 148000                                                   | --                                                 | --                                                         | --                                                   | --                                                  | 1500                                                             | 21000                                                           | 1500                                    | 1500                          |
| Benzo <span></span> fluoranthene (unspecified)  | 56832-73-6 | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | --                                                               | --                                                              | --                                      | --                            |
| Chrysene                                        | 218-01-9   | 4730                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 15000                                                            | 210000                                                          | 15000                                   | 15000                         |
| Dibenzo(a,e)pyrene                              | 192-65-4   | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 38                                                               | 130                                                             | 38                                      | 38                            |
| Dibenzo(a,h)anthracene                          | 53-70-3    | 18400                                                    | --                                                 | --                                                         | --                                                   | --                                                  | 15                                                               | 210                                                             | 15                                      | 15                            |
| Fluoranthene                                    | 206-44-0   | 122000                                                   | --                                                 | --                                                         | --                                                   | --                                                  | 2300000                                                          | 22000000                                                        | 2300000                                 | 2300000                       |
| Fluorene                                        | 86-73-7    | 122000                                                   | --                                                 | --                                                         | --                                                   | --                                                  | 2300000                                                          | 22000000                                                        | 2300000                                 | 2300000                       |
| Indeno(1,2,3-c,d)pyrene                         | 193-39-5   | 109000                                                   | --                                                 | --                                                         | --                                                   | --                                                  | 150                                                              | 2100                                                            | 150                                     | 150                           |
| Total HPAH                                      | --         | --                                                       | --                                                 | 18000                                                      | 1100                                                 | --                                                  | --                                                               | --                                                              | 1100                                    | --                            |
| Total LPAH                                      | --         | --                                                       | --                                                 | 29000                                                      | 100000                                               | --                                                  | --                                                               | --                                                              | 29000                                   | --                            |
| Naphthalene                                     | 91-20-3    | 99.4                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 3600                                                             | 18000                                                           | 3600                                    | 3600                          |
| Phenanthrene                                    | 85-01-8    | 45700                                                    | --                                                 | --                                                         | --                                                   | --                                                  | --                                                               | --                                                              | 45700                                   | --                            |
| Pyrene                                          | 129-00-0   | 78500                                                    | --                                                 | --                                                         | --                                                   | --                                                  | 1700000                                                          | 17000000                                                        | 1700000                                 | 1700000                       |
| Total Benzo <span></span> fluoranthenes (b,j,k) | --         | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | --                                                               | --                                                              | --                                      | --                            |
| Total HPAH                                      | --         | --                                                       | --                                                 | 18000                                                      | 1100                                                 | --                                                  | --                                                               | --                                                              | 1100                                    | --                            |
| Total LPAH                                      | --         | --                                                       | --                                                 | 29000                                                      | 100000                                               | --                                                  | --                                                               | --                                                              | 29000                                   | --                            |
| Total PAH                                       | --         | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | --                                                               | --                                                              | --                                      | --                            |
| Polychlorinated Biphenyls (PCBs) (ug/kg)        |            |                                                          |                                                    |                                                            |                                                      |                                                     |                                                                  |                                                                 |                                         |                               |
| Aroclor 1016                                    | 12674-11-2 | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 3900                                                             | 21000                                                           | 3900                                    | 3900                          |
| Aroclor 1221                                    | 11104-28-2 | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 140                                                              | 540                                                             | 140                                     | 140                           |
| Aroclor 1232                                    | 11141-16-5 | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 140                                                              | 540                                                             | 140                                     | 140                           |
| Aroclor 1242                                    | 53469-21-9 | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 220                                                              | 740                                                             | 220                                     | 220                           |
| Aroclor 1248                                    | 12672-29-6 | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 220                                                              | 740                                                             | 220                                     | 220                           |
| Aroclor 1254                                    | 11097-69-1 | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 220                                                              | 740                                                             | 220                                     | 220                           |
| Aroclor 1260                                    | 11096-82-5 | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 220                                                              | 740                                                             | 220                                     | 220                           |
| Aroclor 1262                                    | 37324-23-5 | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | --                                                               | --                                                              | --                                      | --                            |
| Aroclor 1268                                    | 11100-14-4 | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | --                                                               | --                                                              | --                                      | --                            |
| Total PCB Aroclors                              | --         | 0.332                                                    | --                                                 | --                                                         | --                                                   | --                                                  | 220                                                              | 740                                                             | 220                                     | 220                           |
| Semivolatile Organic Compounds (SVOCs) (ug/kg)  |            |                                                          |                                                    |                                                            |                                                      |                                                     |                                                                  |                                                                 |                                         |                               |
| 1,2,4,5-Tetrachlorobenzene                      | 95-94-3    | 2020                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 18000                                                            | 180000                                                          | 18000                                   | 18000                         |
| 1,2,4-Trichlorobenzene                          | 120-82-1   | 11100                                                    | --                                                 | --                                                         | --                                                   | --                                                  | 22000                                                            | 99000                                                           | 22000                                   | 22000                         |
| 1,2-Dichlorobenzene                             | 95-50-1    | 2960                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 1900000                                                          | 9800000                                                         | 1900000                                 | 1900000                       |
| 1,3-Dichlorobenzene                             | 541-73-1   | 37700                                                    | --                                                 | --                                                         | --                                                   | --                                                  | --                                                               | --                                                              | 37700                                   | --                            |

Table 6-4 - Development of Initial PRGs for Soil

Bremerton Gas Works Site  
Bremerton, Washington

| Analyte                                      | CAS Number | EPA Region 5 RCRA<br>Soil Ecological<br>Screening Levels | EPA Ecological<br>Soil Screening<br>Levels - Birds | EPA Ecological Soil<br>Screening Levels -<br>Invertebrates | EPA Ecological Soil<br>Screening Levels -<br>Mammals | EPA Ecological<br>Soil Screening<br>Levels - Plants | EPA Regional<br>Screening Levels<br>(RSLs) -<br>Residential Soil | EPA Regional<br>Screening Levels<br>(RSLs) - Industrial<br>Soil | Initial PRGs Used for Data<br>Screening |                               |
|----------------------------------------------|------------|----------------------------------------------------------|----------------------------------------------------|------------------------------------------------------------|------------------------------------------------------|-----------------------------------------------------|------------------------------------------------------------------|-----------------------------------------------------------------|-----------------------------------------|-------------------------------|
|                                              |            | EPA, 2003                                                | EPA, 2010                                          | EPA, 2010                                                  | EPA, 2010                                            | EPA, 2010                                           | EPA, 2013                                                        | EPA, 2013                                                       | Surface Soil<br>(0-10 feet)             | Subsurface Soil<br>(>10 feet) |
| 1,4-Dichlorobenzene                          | 106-46-7   | 546                                                      | --                                                 | --                                                         | --                                                   | --                                                  | 2400                                                             | 12000                                                           | 2400                                    | 2400                          |
| 2,2'-Oxybis (1-chloropropane)                | 108-60-1   | 19900                                                    | --                                                 | --                                                         | --                                                   | --                                                  | 4600                                                             | 22000                                                           | 4600                                    | 4600                          |
| 2,3,4,6-Tetrachlorophenol                    | 58-90-2    | 199                                                      | --                                                 | --                                                         | --                                                   | --                                                  | 1800000                                                          | 18000000                                                        | 1800000                                 | 1800000                       |
| 2,4,5-Trichlorophenol                        | 95-95-4    | 14100                                                    | --                                                 | --                                                         | --                                                   | --                                                  | 6100000                                                          | 62000000                                                        | 6100000                                 | 6100000                       |
| 2,4,6-Trichlorophenol                        | 88-06-2    | 9940                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 44000                                                            | 160000                                                          | 44000                                   | 44000                         |
| 2,4-Dichlorophenol                           | 120-83-2   | 87500                                                    | --                                                 | --                                                         | --                                                   | --                                                  | 180000                                                           | 1800000                                                         | 180000                                  | 180000                        |
| 2,4-Dimethylphenol                           | 105-67-9   | 10                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 1200000                                                          | 12000000                                                        | 1200000                                 | 1200000                       |
| 2,4-Dinitrophenol                            | 51-28-5    | 60.9                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 120000                                                           | 1200000                                                         | 120000                                  | 120000                        |
| 2,4-Dinitrotoluene                           | 121-14-2   | 1280                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 1600                                                             | 5500                                                            | 1600                                    | 1600                          |
| 2,6-Dinitrotoluene                           | 606-20-2   | 32.8                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 330                                                              | 1200                                                            | 330                                     | 330                           |
| 2-Chloronaphthalene                          | 91-58-7    | 12.2                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 6300000                                                          | 82000000                                                        | 6300000                                 | 6300000                       |
| 2-Chlorophenol                               | 95-57-8    | 243                                                      | --                                                 | --                                                         | --                                                   | --                                                  | 390000                                                           | 5100000                                                         | 390000                                  | 390000                        |
| 2-Methylphenol (o-Cresol)                    | 95-48-7    | 40400                                                    | --                                                 | --                                                         | --                                                   | --                                                  | 3100000                                                          | 31000000                                                        | 3100000                                 | 3100000                       |
| 2-Nitroaniline                               | 88-74-4    | 74100                                                    | --                                                 | --                                                         | --                                                   | --                                                  | 610000                                                           | 6000000                                                         | 610000                                  | 610000                        |
| 2-Nitrophenol                                | 88-75-5    | 1600                                                     | --                                                 | --                                                         | --                                                   | --                                                  | --                                                               | --                                                              | 1600                                    | --                            |
| 3,3'-Dichlorobenzidine                       | 91-94-1    | 646                                                      | --                                                 | --                                                         | --                                                   | --                                                  | 1100                                                             | 3800                                                            | 1100                                    | 1100                          |
| 3-Methylphenol & 4-Methylphenol (m&p-Cresol) | 1319-77-3  | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 6100000                                                          | 62000000                                                        | 6100000                                 | 6100000                       |
| 3-Methylphenol (m-Cresol)                    | 108-39-4   | 3490                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 3100000                                                          | 31000000                                                        | 3100000                                 | 3100000                       |
| 3-Nitroaniline                               | 99-09-2    | 3160                                                     | --                                                 | --                                                         | --                                                   | --                                                  | --                                                               | --                                                              | 3160                                    | --                            |
| 4-Bromophenyl-phenyl ether                   | 101-55-3   | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | --                                                               | --                                                              | --                                      | --                            |
| 4-Chloro-3-methylphenol                      | 59-50-7    | 7950                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 6100000                                                          | 62000000                                                        | 6100000                                 | 6100000                       |
| 4-Chloroaniline                              | 106-47-8   | 1100                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 2400                                                             | 8600                                                            | 2400                                    | 2400                          |
| 4-Methylphenol (p-Cresol)                    | 106-44-5   | 163000                                                   | --                                                 | --                                                         | --                                                   | --                                                  | 6100000                                                          | 62000000                                                        | 6100000                                 | 6100000                       |
| 4-Nitroaniline                               | 100-01-6   | 21900                                                    | --                                                 | --                                                         | --                                                   | --                                                  | 24000                                                            | 86000                                                           | 24000                                   | 24000                         |
| 4-Nitrophenol                                | 100-02-7   | 5120                                                     | --                                                 | --                                                         | --                                                   | --                                                  | --                                                               | --                                                              | 5120                                    | --                            |
| Acetophenone                                 | 98-86-2    | 300000                                                   | --                                                 | --                                                         | --                                                   | --                                                  | 7800000                                                          | 100000000                                                       | 7800000                                 | 7800000                       |
| Aniline                                      | 62-53-3    | 56.8                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 85000                                                            | 300000                                                          | 85000                                   | 85000                         |
| Atrazine                                     | 1912-24-9  | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 2100                                                             | 7500                                                            | 2100                                    | 2100                          |
| Benzaldehyde                                 | 100-52-7   | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 7800000                                                          | 100000000                                                       | 7800000                                 | 7800000                       |
| Benzidine                                    | 92-87-5    | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 0.5                                                              | 7.5                                                             | 0.5                                     | 0.5                           |
| Benzo(b)pyridine                             | 91-22-5    | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 160                                                              | 570                                                             | 160                                     | 160                           |
| Benzoic acid                                 | 65-85-0    | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 240000000                                                        | 2500000000                                                      | 240000000                               | 240000000                     |
| Benzyl alcohol                               | 100-51-6   | 65800                                                    | --                                                 | --                                                         | --                                                   | --                                                  | 6100000                                                          | 62000000                                                        | 6100000                                 | 6100000                       |
| Biphenyl (1,1'-Biphenyl)                     | 92-52-4    | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 51000                                                            | 210000                                                          | 51000                                   | 51000                         |
| bis(2-Chloroethoxy)methane                   | 111-91-1   | 302                                                      | --                                                 | --                                                         | --                                                   | --                                                  | 180000                                                           | 1800000                                                         | 180000                                  | 180000                        |
| bis(2-Chloroethyl)ether                      | 111-44-4   | 23700                                                    | --                                                 | --                                                         | --                                                   | --                                                  | 210                                                              | 1000                                                            | 210                                     | 210                           |
| bis(2-Ethylhexyl)phthalate                   | 117-81-7   | 925                                                      | --                                                 | --                                                         | --                                                   | --                                                  | 35000                                                            | 120000                                                          | 35000                                   | 35000                         |
| Butylbenzyl phthalate                        | 85-68-7    | 239                                                      | --                                                 | --                                                         | --                                                   | --                                                  | 260000                                                           | 910000                                                          | 260000                                  | 260000                        |

Table 6-4 - Development of Initial PRGs for Soil

Bremerton Gas Works Site  
Bremerton, Washington

| Analyte                                       | CAS Number | EPA Region 5 RCRA<br>Soil Ecological<br>Screening Levels | EPA Ecological<br>Soil Screening<br>Levels - Birds | EPA Ecological Soil<br>Screening Levels -<br>Invertebrates | EPA Ecological Soil<br>Screening Levels -<br>Mammals | EPA Ecological<br>Soil Screening<br>Levels - Plants | EPA Regional<br>Screening Levels<br>(RSLs) -<br>Residential Soil | EPA Regional<br>Screening Levels<br>(RSLs) - Industrial<br>Soil | Initial PRGs Used for Data<br>Screening |                               |
|-----------------------------------------------|------------|----------------------------------------------------------|----------------------------------------------------|------------------------------------------------------------|------------------------------------------------------|-----------------------------------------------------|------------------------------------------------------------------|-----------------------------------------------------------------|-----------------------------------------|-------------------------------|
|                                               |            | EPA, 2003                                                | EPA, 2010                                          | EPA, 2010                                                  | EPA, 2010                                            | EPA, 2010                                           | EPA, 2013                                                        | EPA, 2013                                                       | Surface Soil<br>(0-10 feet)             | Subsurface Soil<br>(>10 feet) |
| Caprolactam                                   | 105-60-2   | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 30000000                                                         | 300000000                                                       | 30000000                                | 30000000                      |
| Dibenzofuran                                  | 132-64-9   | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 78000                                                            | 1000000                                                         | 78000                                   | 78000                         |
| Diethyl phthalate                             | 84-66-2    | 24800                                                    | --                                                 | --                                                         | --                                                   | --                                                  | 49000000                                                         | 490000000                                                       | 49000000                                | 49000000                      |
| Dimethyl phthalate                            | 131-11-3   | 734000                                                   | --                                                 | --                                                         | --                                                   | --                                                  | --                                                               | --                                                              | 734000                                  | --                            |
| Di-n-butyl phthalate                          | 84-74-2    | 150                                                      | --                                                 | --                                                         | --                                                   | --                                                  | 6100000                                                          | 62000000                                                        | 6100000                                 | 6100000                       |
| Dinitro-o-cresol (4,6-Dinitro-2-methylphenol) | 534-52-1   | 144                                                      | --                                                 | --                                                         | --                                                   | --                                                  | 4900                                                             | 49000                                                           | 4900                                    | 4900                          |
| Di-n-octyl phthalate                          | 117-84-0   | 709000                                                   | --                                                 | --                                                         | --                                                   | --                                                  | 610000                                                           | 6200000                                                         | 610000                                  | 610000                        |
| Hexachlorobenzene                             | 118-74-1   | 199                                                      | --                                                 | --                                                         | --                                                   | --                                                  | 300                                                              | 1100                                                            | 300                                     | 300                           |
| Hexachlorocyclopentadiene                     | 77-47-4    | 755                                                      | --                                                 | --                                                         | --                                                   | --                                                  | 370000                                                           | 3700000                                                         | 370000                                  | 370000                        |
| Hexachloroethane                              | 67-72-1    | 596                                                      | --                                                 | --                                                         | --                                                   | --                                                  | 12000                                                            | 43000                                                           | 12000                                   | 12000                         |
| Isophorone                                    | 78-59-1    | 139000                                                   | --                                                 | --                                                         | --                                                   | --                                                  | 510000                                                           | 1800000                                                         | 510000                                  | 510000                        |
| Nitrobenzene                                  | 98-95-3    | 1310                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 4800                                                             | 24000                                                           | 4800                                    | 4800                          |
| n-Nitrosodimethylamine                        | 62-75-9    | 0.0321                                                   | --                                                 | --                                                         | --                                                   | --                                                  | 2.3                                                              | 34                                                              | 2.3                                     | 2.3                           |
| n-Nitrosodi-n-propylamine                     | 621-64-7   | 544                                                      | --                                                 | --                                                         | --                                                   | --                                                  | 69                                                               | 250                                                             | 69                                      | 69                            |
| n-Nitrosodiphenylamine                        | 86-30-6    | 545                                                      | --                                                 | --                                                         | --                                                   | --                                                  | 99000                                                            | 350000                                                          | 99000                                   | 99000                         |
| Pentachlorophenol                             | 87-86-5    | 119                                                      | 2100                                               | 31000                                                      | 2800                                                 | 5000                                                | 890                                                              | 2700                                                            | 890                                     | 890                           |
| Phenol                                        | 108-95-2   | 120000                                                   | --                                                 | --                                                         | --                                                   | --                                                  | 18000000                                                         | 180000000                                                       | 18000000                                | 18000000                      |
| Volatile Organic Compounds (VOCs) (ug/kg)     |            |                                                          |                                                    |                                                            |                                                      |                                                     |                                                                  |                                                                 |                                         |                               |
| 1,1,1,2-Tetrachloroethane                     | 630-20-6   | 225000                                                   | --                                                 | --                                                         | --                                                   | --                                                  | 1900                                                             | 9300                                                            | 1900                                    | 1900                          |
| 1,1,1-Trichloroethane                         | 71-55-6    | 29800                                                    | --                                                 | --                                                         | --                                                   | --                                                  | 8700000                                                          | 38000000                                                        | 8700000                                 | 8700000                       |
| 1,1,2,2-Tetrachloroethane                     | 79-34-5    | 127                                                      | --                                                 | --                                                         | --                                                   | --                                                  | 560                                                              | 2800                                                            | 560                                     | 560                           |
| 1,1,2-Trichloroethane                         | 79-00-5    | 28600                                                    | --                                                 | --                                                         | --                                                   | --                                                  | 1100                                                             | 5300                                                            | 1100                                    | 1100                          |
| 1,1,2-Trichlorotrifluoroethane (Freon 113)    | 76-13-1    | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 43000000                                                         | 180000000                                                       | 43000000                                | 43000000                      |
| 1,1-Dichloroethane                            | 75-34-3    | 20100                                                    | --                                                 | --                                                         | --                                                   | --                                                  | 3300                                                             | 17000                                                           | 3300                                    | 3300                          |
| 1,1-Dichloroethene                            | 75-35-4    | 8280                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 240000                                                           | 1100000                                                         | 240000                                  | 240000                        |
| 1,2,3-Trichlorobenzene                        | 87-61-6    | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 49000                                                            | 490000                                                          | 49000                                   | 49000                         |
| 1,2,3-Trichloropropane                        | 96-18-4    | 3360                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 5                                                                | 95                                                              | 5                                       | 5                             |
| 1,2,4-Trimethylbenzene                        | 95-63-6    | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 62000                                                            | 260000                                                          | 62000                                   | 62000                         |
| 1,2-Dibromo-3-chloropropane                   | 96-12-8    | 35.2                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 5.4                                                              | 69                                                              | 5.4                                     | 5.4                           |
| 1,2-Dichloroethane                            | 107-06-2   | 21200                                                    | --                                                 | --                                                         | --                                                   | --                                                  | 430                                                              | 2200                                                            | 430                                     | 430                           |
| 1,2-Dichloroethene, cis-                      | 156-59-2   | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 160000                                                           | 2000000                                                         | 160000                                  | 160000                        |
| 1,2-Dichloroethene, trans-                    | 156-60-5   | 784                                                      | --                                                 | --                                                         | --                                                   | --                                                  | 150000                                                           | 690000                                                          | 150000                                  | 150000                        |
| 1,2-Dichloropropane                           | 78-87-5    | 32700                                                    | --                                                 | --                                                         | --                                                   | --                                                  | 940                                                              | 4700                                                            | 940                                     | 940                           |
| 1,3,5-Trimethylbenzene (Mesitylene)           | 108-67-8   | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 780000                                                           | 10000000                                                        | 780000                                  | 780000                        |
| 1,3-Dichloropropane                           | 142-28-9   | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 1600000                                                          | 20000000                                                        | 1600000                                 | 1600000                       |
| 1,3-Dichloropropene, cis-                     | 10061-01-5 | 398                                                      | --                                                 | --                                                         | --                                                   | --                                                  | --                                                               | --                                                              | 398                                     | --                            |
| 1,3-Dichloropropene, trans-                   | 10061-02-6 | 398                                                      | --                                                 | --                                                         | --                                                   | --                                                  | --                                                               | --                                                              | 398                                     | --                            |
| 1,4-Dichloro-2-butene, trans-                 | 110-57-6   | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 6.9                                                              | 35                                                              | 6.9                                     | 6.9                           |



Table 6-4 - Development of Initial PRGs for Soil

Bremerton Gas Works Site  
Bremerton, Washington

| Analyte                                                 | CAS Number | EPA Region 5 RCRA<br>Soil Ecological<br>Screening Levels | EPA Ecological<br>Soil Screening<br>Levels - Birds | EPA Ecological Soil<br>Screening Levels -<br>Invertebrates | EPA Ecological Soil<br>Screening Levels -<br>Mammals | EPA Ecological<br>Soil Screening<br>Levels - Plants | EPA Regional<br>Screening Levels<br>(RSLs) -<br>Residential Soil | EPA Regional<br>Screening Levels<br>(RSLs) - Industrial<br>Soil | Initial PRGs Used for Data<br>Screening |                               |
|---------------------------------------------------------|------------|----------------------------------------------------------|----------------------------------------------------|------------------------------------------------------------|------------------------------------------------------|-----------------------------------------------------|------------------------------------------------------------------|-----------------------------------------------------------------|-----------------------------------------|-------------------------------|
|                                                         |            | EPA, 2003                                                | EPA, 2010                                          | EPA, 2010                                                  | EPA, 2010                                            | EPA, 2010                                           | EPA, 2013                                                        | EPA, 2013                                                       | Surface Soil<br>(0-10 feet)             | Subsurface Soil<br>(>10 feet) |
| 1,4-Dioxane                                             | 123-91-1   | 2050                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 4900                                                             | 17000                                                           | 4900                                    | 4900                          |
| 2-Butanone (MEK)                                        | 78-93-3    | 89600                                                    | --                                                 | --                                                         | --                                                   | --                                                  | 28000000                                                         | 20000000                                                        | 28000000                                | 28000000                      |
| 2-Hexanone (Methyl butyl ketone)                        | 591-78-6   | 12600                                                    | --                                                 | --                                                         | --                                                   | --                                                  | 210000                                                           | 1400000                                                         | 210000                                  | 210000                        |
| 4-Chlorotoluene                                         | 106-43-4   | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 1600000                                                          | 20000000                                                        | 1600000                                 | 1600000                       |
| 4-Isopropyltoluene (4-Cymene)                           | 99-87-6    | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | --                                                               | --                                                              | --                                      | --                            |
| Acetone                                                 | 67-64-1    | 2500                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 61000000                                                         | 630000000                                                       | 61000000                                | 61000000                      |
| Acrolein                                                | 107-02-8   | 5270                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 150                                                              | 650                                                             | 150                                     | 150                           |
| Acrylonitrile                                           | 107-13-1   | 23.9                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 240                                                              | 1200                                                            | 240                                     | 240                           |
| Benzene                                                 | 71-43-2    | 255                                                      | --                                                 | --                                                         | --                                                   | --                                                  | 1100                                                             | 5400                                                            | 255                                     | 1100                          |
| Bromobenzene                                            | 108-86-1   | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 300000                                                           | 1800000                                                         | 300000                                  | 300000                        |
| Bromochloromethane                                      | 74-97-5    | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 160000                                                           | 680000                                                          | 160000                                  | 160000                        |
| Bromodichloromethane                                    | 75-27-4    | 540                                                      | --                                                 | --                                                         | --                                                   | --                                                  | 270                                                              | 1400                                                            | 270                                     | 270                           |
| Bromoform (Tribromomethane)                             | 75-25-2    | 15900                                                    | --                                                 | --                                                         | --                                                   | --                                                  | 62000                                                            | 220000                                                          | 62000                                   | 62000                         |
| Bromomethane (Methyl bromide)                           | 74-83-9    | 235                                                      | --                                                 | --                                                         | --                                                   | --                                                  | 7300                                                             | 32000                                                           | 7300                                    | 7300                          |
| Carbon disulfide                                        | 75-15-0    | 94.1                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 820000                                                           | 3700000                                                         | 820000                                  | 820000                        |
| Carbon tetrachloride (Tetrachloromethane)               | 56-23-5    | 2980                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 610                                                              | 3000                                                            | 610                                     | 610                           |
| Chlorobenzene                                           | 108-90-7   | 13100                                                    | --                                                 | --                                                         | --                                                   | --                                                  | 290000                                                           | 1400000                                                         | 290000                                  | 290000                        |
| Chloroethane                                            | 75-00-3    | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 15000000                                                         | 61000000                                                        | 15000000                                | 15000000                      |
| Chloroform                                              | 67-66-3    | 1190                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 290                                                              | 1500                                                            | 290                                     | 290                           |
| Chloromethane                                           | 74-87-3    | 10400                                                    | --                                                 | --                                                         | --                                                   | --                                                  | 120000                                                           | 500000                                                          | 120000                                  | 120000                        |
| Cyclohexane                                             | 110-82-7   | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 7000000                                                          | 29000000                                                        | 7000000                                 | 7000000                       |
| Dibromochloromethane                                    | 124-48-1   | 2050                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 680                                                              | 3300                                                            | 680                                     | 680                           |
| Dibromomethane                                          | 74-95-3    | 65000                                                    | --                                                 | --                                                         | --                                                   | --                                                  | 25000                                                            | 110000                                                          | 25000                                   | 25000                         |
| Dichlorodifluoromethane                                 | 75-71-8    | 39500                                                    | --                                                 | --                                                         | --                                                   | --                                                  | 94000                                                            | 400000                                                          | 94000                                   | 94000                         |
| Dichloromethane (Methylene chloride)                    | 75-09-2    | 4050                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 56000                                                            | 960000                                                          | 56000                                   | 56000                         |
| Ethylbenzene                                            | 100-41-4   | 5160                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 5400                                                             | 27000                                                           | 5400                                    | 5400                          |
| Ethylene dibromide (1,2-Dibromoethane)                  | 106-93-4   | 1230                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 34                                                               | 170                                                             | 34                                      | 34                            |
| Hexachlorobutadiene (Hexachloro-1,3-butadiene)          | 87-68-3    | 39.8                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 6200                                                             | 22000                                                           | 6200                                    | 6200                          |
| Isopropylbenzene (Cumene)                               | 98-82-8    | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 2100000                                                          | 11000000                                                        | 2100000                                 | 2100000                       |
| Methyl acetate                                          | 79-20-9    | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 78000000                                                         | 1000000000                                                      | 78000000                                | 78000000                      |
| Methyl iodide (Iodomethane)                             | 74-88-4    | 1230                                                     | --                                                 | --                                                         | --                                                   | --                                                  | --                                                               | --                                                              | 1230                                    | --                            |
| Methyl isobutyl ketone (4-Methyl-2-pentanone or (MIBK)) | 108-10-1   | 443000                                                   | --                                                 | --                                                         | --                                                   | --                                                  | 5300000                                                          | 53000000                                                        | 5300000                                 | 5300000                       |
| Methyl tert-butyl ether (MTBE)                          | 1634-04-4  | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 43000                                                            | 220000                                                          | 43000                                   | 43000                         |
| n-Butylbenzene                                          | 104-51-8   | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 3900000                                                          | 51000000                                                        | 3900000                                 | 3900000                       |
| n-Propylbenzene                                         | 103-65-1   | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 3400000                                                          | 21000000                                                        | 3400000                                 | 3400000                       |
| o-Xylene                                                | 95-47-6    | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 690000                                                           | 3000000                                                         | 690000                                  | 690000                        |
| sec-Butylbenzene                                        | 135-98-8   | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 7800000                                                          | 100000000                                                       | 7800000                                 | 7800000                       |
| Styrene                                                 | 100-42-5   | 4690                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 6300000                                                          | 36000000                                                        | 6300000                                 | 6300000                       |

Table 6-4 - Development of Initial PRGs for Soil

Bremerton Gas Works Site  
Bremerton, Washington

| Analyte                                         | CAS Number | EPA Region 5 RCRA<br>Soil Ecological<br>Screening Levels | EPA Ecological<br>Soil Screening<br>Levels - Birds | EPA Ecological Soil<br>Screening Levels -<br>Invertebrates | EPA Ecological Soil<br>Screening Levels -<br>Mammals | EPA Ecological<br>Soil Screening<br>Levels - Plants | EPA Regional<br>Screening Levels<br>(RSLs) -<br>Residential Soil | EPA Regional<br>Screening Levels<br>(RSLs) - Industrial<br>Soil | Initial PRGs Used for Data<br>Screening |                               |
|-------------------------------------------------|------------|----------------------------------------------------------|----------------------------------------------------|------------------------------------------------------------|------------------------------------------------------|-----------------------------------------------------|------------------------------------------------------------------|-----------------------------------------------------------------|-----------------------------------------|-------------------------------|
|                                                 |            | EPA, 2003                                                | EPA, 2010                                          | EPA, 2010                                                  | EPA, 2010                                            | EPA, 2010                                           | EPA, 2013                                                        | EPA, 2013                                                       | Surface Soil<br>(0-10 feet)             | Subsurface Soil<br>(>10 feet) |
| tert-Butylbenzene                               | 98-06-6    | --                                                       | --                                                 | --                                                         | --                                                   | --                                                  | 7800000                                                          | 100000000                                                       | 7800000                                 | 7800000                       |
| Tetrachloroethene (PCE)                         | 127-18-4   | 9920                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 22000                                                            | 110000                                                          | 22000                                   | 22000                         |
| Toluene                                         | 108-88-3   | 5450                                                     | --                                                 | --                                                         | --                                                   | --                                                  | 5000000                                                          | 45000000                                                        | 5000000                                 | 5000000                       |
| Total xylene (reported, not calculated)         | 1330-20-7  | 10000                                                    | --                                                 | --                                                         | --                                                   | --                                                  | 630000                                                           | 2700000                                                         | 630000                                  | 630000                        |
| Total Xylene                                    | --         | 10000                                                    | --                                                 | --                                                         | --                                                   | --                                                  | --                                                               | --                                                              | --                                      | --                            |
| Trichloroethene (TCE)                           | 79-01-6    | 12400                                                    | --                                                 | --                                                         | --                                                   | --                                                  | 910                                                              | 6400                                                            | 910                                     | 910                           |
| Trichlorofluoromethane (Fluorotrichloromethane) | 75-69-4    | 16400                                                    | --                                                 | --                                                         | --                                                   | --                                                  | 790000                                                           | 3400000                                                         | 790000                                  | 790000                        |
| Vinyl acetate                                   | 108-05-4   | 12700                                                    | --                                                 | --                                                         | --                                                   | --                                                  | 970000                                                           | 4100000                                                         | 970000                                  | 970000                        |
| Vinyl chloride                                  | 75-01-4    | 646                                                      | --                                                 | --                                                         | --                                                   | --                                                  | 60                                                               | 1700                                                            | 60                                      | 60                            |

Notes:

Compounds frequently associated with MGP-operations.

-- indicates not available  
CAS = Chemical Abstract Services  
EPA = U.S. Environmental Protection Agency  
HPAH = high molecular weight PAH  
LPAH = low molecular weight PAH  
kg = kilogram  
mg = miligram  
MGP = manufactured gas plant  
ng = nanogram  
PRG = preliminary remediation goal  
RCRA = Resource Conservation and Recovery Act  
RSL = regional screening level  
ug = microgram  
WAD = Weak Acid Dissociable Cyanide

References:

EPA, 2003. EPA Region 5 Resource Conservation Recovery Act (RCRA) Ecological Screening Levels. August 22, 2003.

EPA, 2010. Ecological Soil Screening Levels. Updated October 20, 2010. Cited: January 15, 2014. Available from: <http://www.epa.gov/ecotox/ecossl/>

EPA, 2013. EPA Regional Screening Levels. November 2013. Available from: [http://www.epa.gov/reg3hwmd/risk/human/rb-concentration\\_table/Generic\\_Tables/docs/master\\_sl\\_table\\_run\\_NOV2013.pdf](http://www.epa.gov/reg3hwmd/risk/human/rb-concentration_table/Generic_Tables/docs/master_sl_table_run_NOV2013.pdf)

Table 6-5 - Development of Initial PRGs for Groundwater

Bremerton Gas Works Site  
Bremerton, Washington

| Analyte                                       | CAS Number | EPA Regional<br>Screening Levels<br>(RSLs) - MCL | EPA Regional<br>Screening Levels<br>(RSLs) - Tapwater |
|-----------------------------------------------|------------|--------------------------------------------------|-------------------------------------------------------|
|                                               |            | EPA, 2013                                        | EPA, 2013                                             |
| Alkane Isomers (ug/L)                         |            |                                                  |                                                       |
| n-Hexane (C6)                                 | 110-54-3   | --                                               | 250                                                   |
| Conventionals (mg/L)                          |            |                                                  |                                                       |
| Cyanide, free                                 | 57-12-5    | 0.2                                              | 0.0014                                                |
| Sulfide                                       | 18496-25-8 | --                                               | --                                                    |
| Metals (ug/L)                                 |            |                                                  |                                                       |
| Antimony                                      | 7440-36-0  | 6                                                | 6                                                     |
| Arsenic                                       | 7440-38-2  | 10                                               | 0.045                                                 |
| Beryllium                                     | 7440-41-7  | 4                                                | 16                                                    |
| Cadmium                                       | 7440-43-9  | 5                                                | 6.9                                                   |
| Chromium                                      | 7440-47-3  | 100                                              | --                                                    |
| Chromium III                                  | 16065-83-1 | --                                               | 16000                                                 |
| Chromium VI                                   | 18540-29-9 | --                                               | 0.031                                                 |
| Copper                                        | 7440-50-8  | 1300                                             | 620                                                   |
| Lead                                          | 7439-92-1  | 15                                               | 15                                                    |
| Mercury                                       | 7439-97-6  | 2                                                | 0.63                                                  |
| Nickel                                        | 7440-02-0  | --                                               | 300                                                   |
| Selenium                                      | 7782-49-2  | 50                                               | 78                                                    |
| Silver                                        | 7440-22-4  | --                                               | 71                                                    |
| Thallium                                      | 7440-28-0  | 2                                                | 0.16                                                  |
| Zinc                                          | 7440-66-6  | --                                               | 4700                                                  |
| Metals, Organic (ug/L)                        |            |                                                  |                                                       |
| Tributyltin                                   | 688-73-3   | --                                               | 2.8                                                   |
| Polycyclic Aromatic Hydrocarbons (PAHs)(ug/L) |            |                                                  |                                                       |
| 1-Methylnaphthalene                           | 90-12-0    | --                                               | 0.97                                                  |
| 2-Methylnaphthalene                           | 91-57-6    | --                                               | 27                                                    |
| Acenaphthene                                  | 83-32-9    | --                                               | 400                                                   |
| Acenaphthylene                                | 208-96-8   | --                                               | --                                                    |
| Anthracene                                    | 120-12-7   | --                                               | 1300                                                  |
| Benzo(a)anthracene                            | 56-55-3    | --                                               | 0.029                                                 |
| Benzo(a)pyrene                                | 50-32-8    | 0.2                                              | 0.0029                                                |
| Benzo(b)fluoranthene                          | 205-99-2   | --                                               | 0.029                                                 |
| Benzo(b,k)fluoranthene                        | --         | --                                               | --                                                    |
| Benzo(g,h,i)perylene                          | 191-24-2   | --                                               | --                                                    |
| Benzo(j)fluoranthene                          | 205-82-3   | --                                               | 0.056                                                 |
| Benzo(k)fluoranthene                          | 207-08-9   | --                                               | 0.29                                                  |
| Chrysene                                      | 218-01-9   | --                                               | 2.9                                                   |
| Dibenzo(a,h)anthracene                        | 53-70-3    | --                                               | 0.0029                                                |
| Fluoranthene                                  | 206-44-0   | --                                               | 630                                                   |
| Fluorene                                      | 86-73-7    | --                                               | 220                                                   |
| Indeno(1,2,3-c,d)pyrene                       | 193-39-5   | --                                               | 0.029                                                 |
| Naphthalene                                   | 91-20-3    | --                                               | 0.14                                                  |
| Phenanthrene                                  | 85-01-8    | --                                               | --                                                    |
| Pyrene                                        | 129-00-0   | --                                               | 87                                                    |
| Total Benzofluoranthenes (b,j,k)              | --         | --                                               | --                                                    |
| Total HPAH                                    | --         | --                                               | --                                                    |
| Total LPAH                                    | --         | --                                               | --                                                    |
| Total PAH                                     | --         | --                                               | --                                                    |
| Polychlorinated Biphenyls (PCBs) (ug/L)       |            |                                                  |                                                       |
| Aroclor 1016                                  | 12674-11-2 | --                                               | 0.96                                                  |
| Aroclor 1221                                  | 11104-28-2 | --                                               | 0.004                                                 |
| Aroclor 1232                                  | 11141-16-5 | --                                               | 0.004                                                 |
| Aroclor 1242                                  | 53469-21-9 | --                                               | 0.034                                                 |
| Aroclor 1248                                  | 12672-29-6 | --                                               | 0.034                                                 |
| Aroclor 1254                                  | 11097-69-1 | --                                               | 0.034                                                 |
| Aroclor 1260                                  | 11096-82-5 | --                                               | 0.034                                                 |
| Aroclor 1262                                  | 37324-23-5 | --                                               | --                                                    |
| Aroclor 1268                                  | 11100-14-4 | --                                               | --                                                    |
| Total PCB Aroclors                            | --         | --                                               | 0.17                                                  |
| Semivolatile Organic Compounds (SVOCs) (ug/L) |            |                                                  |                                                       |
| 1,2,4,5-Tetrachlorobenzene                    | 95-94-3    | --                                               | 1.2                                                   |
| 1,2,4-Trichlorobenzene                        | 120-82-1   | 70                                               | 0.99                                                  |
| 1,2-Dichlorobenzene                           | 95-50-1    | 600                                              | 280                                                   |
| 1,3-Dichlorobenzene                           | 541-73-1   | --                                               | --                                                    |
| 1,4-Dichlorobenzene                           | 106-46-7   | 75                                               | 0.42                                                  |
| 2,2'-Oxybis (1-chloropropane)                 | 108-60-1   | --                                               | 0.31                                                  |
| 2,3,4,6-Tetrachlorophenol                     | 58-90-2    | --                                               | 170                                                   |
| 2,4,5-Trichlorophenol                         | 95-95-4    | --                                               | 890                                                   |

Table 6-5

Table 6-5 - Development of Initial PRGs for Groundwater

Bremerton Gas Works Site  
Bremerton, Washington

| Analyte                                       | CAS Number | EPA Regional Screening Levels (RSLs) - MCL | EPA Regional Screening Levels (RSLs) - Tapwater |
|-----------------------------------------------|------------|--------------------------------------------|-------------------------------------------------|
|                                               |            | EPA, 2013                                  | EPA, 2013                                       |
| 2,4,6-Trichlorophenol                         | 88-06-2    | --                                         | 3.5                                             |
| 2,4-Dichlorophenol                            | 120-83-2   | --                                         | 35                                              |
| 2,4-Dimethylphenol                            | 105-67-9   | --                                         | 270                                             |
| 2,4-Dinitrophenol                             | 51-28-5    | --                                         | 30                                              |
| 2,4-Dinitrotoluene                            | 121-14-2   | --                                         | 0.2                                             |
| 2,6-Dinitrotoluene                            | 606-20-2   | --                                         | 0.042                                           |
| 2-Chloronaphthalene                           | 91-58-7    | --                                         | 550                                             |
| 2-Chlorophenol                                | 95-57-8    | --                                         | 71                                              |
| 2-Methylphenol (o-Cresol)                     | 95-48-7    | --                                         | 720                                             |
| 2-Nitroaniline                                | 88-74-4    | --                                         | 150                                             |
| 2-Nitrophenol                                 | 88-75-5    | --                                         | --                                              |
| 3,3'-Dichlorobenzidine                        | 91-94-1    | --                                         | 0.11                                            |
| 3-Methylphenol & 4-Methylphenol (m&p-Cresol)  | 1319-77-3  | --                                         | 1400                                            |
| 3-Methylphenol (m-Cresol)                     | 108-39-4   | --                                         | 720                                             |
| 3-Nitroaniline                                | 99-09-2    | --                                         | --                                              |
| 4-Bromophenyl-phenyl ether                    | 101-55-3   | --                                         | --                                              |
| 4-Chloro-3-methylphenol                       | 59-50-7    | --                                         | 1100                                            |
| 4-Chloroaniline                               | 106-47-8   | --                                         | 0.32                                            |
| 4-Methylphenol (p-Cresol)                     | 106-44-5   | --                                         | 1400                                            |
| 4-Nitroaniline                                | 100-01-6   | --                                         | 3.3                                             |
| 4-Nitrophenol                                 | 100-02-7   | --                                         | --                                              |
| Acetophenone                                  | 98-86-2    | --                                         | 1500                                            |
| Aniline                                       | 62-53-3    | --                                         | 12                                              |
| Atrazine                                      | 1912-24-9  | 3                                          | 0.26                                            |
| Benzaldehyde                                  | 100-52-7   | --                                         | 1500                                            |
| Benzidine                                     | 92-87-5    | --                                         | 0.000092                                        |
| Benzoic acid                                  | 65-85-0    | --                                         | 58000                                           |
| Benzyl alcohol                                | 100-51-6   | --                                         | 1500                                            |
| Biphenyl (1,1'-Biphenyl)                      | 92-52-4    | --                                         | 0.83                                            |
| bis(2-Chloroethoxy)methane                    | 111-91-1   | --                                         | 46                                              |
| bis(2-Chloroethyl)ether                       | 111-44-4   | --                                         | 0.012                                           |
| bis(2-Ethylhexyl)phthalate                    | 117-81-7   | 6                                          | 4.8                                             |
| Butylbenzyl phthalate                         | 85-68-7    | --                                         | 14                                              |
| Caprolactam                                   | 105-60-2   | --                                         | 7700                                            |
| Dibenzofuran                                  | 132-64-9   | --                                         | 5.8                                             |
| Diethyl phthalate                             | 84-66-2    | --                                         | 11000                                           |
| Dimethyl phthalate                            | 131-11-3   | --                                         | --                                              |
| Di-n-butyl phthalate                          | 84-74-2    | --                                         | 670                                             |
| Dinitro-o-cresol (4,6-Dinitro-2-methylphenol) | 534-52-1   | --                                         | 1.2                                             |
| Di-n-octyl phthalate                          | 117-84-0   | --                                         | 160                                             |
| Hexachlorobenzene                             | 118-74-1   | 1                                          | 0.042                                           |
| Hexachlorocyclopentadiene                     | 77-47-4    | 50                                         | 22                                              |
| Hexachloroethane                              | 67-72-1    | --                                         | 0.79                                            |
| Isophorone                                    | 78-59-1    | --                                         | 67                                              |
| Nitrobenzene                                  | 98-95-3    | --                                         | 0.12                                            |
| n-Nitrosodimethylamine                        | 62-75-9    | --                                         | 0.00042                                         |
| n-Nitrosodi-n-propylamine                     | 621-64-7   | --                                         | 0.0093                                          |
| n-Nitrosodiphenylamine                        | 86-30-6    | --                                         | 10                                              |
| Pentachlorophenol                             | 87-86-5    | 1                                          | 0.035                                           |
| Phenol                                        | 108-95-2   | --                                         | 4500                                            |
| Volatile Organic Compounds (VOCs) (ug/L)      |            |                                            |                                                 |
| 1,1,1,2-Tetrachloroethane                     | 630-20-6   | --                                         | 0.5                                             |
| 1,1,1-Trichloroethane                         | 71-55-6    | 200                                        | 7500                                            |
| 1,1,2,2-Tetrachloroethane                     | 79-34-5    | --                                         | 0.066                                           |
| 1,1,2-Trichloroethane                         | 79-00-5    | 5                                          | 0.24                                            |
| 1,1,2-Trichlorotrifluoroethane (Freon 113)    | 76-13-1    | --                                         | 53000                                           |
| 1,1-Dichloroethane                            | 75-34-3    | --                                         | 2.4                                             |
| 1,1-Dichloroethene                            | 75-35-4    | 7                                          | 260                                             |
| 1,2,3-Trichlorobenzene                        | 87-61-6    | --                                         | 5.2                                             |
| 1,2,3-Trichloropropane                        | 96-18-4    | --                                         | 0.00065                                         |
| 1,2,4-Trimethylbenzene                        | 95-63-6    | --                                         | 15                                              |
| 1,2-Dibromo-3-chloropropane                   | 96-12-8    | 0.2                                        | 0.00032                                         |
| 1,2-Dichloroethane                            | 107-06-2   | 5                                          | 0.15                                            |
| 1,2-Dichloroethene, cis-                      | 156-59-2   | 70                                         | 28                                              |
| 1,2-Dichloroethene, trans-                    | 156-60-5   | 100                                        | 86                                              |
| 1,2-Dichloropropane                           | 78-87-5    | 5                                          | 0.38                                            |
| 1,3,5-Trimethylbenzene (Mesitylene)           | 108-67-8   | --                                         | 87                                              |
| 1,3-Dichloropropane                           | 142-28-9   | --                                         | 290                                             |

Table 6-5

Table 6-5 - Development of Initial PRGs for Groundwater

Bremerton Gas Works Site  
Bremerton, Washington

| Analyte                                                 | CAS Number | EPA Regional Screening Levels (RSLs) - MCL | EPA Regional Screening Levels (RSLs) - Tapwater |
|---------------------------------------------------------|------------|--------------------------------------------|-------------------------------------------------|
|                                                         |            | EPA, 2013                                  | EPA, 2013                                       |
| 1,3-Dichloropropene, cis-                               | 10061-01-5 | --                                         | --                                              |
| 1,3-Dichloropropene, trans-                             | 10061-02-6 | --                                         | --                                              |
| 1,4-Dichloro-2-butene, trans-                           | 110-57-6   | --                                         | 0.0012                                          |
| 1,4-Dioxane                                             | 123-91-1   | --                                         | 0.67                                            |
| 2-Butanone (MEK)                                        | 78-93-3    | --                                         | 4900                                            |
| 2-Chlorotoluene                                         | 95-49-8    | --                                         | 180                                             |
| 2-Hexanone (Methyl butyl ketone)                        | 591-78-6   | --                                         | 34                                              |
| 4-Chlorotoluene                                         | 106-43-4   | --                                         | 190                                             |
| 4-Isopropyltoluene (4-Cymene)                           | 99-87-6    | --                                         | --                                              |
| Acetone                                                 | 67-64-1    | --                                         | 12000                                           |
| Acrolein                                                | 107-02-8   | --                                         | 0.041                                           |
| Acrylonitrile                                           | 107-13-1   | --                                         | 0.045                                           |
| Benzene                                                 | 71-43-2    | 5                                          | 0.39                                            |
| Bromobenzene                                            | 108-86-1   | --                                         | 54                                              |
| Bromochloromethane                                      | 74-97-5    | --                                         | 83                                              |
| Bromodichloromethane                                    | 75-27-4    | 80                                         | 0.12                                            |
| Bromoform (Tribromomethane)                             | 75-25-2    | 80                                         | 7.9                                             |
| Bromomethane (Methyl bromide)                           | 74-83-9    | --                                         | 7                                               |
| Carbon disulfide                                        | 75-15-0    | --                                         | 720                                             |
| Carbon tetrachloride (Tetrachloromethane)               | 56-23-5    | 5                                          | 0.39                                            |
| Chlorobenzene                                           | 108-90-7   | 100                                        | 72                                              |
| Chloroethane                                            | 75-00-3    | --                                         | 21000                                           |
| Chloroform                                              | 67-66-3    | 80                                         | 0.19                                            |
| Chloromethane                                           | 74-87-3    | --                                         | 190                                             |
| Cyclohexane                                             | 110-82-7   | --                                         | 13000                                           |
| Dibromochloromethane                                    | 124-48-1   | 80                                         | 0.15                                            |
| Dibromomethane                                          | 74-95-3    | --                                         | 7.9                                             |
| Dichlorodifluoromethane                                 | 75-71-8    | --                                         | 190                                             |
| Dichloromethane (Methylene chloride)                    | 75-09-2    | 5                                          | 9.9                                             |
| Ethylbenzene                                            | 100-41-4   | 700                                        | 1.3                                             |
| Ethylene dibromide (1,2-Dibromoethane)                  | 106-93-4   | 0.05                                       | 0.0065                                          |
| Hexachlorobutadiene (Hexachloro-1,3-butadiene)          | 87-68-3    | --                                         | 0.26                                            |
| Isopropylbenzene (Cumene)                               | 98-82-8    | --                                         | 390                                             |
| Methyl acetate                                          | 79-20-9    | --                                         | 16000                                           |
| Methyl iodide (Iodomethane)                             | 74-88-4    | --                                         | --                                              |
| Methyl isobutyl ketone (4-Methyl-2-pentanone or (MIBK)) | 108-10-1   | --                                         | 1000                                            |
| Methyl tert-butyl ether (MTBE)                          | 1634-04-4  | --                                         | 12                                              |
| n-Butylbenzene                                          | 104-51-8   | --                                         | 780                                             |
| n-Propylbenzene                                         | 103-65-1   | --                                         | 530                                             |
| o-Xylene                                                | 95-47-6    | --                                         | 190                                             |
| sec-Butylbenzene                                        | 135-98-8   | --                                         | 1600                                            |
| Styrene                                                 | 100-42-5   | 100                                        | 1100                                            |
| tert-Butylbenzene                                       | 98-06-6    | --                                         | 510                                             |
| Tetrachloroethene (PCE)                                 | 127-18-4   | 5                                          | 9.7                                             |
| Toluene                                                 | 108-88-3   | 1000                                       | 860                                             |
| Total xylene (reported, not calculated)                 | 1330-20-7  | 10000                                      | 190                                             |
| Total Xylene                                            | --         | --                                         | --                                              |
| Trichloroethene (TCE)                                   | 79-01-6    | 5                                          | 0.44                                            |
| Trichlorofluoromethane (Fluorotrichloromethane)         | 75-69-4    | --                                         | 1100                                            |
| Vinyl acetate                                           | 108-05-4   | --                                         | 410                                             |
| Vinyl chloride                                          | 75-01-4    | 2                                          | 0.015                                           |

Notes:

Compounds frequently associated with MGP-operations.

'--' indicates not available

CAS = Chemical Abstract Services

EPA = U. S. Environmental Protection Agency

L = liter

MCL = maximum contaminant level

mg = miligram

MGP = manufactured gas plant

ng = nanogram

PRG = preliminary remediation goal

RSL = regional screening level

ug = microgram

References:

EPA, 2013. EPA Regional Screening Levels. November 2013. Available from: [http://www.epa.gov/reg3hwmd/risk/human/rb-concentration\\_table/Generic\\_Tables/docs/master\\_sl\\_table\\_run\\_NOV2013.pdf](http://www.epa.gov/reg3hwmd/risk/human/rb-concentration_table/Generic_Tables/docs/master_sl_table_run_NOV2013.pdf)

**Table 6-6 - Development of Initial PRGs for Sediment**  
Bremerton Gas Works Site  
Bremerton, Washington

| Analyte                                            | CAS Number | SMS Marine Sediment Cleanup Objective (SCO <sup>1</sup> /LAET <sup>2</sup> ) | SMS Marine Cleanup Screening Level (CSL <sup>1</sup> /2LAET <sup>2</sup> ) | EPA Region 5 RCRA Sediment Ecological Screening Levels | EPA Region 3 BTAG Marine Sediment Screening Benchmarks | Effects Range-Low (ERL) | Effects Range-Median (ERM) | Initial PRGs Used for Data Screening |
|----------------------------------------------------|------------|------------------------------------------------------------------------------|----------------------------------------------------------------------------|--------------------------------------------------------|--------------------------------------------------------|-------------------------|----------------------------|--------------------------------------|
|                                                    |            | DOE, 2013                                                                    | DOE, 2013                                                                  | EPA, 2003                                              | EPA, 2006                                              | Long et al., 1995       | Long et al., 1995          |                                      |
| Alkane Isomers (ug/kg)                             |            |                                                                              |                                                                            |                                                        |                                                        |                         |                            |                                      |
| n-Hexane (C6)                                      | 110-54-3   | --                                                                           | --                                                                         | --                                                     | 39.60                                                  | --                      | --                         | 39.6                                 |
| Conventionals (mg/kg)                              |            |                                                                              |                                                                            |                                                        |                                                        |                         |                            |                                      |
| Cyanide, WAD                                       | 57-12-5    | --                                                                           | --                                                                         | --                                                     | 0.1                                                    | --                      | --                         | 0.1                                  |
| Cyanide, total                                     | 57-12-5    | --                                                                           | --                                                                         | 0.0001                                                 | --                                                     | --                      | --                         | 0.0001                               |
| Sulfide                                            | 18496-25-8 | --                                                                           | --                                                                         | --                                                     | 130                                                    | --                      | --                         | 130                                  |
| Metals (mg/kg)                                     |            |                                                                              |                                                                            |                                                        |                                                        |                         |                            |                                      |
| Antimony                                           | 7440-36-0  | --                                                                           | --                                                                         | --                                                     | 2                                                      | --                      | --                         | 2                                    |
| Arsenic                                            | 7440-38-2  | 57                                                                           | 93                                                                         | 9.79                                                   | 7.24                                                   | 8.2                     | 70                         | 57                                   |
| Beryllium                                          | 7440-41-7  | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| Cadmium                                            | 7440-43-9  | 5.1                                                                          | 6.7                                                                        | 0.99                                                   | 0.68                                                   | 1.2                     | 9.6                        | 5.1                                  |
| Chromium                                           | 7440-47-3  | 260                                                                          | 270                                                                        | 43.4                                                   | 52.3                                                   | 81                      | 370                        | 260                                  |
| Chromium III                                       | 16065-83-1 | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| Chromium VI                                        | 18540-29-9 | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| Copper                                             | 7440-50-8  | 390                                                                          | 390                                                                        | 31.6                                                   | 18.7                                                   | 34                      | 270                        | 390                                  |
| Lead                                               | 7439-92-1  | 450                                                                          | 530                                                                        | 35.8                                                   | 30.2                                                   | 46.7                    | 218                        | 450                                  |
| Mercury                                            | 7439-97-6  | 0.41                                                                         | 0.59                                                                       | 0.174                                                  | 0.13                                                   | 0.15                    | 0.71                       | 0.41                                 |
| Nickel                                             | 7440-02-0  | --                                                                           | --                                                                         | 22.7                                                   | 15.9                                                   | 20.9                    | 51.6                       | 20.9                                 |
| Selenium                                           | 7782-49-2  | --                                                                           | --                                                                         | --                                                     | 2                                                      | --                      | --                         | 2                                    |
| Silver                                             | 7440-22-4  | 6.1                                                                          | 6.1                                                                        | 0.5                                                    | 0.73                                                   | 1                       | 3.7                        | 6.1                                  |
| Thallium                                           | 7440-28-0  | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| Zinc                                               | 7440-66-6  | 410                                                                          | 960                                                                        | 121                                                    | 124                                                    | 150                     | 410                        | 410                                  |
| Metals, Organic (ug/kg)                            |            |                                                                              |                                                                            |                                                        |                                                        |                         |                            |                                      |
| Tributyltin                                        | 688-73-3   | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| Polycyclic Aromatic Hydrocarbons (PAHs) (ug/kg)    |            |                                                                              |                                                                            |                                                        |                                                        |                         |                            |                                      |
| 1-Methylnaphthalene                                | 90-12-0    | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| 2-Methylnaphthalene                                | 91-57-6    | 670                                                                          | 670                                                                        | 20.2                                                   | 20.2                                                   | 70                      | 670                        | 670                                  |
| Acenaphthene                                       | 83-32-9    | 500                                                                          | 500                                                                        | 6.71                                                   | 6.71                                                   | 16                      | 500                        | 500                                  |
| Acenaphthylene                                     | 208-96-8   | 1300                                                                         | 1300                                                                       | 5.87                                                   | 5.87                                                   | 44                      | 640                        | 1300                                 |
| Anthracene                                         | 120-12-7   | 960                                                                          | 960                                                                        | 57.2                                                   | 46.9                                                   | 85.3                    | 1100                       | 960                                  |
| Benzo(a)anthracene                                 | 56-55-3    | 1300                                                                         | 1600                                                                       | 108                                                    | 74.8                                                   | 261                     | 1600                       | 1300                                 |
| Benzo(a)pyrene                                     | 50-32-8    | 1600                                                                         | 1600                                                                       | 150                                                    | 88.8                                                   | 430                     | 1600                       | 1600                                 |
| Benzo(b)fluoranthene                               | 205-99-2   | --                                                                           | --                                                                         | 10400                                                  | --                                                     | --                      | --                         | 10400                                |
| Benzo(b,k)fluoranthene                             | --         | --                                                                           | --                                                                         | --                                                     | 27.2                                                   | --                      | --                         | 27.2                                 |
| Benzo(g,h,i)perylene                               | 191-24-2   | 670                                                                          | 720                                                                        | 170                                                    | 170                                                    | --                      | --                         | 670                                  |
| Benzo(j)fluoranthene                               | 205-82-3   | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| Benzo(k)fluoranthene                               | 207-08-9   | --                                                                           | --                                                                         | 240                                                    | 240                                                    | --                      | --                         | 240                                  |
| Chrysene                                           | 218-01-9   | 1400                                                                         | 2800                                                                       | 166                                                    | 108                                                    | 384                     | 2800                       | 1400                                 |
| Dibenzo(a,h)anthracene                             | 53-70-3    | 230                                                                          | 230                                                                        | 33                                                     | 6.22                                                   | 63.4                    | 260                        | 230                                  |
| Fluoranthene                                       | 206-44-0   | 1700                                                                         | 2500                                                                       | 423                                                    | 113                                                    | 600                     | 5100                       | 1700                                 |
| Fluorene                                           | 86-73-7    | 540                                                                          | 540                                                                        | 77.4                                                   | 21.2                                                   | 19                      | 540                        | 540                                  |
| Indeno(1,2,3-c,d)pyrene                            | 193-39-5   | 600                                                                          | 690                                                                        | 200                                                    | 17                                                     | --                      | --                         | 600                                  |
| Naphthalene                                        | 91-20-3    | 2100                                                                         | 2100                                                                       | 176                                                    | 34.6                                                   | 160                     | 2100                       | 2100                                 |
| Phenanthrene                                       | 85-01-8    | 1500                                                                         | 1500                                                                       | 204                                                    | 86.7                                                   | 240                     | 1500                       | 1500                                 |
| Pyrene                                             | 129-00-0   | 2600                                                                         | 3300                                                                       | 195                                                    | 153                                                    | 665                     | 2600                       | 2600                                 |
| Total Benzofluoranthenes (b,j,k)                   | --         | 3200                                                                         | 3600                                                                       | --                                                     | --                                                     | --                      | --                         | 3200                                 |
| Total HPAH                                         | --         | 12000                                                                        | 17000                                                                      | --                                                     | 655                                                    | 1700                    | 9600                       | 12000                                |
| Total LPAH                                         | --         | 5200                                                                         | 5200                                                                       | --                                                     | 312                                                    | 552                     | 3160                       | 5200                                 |
| Total PAH                                          | --         | --                                                                           | --                                                                         | --                                                     | 2900                                                   | 4022                    | 44792                      | 4022                                 |
| Polycyclic Aromatic Hydrocarbons (PAHs) (mg/kg-OC) |            |                                                                              |                                                                            |                                                        |                                                        |                         |                            |                                      |
| 2-Methylnaphthalene                                | 91-57-6    | 38                                                                           | 64                                                                         | --                                                     | --                                                     | --                      | --                         | 38                                   |
| Acenaphthene                                       | 83-32-9    | 16                                                                           | 57                                                                         | --                                                     | --                                                     | --                      | --                         | 16                                   |
| Acenaphthylene                                     | 208-96-8   | 66                                                                           | 66                                                                         | --                                                     | --                                                     | --                      | --                         | 66                                   |
| Anthracene                                         | 120-12-7   | 220                                                                          | 1200                                                                       | --                                                     | --                                                     | --                      | --                         | 220                                  |
| Benzo(a)anthracene                                 | 56-55-3    | 110                                                                          | 270                                                                        | --                                                     | --                                                     | --                      | --                         | 110                                  |
| Benzo(a)pyrene                                     | 50-32-8    | 99                                                                           | 210                                                                        | --                                                     | --                                                     | --                      | --                         | 99                                   |
| Benzo(g,h,i)perylene                               | 191-24-2   | 31                                                                           | 78                                                                         | --                                                     | --                                                     | --                      | --                         | 31                                   |
| Chrysene                                           | 218-01-9   | 110                                                                          | 460                                                                        | --                                                     | --                                                     | --                      | --                         | 110                                  |
| Dibenzo(a,h)anthracene                             | 53-70-3    | 12                                                                           | 33                                                                         | --                                                     | --                                                     | --                      | --                         | 12                                   |
| Fluoranthene                                       | 206-44-0   | 160                                                                          | 1200                                                                       | --                                                     | --                                                     | --                      | --                         | 160                                  |
| Fluorene                                           | 86-73-7    | 23                                                                           | 79                                                                         | --                                                     | --                                                     | --                      | --                         | 23                                   |
| Indeno(1,2,3-c,d)pyrene                            | 193-39-5   | 34                                                                           | 88                                                                         | --                                                     | --                                                     | --                      | --                         | 34                                   |
| Naphthalene                                        | 91-20-3    | 99                                                                           | 170                                                                        | --                                                     | --                                                     | --                      | --                         | 99                                   |
| Phenanthrene                                       | 85-01-8    | 100                                                                          | 480                                                                        | --                                                     | --                                                     | --                      | --                         | 100                                  |
| Pyrene                                             | 129-00-0   | 1000                                                                         | 1400                                                                       | --                                                     | --                                                     | --                      | --                         | 1000                                 |
| Total Benzofluoranthenes (b,j,k)                   | --         | 230                                                                          | 450                                                                        | --                                                     | --                                                     | --                      | --                         | 230                                  |
| Total HPAH                                         | --         | 960                                                                          | 5300                                                                       | --                                                     | --                                                     | --                      | --                         | 960                                  |
| Total LPAH                                         | --         | 370                                                                          | 780                                                                        | --                                                     | --                                                     | --                      | --                         | 370                                  |
| Polychlorinated Biphenyls (PCBs) (ug/kg)           |            |                                                                              |                                                                            |                                                        |                                                        |                         |                            |                                      |
| Aroclor 1016                                       | 12674-11-2 | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| Aroclor 1221                                       | 11104-28-2 | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| Aroclor 1232                                       | 11141-16-5 | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| Aroclor 1242                                       | 53469-21-9 | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| Aroclor 1248                                       | 12672-29-6 | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| Aroclor 1254                                       | 11097-69-1 | --                                                                           | --                                                                         | --                                                     | 63.3                                                   | --                      | --                         | 63.3                                 |
| Aroclor 1260                                       | 11096-82-5 | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| Aroclor 1262                                       | 37324-23-5 | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| Aroclor 1268                                       | 11100-14-4 | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| Total PCB Aroclors                                 | --         | 130                                                                          | 1000                                                                       | 59.8                                                   | 40                                                     | 22.7                    | 180                        | 130                                  |
| Polychlorinated Biphenyls (PCBs) (mg/kg-OC)        |            |                                                                              |                                                                            |                                                        |                                                        |                         |                            |                                      |
| Total PCB Aroclors                                 | --         | 12                                                                           | 65                                                                         | --                                                     | --                                                     | --                      | --                         | 12                                   |
| Semivolatile Organic Compounds (SVOCs)(ug/kg)      |            |                                                                              |                                                                            |                                                        |                                                        |                         |                            |                                      |
| 1,2,4,5-Tetrachlorobenzene                         | 95-94-3    | --                                                                           | --                                                                         | 1252                                                   | 47000                                                  | --                      | --                         | 47000                                |
| 1,2,4-Trichlorobenzene                             | 120-82-1   | 31                                                                           | 51                                                                         | 5062                                                   | 473                                                    | --                      | --                         | 31                                   |
| 1,2-Dichlorobenzene                                | 95-50-1    | 35                                                                           | 50                                                                         | 294                                                    | 989                                                    | --                      | --                         | 35                                   |
| 1,3-Dichlorobenzene                                | 541-73-1   | --                                                                           | --                                                                         | 1315                                                   | 842                                                    | --                      | --                         | 842                                  |
| 1,4-Dichlorobenzene                                | 106-46-7   | 110                                                                          | 110                                                                        | 318                                                    | 460                                                    | --                      | --                         | 110                                  |
| 2,2'-Oxybis (1-chloropropane)                      | 108-60-1   | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| 2,3,4,6-Tetrachlorophenol                          | 58-90-2    | --                                                                           | --                                                                         | 129                                                    | 284                                                    | --                      | --                         | 284                                  |
| 2,4,5-Trichlorophenol                              | 95-95-4    | --                                                                           | --                                                                         | --                                                     | 819                                                    | --                      | --                         | 819                                  |
| 2,4,6-Trichlorophenol                              | 88-06-2    | --                                                                           | --                                                                         | 208                                                    | 2650                                                   | --                      | --                         | 2650                                 |



**Table 6-6 - Development of Initial PRGs for Sediment**  
Bremerton Gas Works Site  
Bremerton, Washington

| Analyte                                           | CAS Number | SMS Marine Sediment Cleanup Objective (SCO <sup>1</sup> /LAET <sup>3</sup> ) | SMS Marine Cleanup Screening Level (CSL <sup>1</sup> /2LAET <sup>3</sup> ) | EPA Region 5 RCRA Sediment Ecological Screening Levels | EPA Region 3 BTAG Marine Sediment Screening Benchmarks | Effects Range-Low (ERL) | Effects Range-Median (ERM) | Initial PRGs Used for Data Screening |
|---------------------------------------------------|------------|------------------------------------------------------------------------------|----------------------------------------------------------------------------|--------------------------------------------------------|--------------------------------------------------------|-------------------------|----------------------------|--------------------------------------|
|                                                   |            | DOE, 2013                                                                    | DOE, 2013                                                                  | EPA, 2003                                              | EPA, 2006                                              | Long et al., 1995       | Long et al., 1995          |                                      |
| 2,4-Dichlorophenol                                | 120-83-2   | --                                                                           | --                                                                         | 81.7                                                   | 117                                                    | --                      | --                         | 117                                  |
| 2,4-Dimethylphenol                                | 105-67-9   | 29                                                                           | 29                                                                         | 304                                                    | 29                                                     | --                      | --                         | 29                                   |
| 2,4-Dinitrophenol                                 | 51-28-5    | --                                                                           | --                                                                         | 6.21                                                   | --                                                     | --                      | --                         | 6.21                                 |
| 2,4-Dinitrotoluene                                | 121-14-2   | --                                                                           | --                                                                         | 14.4                                                   | 41.6                                                   | --                      | --                         | 41.6                                 |
| 2,6-Dinitrotoluene                                | 606-20-2   | --                                                                           | --                                                                         | 39.8                                                   | --                                                     | --                      | --                         | 39.8                                 |
| 2-Chloronaphthalene                               | 91-58-7    | --                                                                           | --                                                                         | 417                                                    | --                                                     | --                      | --                         | 417                                  |
| 2-Chlorophenol                                    | 95-57-8    | --                                                                           | --                                                                         | 31.9                                                   | 344                                                    | --                      | --                         | 344                                  |
| 2-Methylphenol (o-Cresol)                         | 95-48-7    | 63                                                                           | 63                                                                         | 55.4                                                   | --                                                     | --                      | --                         | 63                                   |
| 2-Nitroaniline                                    | 88-74-4    | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| 2-Nitrophenol                                     | 88-75-5    | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| 3,3'-Dichlorobenzidine                            | 91-94-1    | --                                                                           | --                                                                         | 127                                                    | 2060                                                   | --                      | --                         | 2060                                 |
| 3-Methylphenol & 4-Methylphenol (m&p-Cresol)      | 1319-77-3  | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| 3-Methylphenol (m-Cresol)                         | 108-39-4   | --                                                                           | --                                                                         | 52.4                                                   | --                                                     | --                      | --                         | 52.4                                 |
| 3-Nitroaniline                                    | 99-09-2    | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| 4-Bromophenyl-phenyl ether                        | 101-55-3   | --                                                                           | --                                                                         | 1550                                                   | 1230                                                   | --                      | --                         | 1230                                 |
| 4-Chloro-3-methylphenol                           | 59-50-7    | --                                                                           | --                                                                         | 388                                                    | --                                                     | --                      | --                         | 388                                  |
| 4-Chloroaniline                                   | 106-47-8   | --                                                                           | --                                                                         | 146                                                    | --                                                     | --                      | --                         | 146                                  |
| 4-Methylphenol (p-Cresol)                         | 106-44-5   | 670                                                                          | 670                                                                        | 20.2                                                   | 670                                                    | --                      | --                         | 670                                  |
| 4-Nitroaniline                                    | 100-01-6   | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| 4-Nitrophenol                                     | 100-02-7   | --                                                                           | --                                                                         | 13.3                                                   | --                                                     | --                      | --                         | 13.3                                 |
| Acetophenone                                      | 98-86-2    | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| Aniline                                           | 62-53-3    | --                                                                           | --                                                                         | 0.31                                                   | --                                                     | --                      | --                         | 0.31                                 |
| Atrazine                                          | 1912-24-9  | --                                                                           | --                                                                         | --                                                     | 6.62                                                   | --                      | --                         | 6.62                                 |
| Benzaldehyde                                      | 100-52-7   | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| Benzidine                                         | 92-87-5    | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| Benzoic acid                                      | 65-85-0    | 650                                                                          | 650                                                                        | --                                                     | 650                                                    | --                      | --                         | 650                                  |
| Benzyl alcohol                                    | 100-51-6   | 57                                                                           | 73                                                                         | 1.04                                                   | --                                                     | --                      | --                         | 57                                   |
| Biphenyl (1,1'-Biphenyl)                          | 92-52-4    | --                                                                           | --                                                                         | --                                                     | 1220                                                   | --                      | --                         | 1220                                 |
| bis(2-Chloroethoxy)methane                        | 111-91-1   | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| bis(2-Chloroethyl)ether                           | 111-44-4   | --                                                                           | --                                                                         | 3520                                                   | --                                                     | --                      | --                         | 3520                                 |
| bis(2-Ethylhexyl)phthalate                        | 117-81-7   | 1300                                                                         | 3100                                                                       | 182                                                    | 182                                                    | --                      | --                         | 1300                                 |
| Butylbenzyl phthalate                             | 85-68-7    | 63                                                                           | 900                                                                        | 1970                                                   | 16800                                                  | --                      | --                         | 63                                   |
| Caprolactam                                       | 105-60-2   | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| Dibenzofuran                                      | 132-64-9   | 540                                                                          | 540                                                                        | 449                                                    | 7300                                                   | --                      | --                         | 540                                  |
| Diethyl phthalate                                 | 84-66-2    | 200                                                                          | 1200                                                                       | 295                                                    | 218                                                    | --                      | --                         | 200                                  |
| Dimethyl phthalate                                | 131-11-3   | 71                                                                           | 160                                                                        | --                                                     | --                                                     | --                      | --                         | 71                                   |
| Di-n-butyl phthalate                              | 84-74-2    | 1400                                                                         | 5100                                                                       | 1114                                                   | 1160                                                   | --                      | --                         | 1400                                 |
| Dinitro-o-cresol (4,6-Dinitro-2-methylphenol)     | 534-52-1   | --                                                                           | --                                                                         | 104                                                    | --                                                     | --                      | --                         | 104                                  |
| Di-n-octyl phthalate                              | 117-84-0   | 6200                                                                         | 6200                                                                       | 40600                                                  | --                                                     | --                      | --                         | 6200                                 |
| Hexachlorobenzene                                 | 118-74-1   | 22                                                                           | 70                                                                         | 20                                                     | 20                                                     | --                      | --                         | 22                                   |
| Hexachlorocyclopentadiene                         | 77-47-4    | --                                                                           | --                                                                         | 901                                                    | 139                                                    | --                      | --                         | 139                                  |
| Hexachloroethane                                  | 67-72-1    | --                                                                           | --                                                                         | 584                                                    | 804                                                    | --                      | --                         | 804                                  |
| Isophorone                                        | 78-59-1    | --                                                                           | --                                                                         | 432                                                    | --                                                     | --                      | --                         | 432                                  |
| Nitrobenzene                                      | 98-95-3    | --                                                                           | --                                                                         | 145                                                    | --                                                     | --                      | --                         | 145                                  |
| n-Nitrosodimethylamine                            | 62-75-9    | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| n-Nitrosodi-n-propylamine                         | 621-64-7   | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| n-Nitrosodiphenylamine                            | 86-30-6    | 28                                                                           | 40                                                                         | --                                                     | 422000                                                 | --                      | --                         | 28                                   |
| Pentachlorophenol                                 | 87-86-5    | 360                                                                          | 690                                                                        | 23000                                                  | 7970                                                   | --                      | --                         | 360                                  |
| Phenol                                            | 108-95-2   | 420                                                                          | 1200                                                                       | 49.1                                                   | 420                                                    | --                      | --                         | 420                                  |
| Semivolatile Organic Compounds (SVOCs) (mg/kg-OC) |            |                                                                              |                                                                            |                                                        |                                                        |                         |                            |                                      |
| 1,2,4-Trichlorobenzene                            | 120-82-1   | 0.81                                                                         | 1.8                                                                        | --                                                     | --                                                     | --                      | --                         | 0.81                                 |
| 1,2-Dichlorobenzene                               | 95-50-1    | 2.3                                                                          | 2.3                                                                        | --                                                     | --                                                     | --                      | --                         | 2.3                                  |
| 1,4-Dichlorobenzene                               | 106-46-7   | 3.1                                                                          | 9                                                                          | --                                                     | --                                                     | --                      | --                         | 3.1                                  |
| bis(2-Ethylhexyl)phthalate                        | 117-81-7   | 47                                                                           | 78                                                                         | --                                                     | --                                                     | --                      | --                         | 47                                   |
| Butylbenzyl phthalate                             | 85-68-7    | 4.9                                                                          | 64                                                                         | --                                                     | --                                                     | --                      | --                         | 4.9                                  |
| Dibenzofuran                                      | 132-64-9   | 15                                                                           | 58                                                                         | --                                                     | --                                                     | --                      | --                         | 15                                   |
| Diethyl phthalate                                 | 84-66-2    | 61                                                                           | 110                                                                        | --                                                     | --                                                     | --                      | --                         | 61                                   |
| Dimethyl phthalate                                | 131-11-3   | 53                                                                           | 53                                                                         | --                                                     | --                                                     | --                      | --                         | 53                                   |
| Di-n-butyl phthalate                              | 84-74-2    | 220                                                                          | 1700                                                                       | --                                                     | --                                                     | --                      | --                         | 220                                  |
| Di-n-octyl phthalate                              | 117-84-0   | 58                                                                           | 4500                                                                       | --                                                     | --                                                     | --                      | --                         | 58                                   |
| Hexachlorobenzene                                 | 118-74-1   | 0.38                                                                         | 2.3                                                                        | --                                                     | --                                                     | --                      | --                         | 0.38                                 |
| n-Nitrosodiphenylamine                            | 86-30-6    | 11                                                                           | 11                                                                         | --                                                     | --                                                     | --                      | --                         | 11                                   |
| Volatile Organic Compounds (VOCs) (ug/kg)         |            |                                                                              |                                                                            |                                                        |                                                        |                         |                            |                                      |
| 1,1,1,2-Tetrachloroethane                         | 630-20-6   | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| 1,1,1-Trichloroethane                             | 71-55-6    | --                                                                           | --                                                                         | 213                                                    | 856                                                    | --                      | --                         | 856                                  |
| 1,1,2,2-Tetrachloroethane                         | 79-34-5    | --                                                                           | --                                                                         | 850                                                    | 202                                                    | --                      | --                         | 202                                  |
| 1,1,2-Trichloroethane                             | 79-00-5    | --                                                                           | --                                                                         | 518                                                    | 570                                                    | --                      | --                         | 570                                  |
| 1,1,2-Trichlorotrifluoroethane (Freon 113)        | 76-13-1    | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| 1,1-Dichloroethane                                | 75-34-3    | --                                                                           | --                                                                         | 0.575                                                  | --                                                     | --                      | --                         | 0.575                                |
| 1,1-Dichloroethene                                | 75-35-4    | --                                                                           | --                                                                         | 19.4                                                   | 2780                                                   | --                      | --                         | 2780                                 |
| 1,2,3-Trichlorobenzene                            | 87-61-6    | --                                                                           | --                                                                         | --                                                     | 858                                                    | --                      | --                         | 858                                  |
| 1,2,3-Trichloropropane                            | 96-18-4    | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| 1,2,4-Trimethylbenzene                            | 95-63-6    | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| 1,2-Dibromo-3-chloropropane                       | 96-12-8    | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| 1,2-Dichloroethane                                | 107-06-2   | --                                                                           | --                                                                         | 260                                                    | --                                                     | --                      | --                         | 260                                  |
| 1,2-Dichloroethene, cis-                          | 156-59-2   | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| 1,2-Dichloroethene, trans-                        | 156-60-5   | --                                                                           | --                                                                         | 654                                                    | 1050                                                   | --                      | --                         | 1050                                 |
| 1,2-Dichloropropane                               | 78-87-5    | --                                                                           | --                                                                         | 333                                                    | --                                                     | --                      | --                         | 333                                  |
| 1,3,5-Trimethylbenzene (Mesitylene)               | 108-67-8   | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| 1,3-Dichloropropane                               | 142-28-9   | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| 1,3-Dichloropropene, cis-                         | 10061-01-5 | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| 1,3-Dichloropropene, trans-                       | 10061-02-6 | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| 1,4-Dichloro-2-butene, trans-                     | 110-57-6   | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| 1,4-Dioxane                                       | 123-91-1   | --                                                                           | --                                                                         | 119                                                    | --                                                     | --                      | --                         | 119                                  |
| 2-Butanone (MEK)                                  | 78-93-3    | --                                                                           | --                                                                         | 42.4                                                   | --                                                     | --                      | --                         | 42.4                                 |
| 2-Chlorotoluene                                   | 95-49-8    | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| 2-Hexanone (Methyl butyl ketone)                  | 591-78-6   | --                                                                           | --                                                                         | 58.2                                                   | --                                                     | --                      | --                         | 58.2                                 |
| 4-Chlorotoluene                                   | 106-43-4   | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| 4-Isopropyltoluene (4-Cymene)                     | 99-87-6    | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| Acetone                                           | 67-64-1    | --                                                                           | --                                                                         | 9.9                                                    | --                                                     | --                      | --                         | 9.9                                  |
| Acrolein                                          | 107-02-8   | --                                                                           | --                                                                         | 0.00152                                                | --                                                     | --                      | --                         | 0.00152                              |
| Acrylonitrile                                     | 107-13-1   | --                                                                           | --                                                                         | 1.2                                                    | --                                                     | --                      | --                         | 1.2                                  |

**Table 6-6 - Development of Initial PRGs for Sediment**  
Bremerton Gas Works Site  
Bremerton, Washington

| Analyte                                                 | CAS Number | SMS Marine Sediment Cleanup Objective (SCO <sup>1</sup> /LAET <sup>2</sup> ) | SMS Marine Cleanup Screening Level (CSL <sup>1</sup> /2LAET <sup>2</sup> ) | EPA Region 5 RCRA Sediment Ecological Screening Levels | EPA Region 3 BTAG Marine Sediment Screening Benchmarks | Effects Range-Low (ERL) | Effects Range-Median (ERM) | Initial PRGs Used for Data Screening |
|---------------------------------------------------------|------------|------------------------------------------------------------------------------|----------------------------------------------------------------------------|--------------------------------------------------------|--------------------------------------------------------|-------------------------|----------------------------|--------------------------------------|
|                                                         |            | DOE, 2013                                                                    | DOE, 2013                                                                  | EPA, 2003                                              | EPA, 2006                                              | Long et al., 1995       | Long et al., 1995          |                                      |
| Benzene                                                 | 71-43-2    | --                                                                           | --                                                                         | 142                                                    | 137                                                    | --                      | --                         | 137                                  |
| Bromobenzene                                            | 108-86-1   | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| Bromochloromethane                                      | 74-97-5    | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| Bromodichloromethane                                    | 75-27-4    | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| Bromoform (Tribromomethane)                             | 75-25-2    | --                                                                           | --                                                                         | 492                                                    | 1310                                                   | --                      | --                         | 1310                                 |
| Bromomethane (Methyl bromide)                           | 74-83-9    | --                                                                           | --                                                                         | 1.37                                                   | --                                                     | --                      | --                         | 1.37                                 |
| Carbon disulfide                                        | 75-15-0    | --                                                                           | --                                                                         | 23.9                                                   | 0.851                                                  | --                      | --                         | 0.851                                |
| Carbon tetrachloride (Tetrachloromethane)               | 56-23-5    | --                                                                           | --                                                                         | 1450                                                   | 7240                                                   | --                      | --                         | 7240                                 |
| Chlorobenzene                                           | 108-90-7   | --                                                                           | --                                                                         | 291                                                    | 162                                                    | --                      | --                         | 162                                  |
| Chloroethane                                            | 75-00-3    | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| Chloroform                                              | 67-66-3    | --                                                                           | --                                                                         | 121                                                    | --                                                     | --                      | --                         | 121                                  |
| Chloromethane                                           | 74-87-3    | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| Cyclohexane                                             | 110-82-7   | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| Dibromochloromethane                                    | 124-48-1   | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| Dibromomethane                                          | 74-95-3    | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| Dichlorodifluoromethane                                 | 75-71-8    | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| Dichloromethane (Methylene chloride)                    | 75-09-2    | --                                                                           | --                                                                         | 159                                                    | --                                                     | --                      | --                         | 159                                  |
| Ethylbenzene                                            | 100-41-4   | --                                                                           | --                                                                         | 175                                                    | 305                                                    | --                      | --                         | 305                                  |
| Ethylene dibromide (1,2-Dibromoethane)                  | 106-93-4   | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| Hexachlorobutadiene (Hexachloro-1,3-butadiene)          | 87-68-3    | 11                                                                           | 120                                                                        | 26.5                                                   | --                                                     | --                      | --                         | 11                                   |
| Isopropylbenzene (Cumene)                               | 98-82-8    | --                                                                           | --                                                                         | --                                                     | 86                                                     | --                      | --                         | 86                                   |
| Methyl acetate                                          | 79-20-9    | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| Methyl iodide (Iodomethane)                             | 74-88-4    | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| Methyl isobutyl ketone (4-Methyl-2-pentanone or (MIBK)) | 108-10-1   | --                                                                           | --                                                                         | 25.1                                                   | --                                                     | --                      | --                         | 25.1                                 |
| Methyl tert-butyl ether (MTBE)                          | 1634-04-4  | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| n-Butylbenzene                                          | 104-51-8   | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| n-Propylbenzene                                         | 103-65-1   | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| o-Xylene                                                | 95-47-6    | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| sec-Butylbenzene                                        | 135-98-8   | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| Styrene                                                 | 100-42-5   | --                                                                           | --                                                                         | 254                                                    | 7070                                                   | --                      | --                         | 7070                                 |
| tert-Butylbenzene                                       | 98-06-6    | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| Tetrachloroethene (PCE)                                 | 127-18-4   | --                                                                           | --                                                                         | 990                                                    | 190                                                    | --                      | --                         | 190                                  |
| Toluene                                                 | 108-88-3   | --                                                                           | --                                                                         | 1220                                                   | 1090                                                   | --                      | --                         | 1090                                 |
| Total xylene (reported, not calculated)                 | 1330-20-7  | --                                                                           | --                                                                         | 433                                                    | --                                                     | --                      | --                         | 433                                  |
| Total Xylene                                            | --         | --                                                                           | --                                                                         | 433                                                    | --                                                     | --                      | --                         | 433                                  |
| Trichloroethene (TCE)                                   | 79-01-6    | --                                                                           | --                                                                         | 112                                                    | 8950                                                   | --                      | --                         | 8950                                 |
| Trichlorofluoromethane (Fluorotrichloromethane)         | 75-69-4    | --                                                                           | --                                                                         | --                                                     | --                                                     | --                      | --                         | --                                   |
| Vinyl acetate                                           | 108-05-4   | --                                                                           | --                                                                         | 13                                                     | --                                                     | --                      | --                         | 13                                   |
| Vinyl chloride                                          | 75-01-4    | --                                                                           | --                                                                         | 202                                                    | --                                                     | --                      | --                         | 202                                  |
| <b>Volatile Organic Compounds (VOCs) (mg/kg-OC)</b>     |            |                                                                              |                                                                            |                                                        |                                                        |                         |                            |                                      |
| Hexachlorobutadiene (Hexachloro-1,3-butadiene)          | 87-68-3    | 3.9                                                                          | 6.2                                                                        | --                                                     | --                                                     | --                      | --                         | 3.9                                  |

Notes:

Compounds frequently associated with MGP-operations

- '--' indicates not available
- 1 = This criteria will be used when total organic carbon (TOC) is between 0.5% to 5%.
- 2 = This criteria will be used when total organic carbon (TOC) is less than 0.5% or greater than 5%.
- 2LAET = Second Lowest Apparent Effects Threshold
- BTAG = Biological Technical Assistance Group
- CAS = Chemical Abstract Services
- CSL = Cleanup Screening Level
- DOE = Washington Department of Ecology
- EPA = United States Environmental Protection Agency
- kg = kilogram
- LAET = Lowest Apparent Effects Threshold
- mg = milligram
- MGP = Manufactured Gas Plant
- ng = nanogram
- OC = organic carbon
- PRG = preliminary remediation goal
- RCRA = Resource Conservation and Recovery Act
- SCO = Sediment Cleanup Objective
- SMS = Sediment Management Standards
- ug = microgram

References:

Ecology, 2013. Sediment Management Standards, Chapter 173-204 WAC: Final Rule February 22, 2013. September 1, 2013.

DOE, 1998. Puget Sound Estuary Program CSL/2LAET and SQS (SCO)/LAET. Available at: [http://www.ecy.wa.gov/programs/tcp/smu/SQS\\_CSL\\_DW%20for%20Website%20CORRECTED%2014JUN2013%20\(2\).pdf](http://www.ecy.wa.gov/programs/tcp/smu/SQS_CSL_DW%20for%20Website%20CORRECTED%2014JUN2013%20(2).pdf)

EPA, 2003. EPA Region 5 Resource Conservation Recovery Act (RCRA) Ecological Screening Levels. August 22, 2003.

EPA, 2006. EPA Region 3 Biological Technical Assistance Group (BTAG) Screening Benchmarks. Marine Sediment Benchmarks. July 2006.

Long, E.R, D. MacDonald, S. Smith, and F. Calder, 1995. Incidence of adverse biological effects within ranges of chemical concentrations in marine and estuarine sediments. Environmental Management 1991:81-97.



Table 6-7 - Development of Initial PRGs for Surface Water  
Bremerton Gas Works Site  
Bremerton, Washington

| Analyte                                        | CAS Number | EPA Region 3 BTAG<br>Marine Water Screening<br>Benchmarks | National Recommended<br>Water Quality Criteria -<br>Aquatic Life Criteria -<br>Saltwater CCC (chronic) <sup>1</sup> | National Recommended<br>Water Quality Criteria -<br>Aquatic Life Criteria -<br>Saltwater CMC (acute) <sup>1</sup> | EPA Region 5 RCRA -<br>Ecological Screening<br>Levels - Water | National Recommended<br>Water Quality Criteria -<br>Human Health for the<br>Consumption of<br>Organisms | Initial PRGs Used<br>for Data Screening |
|------------------------------------------------|------------|-----------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------|---------------------------------------------------------------------------------------------------------|-----------------------------------------|
|                                                |            | EPA, 2006                                                 | EPA, 2013                                                                                                           | EPA, 2013                                                                                                         | EPA, 2003                                                     | EPA, 2013                                                                                               |                                         |
| Alkane Isomers (ug/L)                          |            |                                                           |                                                                                                                     |                                                                                                                   |                                                               |                                                                                                         |                                         |
| n-Hexane (C6)                                  | 110-54-3   | 0.58                                                      | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | 0.58                                    |
| Conventionals (mg/L)                           |            |                                                           |                                                                                                                     |                                                                                                                   |                                                               |                                                                                                         |                                         |
| Cyanide, free                                  | 57-12-5    | 0.001                                                     | 0.001                                                                                                               | 0.001                                                                                                             | --                                                            | --                                                                                                      | 0.001                                   |
| Cyanide, total                                 | 57-12-5    | --                                                        | --                                                                                                                  | --                                                                                                                | 0.0052                                                        | 0.14                                                                                                    | 0.14                                    |
| Sulfide                                        | 18496-25-8 | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| Metals (ug/L)                                  |            |                                                           |                                                                                                                     |                                                                                                                   |                                                               |                                                                                                         |                                         |
| Antimony                                       | 7440-36-0  | 500                                                       | --                                                                                                                  | --                                                                                                                | 80                                                            | 640                                                                                                     | 640                                     |
| Arsenic                                        | 7440-38-2  | 12.5 (a)                                                  | 36                                                                                                                  | 69                                                                                                                | 148                                                           | 0.14                                                                                                    | 0.14                                    |
| Beryllium                                      | 7440-41-7  | 0.66                                                      | --                                                                                                                  | --                                                                                                                | 3.6                                                           | --                                                                                                      | 0.66                                    |
| Cadmium                                        | 7440-43-9  | 0.12 (a)                                                  | 8.8                                                                                                                 | 40                                                                                                                | 0.15                                                          | --                                                                                                      | 8.8                                     |
| Chromium                                       | 7440-47-3  | 57.5                                                      | --                                                                                                                  | --                                                                                                                | 42                                                            | --                                                                                                      | 57.5                                    |
| Chromium III                                   | 16065-83-1 | 56 (a)                                                    | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | 56                                      |
| Chromium VI                                    | 18540-29-9 | 1.5 (a)                                                   | 50                                                                                                                  | 1100                                                                                                              | --                                                            | --                                                                                                      | 50                                      |
| Copper                                         | 7440-50-8  | 3.1                                                       | 3.1                                                                                                                 | 4.8                                                                                                               | 1.58                                                          | --                                                                                                      | 3.1                                     |
| Lead                                           | 7439-92-1  | 8.1                                                       | 8.1                                                                                                                 | 210                                                                                                               | 1.17                                                          | --                                                                                                      | 8.1                                     |
| Mercury                                        | 7439-97-6  | 0.016 (a)                                                 | 0.94                                                                                                                | 1.8                                                                                                               | 0.0013                                                        | --                                                                                                      | 0.94                                    |
| Nickel                                         | 7440-02-0  | 8.2                                                       | 8.2                                                                                                                 | 74                                                                                                                | 28.9                                                          | 4600                                                                                                    | 8.2                                     |
| Selenium                                       | 7782-49-2  | 71                                                        | 71                                                                                                                  | 290                                                                                                               | 5                                                             | 4200                                                                                                    | 71                                      |
| Silver                                         | 7440-22-4  | 0.23                                                      | --                                                                                                                  | 1.9                                                                                                               | 0.12                                                          | --                                                                                                      | 0.23                                    |
| Thallium                                       | 7440-28-0  | 21.3                                                      | --                                                                                                                  | --                                                                                                                | 10                                                            | 0.47                                                                                                    | 0.47                                    |
| Zinc                                           | 7440-66-6  | 81                                                        | 81                                                                                                                  | 90                                                                                                                | 65.7                                                          | 26000                                                                                                   | 81                                      |
| Metals, Organic (ug/L)                         |            |                                                           |                                                                                                                     |                                                                                                                   |                                                               |                                                                                                         |                                         |
| Tributyltin                                    | 688-73-3   | 0.001 (a)                                                 | 0.0074                                                                                                              | 0.42                                                                                                              | --                                                            | --                                                                                                      | 0.0074                                  |
| Polycyclic Aromatic Hydrocarbons (PAHs) (ug/L) |            |                                                           |                                                                                                                     |                                                                                                                   |                                                               |                                                                                                         |                                         |
| 1-Methylnaphthalene                            | 90-12-0    | 2.1                                                       | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | 2.1                                     |
| 2-Methylnaphthalene                            | 91-57-6    | 4.2                                                       | --                                                                                                                  | --                                                                                                                | 330                                                           | --                                                                                                      | 4.2                                     |
| Acenaphthene                                   | 83-32-9    | 6.6                                                       | --                                                                                                                  | --                                                                                                                | 38                                                            | 990                                                                                                     | 990                                     |
| Acenaphthylene                                 | 208-96-8   | --                                                        | --                                                                                                                  | --                                                                                                                | 4840                                                          | --                                                                                                      | 4840                                    |
| Anthracene                                     | 120-12-7   | 0.18                                                      | --                                                                                                                  | --                                                                                                                | 0.035                                                         | 40000                                                                                                   | 40000                                   |
| Benzo(a)anthracene                             | 56-55-3    | 0.018                                                     | --                                                                                                                  | --                                                                                                                | 0.025                                                         | 0.018                                                                                                   | 0.018                                   |
| Benzo(a)pyrene                                 | 50-32-8    | 0.015                                                     | --                                                                                                                  | --                                                                                                                | 0.014                                                         | 0.018                                                                                                   | 0.018                                   |
| Benzo(b)fluoranthene                           | 205-99-2   | --                                                        | --                                                                                                                  | --                                                                                                                | 9.07                                                          | 0.018                                                                                                   | 0.018                                   |
| Benzo(b,k)fluoranthene                         | --         | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| Benzo(g,h,i)perylene                           | 191-24-2   | --                                                        | --                                                                                                                  | --                                                                                                                | 7.64                                                          | --                                                                                                      | 7.64                                    |
| Benzo(j)fluoranthene                           | 205-82-3   | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| Benzo(k)fluoranthene                           | 207-08-9   | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | 0.018                                                                                                   | 0.018                                   |
| Chrysene                                       | 218-01-9   | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | 0.018                                                                                                   | 0.018                                   |
| Dibenzo(a,h)anthracene                         | 53-70-3    | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | 0.018                                                                                                   | 0.018                                   |
| Fluoranthene                                   | 206-44-0   | 1.6                                                       | --                                                                                                                  | --                                                                                                                | 1.9                                                           | 140                                                                                                     | 140                                     |
| Fluorene                                       | 86-73-7    | 2.5                                                       | --                                                                                                                  | --                                                                                                                | 19                                                            | 5300                                                                                                    | 5300                                    |
| Indeno(1,2,3-c,d)pyrene                        | 193-39-5   | --                                                        | --                                                                                                                  | --                                                                                                                | 4.31                                                          | 0.018                                                                                                   | 0.018                                   |
| Naphthalene                                    | 91-20-3    | 1.4 (a)                                                   | --                                                                                                                  | --                                                                                                                | 13                                                            | --                                                                                                      | 13                                      |
| Phenanthrene                                   | 85-01-8    | 1.5                                                       | --                                                                                                                  | --                                                                                                                | 3.6                                                           | --                                                                                                      | 1.5                                     |
| Pyrene                                         | 129-00-0   | 0.24                                                      | --                                                                                                                  | --                                                                                                                | 0.3                                                           | 4000                                                                                                    | 4000                                    |
| Total Benzo(a)fluoranthenes (b,j,k)            | --         | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| Total HPAH                                     | --         | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| Total LPAH                                     | --         | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| Total PAH                                      | --         | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| Polychlorinated Biphenyls (PCBs) (ug/L)        |            |                                                           |                                                                                                                     |                                                                                                                   |                                                               |                                                                                                         |                                         |
|                                                | 12674-11-2 | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| Aroclor 1221                                   | 11104-28-2 | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| Aroclor 1232                                   | 11141-16-5 | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| Aroclor 1242                                   | 53469-21-9 | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| Aroclor 1248                                   | 12672-29-6 | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| Aroclor 1254                                   | 11097-69-1 | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| Aroclor 1260                                   | 11096-82-5 | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| Aroclor 1262                                   | 37324-23-5 | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| Aroclor 1268                                   | 11100-14-4 | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| Semivolatile Organic Carbons (SVOCs) (ug/L)    |            |                                                           |                                                                                                                     |                                                                                                                   |                                                               |                                                                                                         |                                         |
| 1,2,4,5-Tetrachlorobenzene                     | 95-94-3    | 129                                                       | --                                                                                                                  | --                                                                                                                | 3                                                             | 1.1                                                                                                     | 1.1                                     |
| 1,2,4-Trichlorobenzene                         | 120-82-1   | 5.4 (a)                                                   | --                                                                                                                  | --                                                                                                                | 30                                                            | 70                                                                                                      | 70                                      |
| 1,2-Dichlorobenzene                            | 95-50-1    | 42 (a)                                                    | --                                                                                                                  | --                                                                                                                | 14                                                            | 1300                                                                                                    | 1300                                    |
| 1,3-Dichlorobenzene                            | 541-73-1   | 28.5                                                      | --                                                                                                                  | --                                                                                                                | 38                                                            | 960                                                                                                     | 960                                     |
| 1,4-Dichlorobenzene                            | 106-46-7   | 19.9                                                      | --                                                                                                                  | --                                                                                                                | 9.4                                                           | 190                                                                                                     | 190                                     |
| 2,2'-Oxybis (1-chloropropane)                  | 108-60-1   | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | 65000                                                                                                   | 65000                                   |
| 2,3,4,6-Tetrachlorophenol                      | 58-90-2    | 1.2                                                       | --                                                                                                                  | --                                                                                                                | 1.2                                                           | --                                                                                                      | 1.2                                     |
| 2,4,5-Trichlorophenol                          | 95-95-4    | 12                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | 12                                      |
| 2,4,6-Trichlorophenol                          | 88-06-2    | 61                                                        | --                                                                                                                  | --                                                                                                                | 4.9                                                           | 2.4                                                                                                     | 2.4                                     |
| 2,4-Dichlorophenol                             | 120-83-2   | 11                                                        | --                                                                                                                  | --                                                                                                                | 11                                                            | 290                                                                                                     | 290                                     |
| 2,4-Dimethylphenol                             | 105-67-9   | --                                                        | --                                                                                                                  | --                                                                                                                | 100                                                           | 850                                                                                                     | 850                                     |
| 2,4-Dinitrophenol                              | 51-28-5    | 48.5                                                      | --                                                                                                                  | --                                                                                                                | 19                                                            | 5300                                                                                                    | 5300                                    |
| 2,4-Dinitrotoluene                             | 121-14-2   | 44                                                        | --                                                                                                                  | --                                                                                                                | 44                                                            | 3.4                                                                                                     | 3.4                                     |
| 2,6-Dinitrotoluene                             | 606-20-2   | 81                                                        | --                                                                                                                  | --                                                                                                                | 81                                                            | --                                                                                                      | 81                                      |
| 2-Chloronaphthalene                            | 91-58-7    | --                                                        | --                                                                                                                  | --                                                                                                                | 0.396                                                         | 1600                                                                                                    | 1600                                    |
| 2-Chlorophenol                                 | 95-57-8    | 265                                                       | --                                                                                                                  | --                                                                                                                | 24                                                            | 150                                                                                                     | 150                                     |
| 2-Methylphenol (o-Cresol)                      | 95-48-7    | 1020                                                      | --                                                                                                                  | --                                                                                                                | 67                                                            | --                                                                                                      | 1020                                    |
| 2-Nitroaniline                                 | 88-74-4    | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| 2-Nitrophenol                                  | 88-75-5    | 2940                                                      | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | 2940                                    |
| 3,3'-Dichlorobenzidine                         | 91-94-1    | 73                                                        | --                                                                                                                  | --                                                                                                                | 4.5                                                           | 0.028                                                                                                   | 0.028                                   |
| 3-Methylphenol & 4-Methylphenol (m&p-Cresol)   | 1319-77-3  | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| 3-Methylphenol (m-Cresol)                      | 108-39-4   | --                                                        | --                                                                                                                  | --                                                                                                                | 62                                                            | --                                                                                                      | 62                                      |
| 3-Nitroaniline                                 | 99-09-2    | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| 4-Bromophenyl-phenyl ether                     | 101-55-3   | 1.5                                                       | --                                                                                                                  | --                                                                                                                | 1.5                                                           | --                                                                                                      | 1.5                                     |
| 4-Chloro-3-methylphenol                        | 59-50-7    | --                                                        | --                                                                                                                  | --                                                                                                                | 34.8                                                          | --                                                                                                      | 34.8                                    |
| 4-Chloroaniline                                | 106-47-8   | 232                                                       | --                                                                                                                  | --                                                                                                                | 232                                                           | --                                                                                                      | 232                                     |
| 4-Methylphenol (p-Cresol)                      | 106-44-5   | 543                                                       | --                                                                                                                  | --                                                                                                                | 25                                                            | --                                                                                                      | 543                                     |
| 4-Nitroaniline                                 | 100-01-6   | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| 4-Nitrophenol                                  | 100-02-7   | 71.7                                                      | --                                                                                                                  | --                                                                                                                | 60                                                            | --                                                                                                      | 71.7                                    |
| Acetophenone                                   | 98-86-2    | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| Aniline                                        | 62-53-3    | 2.2                                                       | --                                                                                                                  | --                                                                                                                | 4.1                                                           | --                                                                                                      | 2.2                                     |
| Atrazine                                       | 1912-24-9  | 1.8                                                       | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | 1.8                                     |
| Benzaldehyde                                   | 100-52-7   | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| Benzidine                                      | 92-87-5    | 3.9                                                       | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | 3.9                                     |
| Benzoic acid                                   | 65-85-0    | 42                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | 42                                      |
| Benzyl alcohol                                 | 100-51-6   | 8.6                                                       | --                                                                                                                  | --                                                                                                                | 8.6                                                           | --                                                                                                      | 8.6                                     |
| Biphenyl (1,1'-Biphenyl)                       | 92-52-4    | 14                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | 14                                      |
| bis(2-Chloroethoxy)methane                     | 111-91-1   | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| bis(2-Chloroethyl)ether                        | 111-44-4   | --                                                        | --                                                                                                                  | --                                                                                                                | 19000                                                         | 0.53                                                                                                    | 0.53                                    |
| bis(2-Ethylhexyl)phthalate                     | 117-81-7   | 16                                                        | --                                                                                                                  | --                                                                                                                | 0.3                                                           | 2.2                                                                                                     | 2.2                                     |
| Butylbenzyl phthalate                          | 85-68-7    | 29.4                                                      | --                                                                                                                  | --                                                                                                                | 23                                                            | 1900                                                                                                    | 1900                                    |
| Caprolactam                                    | 105-60-2   | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| Dibenzofuran                                   | 132-64-9   | 65                                                        | --                                                                                                                  | --                                                                                                                | 4                                                             | --                                                                                                      | 65                                      |
| Diethyl phthalate                              | 84-66-2    | 75.9                                                      | --                                                                                                                  | --                                                                                                                | 110                                                           | 44000                                                                                                   | 44000                                   |
| Dimethyl phthalate                             | 131-11-3   | 580                                                       | --                                                                                                                  | --                                                                                                                | --                                                            | 1100000                                                                                                 | 1100000                                 |
| Di-n-butyl phthalate                           | 84-74-2    | 3.4                                                       | --                                                                                                                  | --                                                                                                                | 9.7                                                           | 4500                                                                                                    | 4500                                    |
| Dinitro-o-cresol (4,6-Dinitro-2-methylphenol)  | 534-52-1   | --                                                        | --                                                                                                                  | --                                                                                                                | 23                                                            | 280                                                                                                     | 280                                     |
| Di-n-octyl phthalate                           | 117-84-0   | 22                                                        | --                                                                                                                  | --                                                                                                                | 30                                                            | --                                                                                                      | 22                                      |
| Hexachlorobenzene                              | 118-74-1   | 0.0003                                                    | --                                                                                                                  | --                                                                                                                | 0.0003                                                        | 0.00029                                                                                                 | 0.00029                                 |
| Hexachlorocyclopentadiene                      | 77-47-4    | 0.07                                                      | --                                                                                                                  | --                                                                                                                | 77                                                            | 1100                                                                                                    | 1100                                    |
| Hexachloroethane                               | 67-72-1    | 9.4                                                       | --                                                                                                                  | --                                                                                                                | 8                                                             | 3.3                                                                                                     | 3.3                                     |
| Isophorone                                     | 78-59-1    | 129                                                       | --                                                                                                                  | --                                                                                                                | 920                                                           | 960                                                                                                     | 960                                     |
| Nitrobenzene                                   | 98-95-3    | 66.8                                                      | --                                                                                                                  | --                                                                                                                | 220                                                           | 690                                                                                                     | 690                                     |
| n-Nitrosodimethylamine                         | 62-75-9    | 330000                                                    | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | 330000                                  |
| n-Nitrosodi-n-propylamine                      | 621-64-7   | 120                                                       | --                                                                                                                  | --                                                                                                                | --                                                            | 0.51                                                                                                    | 0.51                                    |
| n-Nitrosodiphenylamine                         | 86-30-6    | 33000                                                     | --                                                                                                                  | --                                                                                                                | --                                                            | 6                                                                                                       | 6                                       |
| Pentachlorophenol                              | 87-86-5    | 7.9                                                       | 7.9                                                                                                                 | 13                                                                                                                | 4                                                             | 3                                                                                                       | 3                                       |
| Phenol                                         | 108-95-2   | 58                                                        | --                                                                                                                  | --                                                                                                                | 180                                                           | 860000                                                                                                  | 860000                                  |

Table 6-7 - Development of Initial PRGs for Surface Water  
Bremerton Gas Works Site  
Bremerton, Washington

| Analyte                                                 | CAS Number | EPA Region 3 BTAG<br>Marine Water Screening<br>Benchmarks | National Recommended<br>Water Quality Criteria -<br>Aquatic Life Criteria -<br>Saltwater CCC (chronic) <sup>1</sup> | National Recommended<br>Water Quality Criteria -<br>Aquatic Life Criteria -<br>Saltwater CMC (acute) <sup>1</sup> | EPA Region 5 RCRA -<br>Ecological Screening<br>Levels - Water | National Recommended<br>Water Quality Criteria -<br>Human Health for the<br>Consumption of<br>Organisms | Initial PRGs Used<br>for Data Screening |
|---------------------------------------------------------|------------|-----------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------|---------------------------------------------------------------------------------------------------------|-----------------------------------------|
|                                                         |            | EPA, 2006                                                 | EPA, 2013                                                                                                           | EPA, 2013                                                                                                         | EPA, 2003                                                     | EPA, 2013                                                                                               |                                         |
| Volatile Organic Carbons (VOCs) (ug/L)                  |            |                                                           |                                                                                                                     |                                                                                                                   |                                                               |                                                                                                         |                                         |
| 1,1,1-Trichloroethane                                   | 71-55-6    | 312                                                       | --                                                                                                                  | --                                                                                                                | 76                                                            | --                                                                                                      | 312                                     |
| 1,1,1,2-Tetrachloroethane                               | 630-20-6   | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| 1,1,2,2-Tetrachloroethane                               | 79-34-5    | 90.2                                                      | --                                                                                                                  | --                                                                                                                | 380                                                           | 4                                                                                                       | 4                                       |
| 1,1,2-Trichloroethane                                   | 79-00-5    | 550                                                       | --                                                                                                                  | --                                                                                                                | 500                                                           | 16                                                                                                      | 16                                      |
| 1,1,2-Trichlorotrifluoroethane (Freon 113)              | 76-13-1    | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| 1,1-Dichloroethane                                      | 75-34-3    | 47                                                        | --                                                                                                                  | --                                                                                                                | 47                                                            | --                                                                                                      | 47                                      |
| 1,1-Dichloroethene                                      | 75-35-4    | 2240                                                      | --                                                                                                                  | --                                                                                                                | 65                                                            | 7100                                                                                                    | 7100                                    |
| 1,2,3-Trichlorobenzene                                  | 87-61-6    | 8                                                         | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | 8                                       |
| 1,2,3-Trichloropropane                                  | 96-18-4    | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| 1,2,4-Trimethylbenzene                                  | 95-63-6    | 19                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | 19                                      |
| 1,2-Dibromo-3-chloropropane                             | 96-12-8    | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| 1,2-Dichloroethane                                      | 107-06-2   | 1130                                                      | --                                                                                                                  | --                                                                                                                | 910                                                           | 37                                                                                                      | 37                                      |
| 1,2-Dichloroethene, cis-                                | 156-59-2   | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| 1,2-Dichloroethene, trans-                              | 156-60-5   | 970                                                       | --                                                                                                                  | --                                                                                                                | 970                                                           | 10000                                                                                                   | 10000                                   |
| 1,2-Dichloropropane                                     | 78-87-5    | 2400                                                      | --                                                                                                                  | --                                                                                                                | 360                                                           | 15                                                                                                      | 15                                      |
| 1,3,5-Trimethylbenzene (Mesitylene)                     | 108-67-8   | 71                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | 71                                      |
| 1,3-Dichloropropane                                     | 142-28-9   | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| 1,3-Dichloropropene, cis-                               | 10061-01-5 | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | 21                                                                                                      | 21                                      |
| 1,3-Dichloropropene, trans-                             | 10061-02-6 | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | 21                                                                                                      | 21                                      |
| 1,4-Dichloro-2-butene, trans-                           | 110-57-6   | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| 1,4-Dioxane                                             | 123-91-1   | --                                                        | --                                                                                                                  | --                                                                                                                | 22000                                                         | --                                                                                                      | 22000                                   |
| 2-Butanone (MEK)                                        | 78-93-3    | 14000                                                     | --                                                                                                                  | --                                                                                                                | 2200                                                          | --                                                                                                      | 14000                                   |
| 2-Chlorotoluene                                         | 95-49-8    | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| 2-Hexanone (Methyl butyl ketone)                        | 591-78-6   | 99                                                        | --                                                                                                                  | --                                                                                                                | 99                                                            | --                                                                                                      | 99                                      |
| 4-Chlorotoluene                                         | 106-43-4   | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| 4-Isopropyltoluene (4-Cymene)                           | 99-87-6    | 85                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | 85                                      |
| Acetone                                                 | 67-64-1    | 564000                                                    | --                                                                                                                  | --                                                                                                                | 1700                                                          | --                                                                                                      | 564000                                  |
| Acrolein                                                | 107-02-8   | 0.55                                                      | --                                                                                                                  | --                                                                                                                | 0.19                                                          | --                                                                                                      | 0.55                                    |
| Acrylonitrile                                           | 107-13-1   | 581                                                       | --                                                                                                                  | --                                                                                                                | 66                                                            | --                                                                                                      | 581                                     |
| Benzene                                                 | 71-43-2    | 110 (a)                                                   | --                                                                                                                  | --                                                                                                                | 114                                                           | 51                                                                                                      | 51                                      |
| Bromobenzene                                            | 108-86-1   | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| Bromochloromethane                                      | 74-97-5    | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| Bromodichloromethane                                    | 75-27-4    | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | 17                                                                                                      | 17                                      |
| Bromoform (Tribromomethane)                             | 75-25-2    | 640                                                       | --                                                                                                                  | --                                                                                                                | 230                                                           | 140                                                                                                     | 140                                     |
| Bromomethane (Methyl bromide)                           | 74-83-9    | 120                                                       | --                                                                                                                  | --                                                                                                                | 16                                                            | 1500                                                                                                    | 1500                                    |
| Carbon disulfide                                        | 75-15-0    | 0.92                                                      | --                                                                                                                  | --                                                                                                                | 15                                                            | --                                                                                                      | 0.92                                    |
| Carbon tetrachloride (Tetrachloromethane)               | 56-23-5    | 1500                                                      | --                                                                                                                  | --                                                                                                                | 240                                                           | 1.6                                                                                                     | 1.6                                     |
| Chlorobenzene                                           | 108-90-7   | 25 (a)                                                    | --                                                                                                                  | --                                                                                                                | 47                                                            | 1600                                                                                                    | 1600                                    |
| Chloroethane                                            | 75-00-3    | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| Chloroform                                              | 67-66-3    | 815                                                       | --                                                                                                                  | --                                                                                                                | 140                                                           | 470                                                                                                     | 470                                     |
| Chloromethane                                           | 74-87-3    | 2700                                                      | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | 2700                                    |
| Cyclohexane                                             | 110-82-7   | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| Dibromochloromethane                                    | 124-48-1   | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | 13                                                                                                      | 13                                      |
| Dibromomethane                                          | 74-95-3    | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| Dichlorodifluoromethane                                 | 75-71-8    | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| Dichloromethane (Methylene chloride)                    | 75-09-2    | 2560                                                      | --                                                                                                                  | --                                                                                                                | 940                                                           | 590                                                                                                     | 590                                     |
| Ethylbenzene                                            | 100-41-4   | 25 (a)                                                    | --                                                                                                                  | --                                                                                                                | 14                                                            | 2100                                                                                                    | 2100                                    |
| Ethylene dibromide (1,2-Dibromoethane)                  | 106-93-4   | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| Hexachlorobutadiene (Hexachloro-1,3-butadiene)          | 87-68-3    | 0.3                                                       | --                                                                                                                  | --                                                                                                                | 0.053                                                         | 18                                                                                                      | 18                                      |
| Isopropylbenzene (Cumene)                               | 98-82-8    | 2.6                                                       | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | 2.6                                     |
| Methyl acetate                                          | 79-20-9    | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| Methyl iodide (Iodomethane)                             | 74-88-4    | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| Methyl isobutyl ketone (4-Methyl-2-pentanone or (MIBK)) | 108-10-1   | 123000                                                    | --                                                                                                                  | --                                                                                                                | 170                                                           | --                                                                                                      | 123000                                  |
| Methyl tert-butyl ether (MTBE)                          | 1634-04-4  | 11070                                                     | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | 11070                                   |
| n-Butylbenzene                                          | 104-51-8   | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| n-Propylbenzene                                         | 103-65-1   | 128                                                       | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | 128                                     |
| o-Xylene                                                | 95-47-6    | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| sec-Butylbenzene                                        | 135-98-8   | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| Styrene                                                 | 100-42-5   | 910                                                       | --                                                                                                                  | --                                                                                                                | 32                                                            | --                                                                                                      | 910                                     |
| tert-Butylbenzene                                       | 98-06-6    | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| Tetrachloroethene (PCE)                                 | 127-18-4   | 45                                                        | --                                                                                                                  | --                                                                                                                | 45                                                            | 3.3                                                                                                     | 3.3                                     |
| Toluene                                                 | 108-88-3   | 215 (a)                                                   | --                                                                                                                  | --                                                                                                                | 253                                                           | 15000                                                                                                   | 15000                                   |
| Total xylene (reported, not calculated)                 | 1330-20-7  | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| Total Xylene                                            | --         | 19                                                        | --                                                                                                                  | --                                                                                                                | 27                                                            | --                                                                                                      | 19                                      |
| Trichloroethene (TCE)                                   | 79-01-6    | 21                                                        | --                                                                                                                  | --                                                                                                                | 47                                                            | 30                                                                                                      | 30                                      |
| Trichlorofluoromethane (Fluorotrichloromethane)         | 75-69-4    | --                                                        | --                                                                                                                  | --                                                                                                                | --                                                            | --                                                                                                      | --                                      |
| Vinyl acetate                                           | 108-05-4   | 16                                                        | --                                                                                                                  | --                                                                                                                | 248                                                           | --                                                                                                      | 16                                      |
| Vinyl chloride                                          | 75-01-4    | 930                                                       | --                                                                                                                  | --                                                                                                                | 930                                                           | 2.4                                                                                                     | 2.4                                     |

Notes:  
Compounds frequently associated with MGP-operations

<sup>1</sup>-- indicates not available

1 = Criteria for metals and methyl mercury are expressed in terms of the dissolved metal in the water column.  
(a) = This is a Canadian Water Quality Guideline value and refers to the total concentration in an unfiltered sample.  
BTAG = Biological Technical Assistance Group  
CAS = Chemical Abstract Services  
CCC = Criterion Continuous Concentration  
CMC = Criterion Maximum Concentration  
EPA = U.S. Environmental Protection Agency  
HPAH = high molecular weight PAH  
LPAH = low molecular weight PAH  
L = liter  
mg = milligram  
MGP = manufactured gas plant  
ng = nanogram  
PRG = Preliminary Remediation Goal  
RCRA = Rsource Conservation and Recovery Act  
RSL = regional screening level  
ug = microgram

References:  
EPA, 2003. EPA Region 5 Resource Conservation Recovery Act (RCRA) Ecological Screening Levels. August 22, 2003.  
EPA, 2006. EPA Region 3 Biological Technical Assistance Group (BTAG) Screening Benchmarks. Marine Sediment Benchmarks. July 2006.  
EPA, 2013a. National Recommended Water Quality Criteria. Updated August 22, 2013. Available from: <http://water.epa.gov/scitech/swguidance/standards/criteria/current/index.cfm#altable>.

Table 7-1 - Summary of Data Quality Review for Existing Site Data  
Bremerton Gas Works Site  
Bremerton, Waashington

|                                                                                                            |                                                                                                                                                                                                           | Study/Media                                                                                                                                                                             |                                                                                                                       |                                                                                                                                                                                                          |                                                                                                                                                                                                                                                                          |                                                                                                                                                                                                          |                                                                                                                                                                                                                                                                          |                                          |
|------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------|
|                                                                                                            |                                                                                                                                                                                                           | 2008 E&E Targeted Brownfields (E&E 2008)                                                                                                                                                | 2010 E&E Removal Action (AnchorQEA 2011)                                                                              | 1995 Ecology (Ecology 1995)                                                                                                                                                                              | 2007 Geoengineers (Geoengineers 2007a)                                                                                                                                                                                                                                   | 2008 E&E Targeted Brownfields (E&E 2008)                                                                                                                                                                 | 2007 Geoengineers (Geoengineers 2007a)                                                                                                                                                                                                                                   | 2008 E&E Targeted Brownfields (E&E 2008) |
|                                                                                                            |                                                                                                                                                                                                           | Sediment                                                                                                                                                                                | Sediment                                                                                                              | Soil                                                                                                                                                                                                     | Soil                                                                                                                                                                                                                                                                     | Soil                                                                                                                                                                                                     | Groundwater                                                                                                                                                                                                                                                              | Groundwater                              |
| Work Plan Documentation                                                                                    |                                                                                                                                                                                                           |                                                                                                                                                                                         |                                                                                                                       |                                                                                                                                                                                                          |                                                                                                                                                                                                                                                                          |                                                                                                                                                                                                          |                                                                                                                                                                                                                                                                          |                                          |
| Work Plan (SAP/QAPP)                                                                                       | Detailed QAPP covering multiple pieces of sampling program (soil, groundwater and sediment). Also includes general sediment sampling SOP and data report.                                                 | Site-Specific Sampling Plan (SSSP; not reviewed) approved by EPA, finalized after sampling conducted but in field deviations approved by EPA.                                           | None                                                                                                                  | Work Plan, including site-specific SAP and QAPP, dated June 1, 2007                                                                                                                                      | SQAPP dated March 5, 2008                                                                                                                                                                                                                                                | Work Plan, including site-specific SAP and QAPP, dated June 1, 2007                                                                                                                                      | SQAPP dated March 5, 2008                                                                                                                                                                                                                                                |                                          |
| Collection methods and purpose                                                                             | Detailed in QAPP. Sampling under EPA Brownfields management, follows EPA procedures. Limited for sediment; to determine if GW migration from upland sources is occurring into the Narrows.                | Developed under EPA Superfund Tecncial Assesment Respoonse Team (START). Determining origin of contamination from 12" exposed drain pipe on Sesko property beach.                       | Surface soil/sediment samples of suspected contamination based on visual inspection.                                  | Purpose to assess soil quality in potential contaminant source areas. Table of rationale for specific boring/sample locations referenced but not included in final work plan.                            | Judgmental sampling design to determine presence of contamination in areas of concern. Detailed rationale provided in SQAPP.                                                                                                                                             | Purpose to assess groundwater quality in and downgradient of potential contaminant source areas. Table of rationale for specific boring/sample locations referenced but not included in final work plan. | Judgmental sampling design to determine presence of contamination in areas of concern. Detailed rationale provided in SQAPP.                                                                                                                                             |                                          |
| Sample Location and Collection Methods                                                                     |                                                                                                                                                                                                           |                                                                                                                                                                                         |                                                                                                                       |                                                                                                                                                                                                          |                                                                                                                                                                                                                                                                          |                                                                                                                                                                                                          |                                                                                                                                                                                                                                                                          |                                          |
| Location method, accuracy, and datum.                                                                      | Location established with GPS coordinates; accuracy not specified. Actual sampling appear to be close/at QAPP locations. Datum not specified.                                                             | Location established with GPS coordinates; accuracy not specified. Datum not specified.                                                                                                 | Sample locations recorded on rough site sketch. No survey information provided.                                       | Locations provided on scaled site map. Location method unknown. No survey information provided.                                                                                                          | Locations provided on scaled site map. Location method unknown. No survey information provided. Note: locations of borings SP01 and SP03 apparently switched on site map, based on boring log information and correlation of chemical data with boring log observations. | Locations provided on scaled site map. Location method unknown. No survey information provided.                                                                                                          | Locations provided on scaled site map. Location method unknown. No survey information provided. Note: locations of borings SP01 and SP03 apparently switched on site map, based on boring log information and correlation of chemical data with boring log observations. |                                          |
| Sample depths                                                                                              | 0-30cm                                                                                                                                                                                                    | 0-6 inches                                                                                                                                                                              | Less than 10 inches                                                                                                   | up to 45 feet deep                                                                                                                                                                                       | up to 40 feet deep                                                                                                                                                                                                                                                       | 15-foot long well screens up to 45 feet deep                                                                                                                                                             | Monitoring Wells: 10-foot long well screens up to 45 feet deep. Temporary borings: depth not provided.                                                                                                                                                                   |                                          |
| Collection method and matrix                                                                               | Surface sediment. Dedicated stainless steel spoon. Collected at low tide from 5 biased locations targeted to evaluate potential for GW migration based on previous analytical and "on-site observations". | Surface sediment. Dedicated stainless steel spoon. Known areas of sediment deposition within the direct vicinity of the 12: drainpipe, collected below average high tide line.          | Hand collection of surface soil/sediment samples                                                                      | Hollow-stem auger drilling with split-spoon sampling.                                                                                                                                                    | Hollow-stem auger drilling with split-spoon sampling.                                                                                                                                                                                                                    | Report states low-flow sampling with peristaltic pump. Questionable for 30-ft deep groundwater samples.                                                                                                  | Monitoring wells sampled using low-flow sampling using electric submersible pump. Methods for sampling temporary boreholes not provided.                                                                                                                                 |                                          |
| Sample collection, processing and handling                                                                 | Homogenized in dedicated stainless steel bowls (VOC cores taken from sampling locations prior to other sediment collection). Data report includes photographs at each sediment station.                   | Homogenized in dedicated stainless steel bowls (VOC cores taken from sampling locations prior to other sediment collection). Data report includes photographs at each sediment station. | Collection and handling activities not reported.                                                                      | Soil samples collected from 8 borings at 5-foot intervals and field screened for contamination. 17 samples collected for sample analysis. VOC samples collected by EPA 5035A. Protocols detailed in SAP. | Soil samples collected from 7 borings at 5-foot intervals and field screened for contamination. 48 samples collected for sample analysis. VOC samples collected by EPA 5035A. Protocols detailed in SAP.                                                                 | Groundwater samples collected from 8 permanent, developed monitoring wells. Processing and handling protocols detailed in SAP.                                                                           | Groundwater samples collected from 2 permanent, developed monitoring wells and 4 temporary borings. Processing and handling protocols detailed in SAP.                                                                                                                   |                                          |
| Holding time, preservation, and chain of custody                                                           | Detailed in the QAPP. COCs provided in data report. Holding time and preservation discussed in lab data report.                                                                                           | COCs provided in data report. Holding time and preservation discussed in lab data report.                                                                                               | chain of custody not provided. Laboratory case narrative indicates holding times were within recommended limits.      | Requirements detailed in SAP and QAPP. Holding times and preservation were met as documented in data report. Chain of custody provided in data report.                                                   | Requirements detailed in SAP and QAPP. Holding times and preservation were met as documented in data report. Chain of custody provided in data report.                                                                                                                   | Requirements detailed in SAP and QAPP. Holding times and preservation were met as documented in data report. Chain of custody provided in data report.                                                   | Requirements detailed in SAP and QAPP. Holding times and preservation were met as documented in data report. Chain of custody provided in data report.                                                                                                                   |                                          |
| Laboratory Analysis                                                                                        |                                                                                                                                                                                                           |                                                                                                                                                                                         |                                                                                                                       |                                                                                                                                                                                                          |                                                                                                                                                                                                                                                                          |                                                                                                                                                                                                          |                                                                                                                                                                                                                                                                          |                                          |
| Analytical methods are standard or USEPA approved                                                          | EPA and NWTPH methods. TPH-Dx, TPH-Dx, VOC, SVOC, TAL metals.                                                                                                                                             | EPA methods. VOC by 8260, SVOC by 8270, static sheen test.                                                                                                                              | EPA Methods.<br>Metals - EPA200.7, EPA270.2, EPA206.2, EPA279.2, EPA245.5<br>PAHs - Manchester Modification of SW8270 | EPA and NWTPH Methods.<br>TPH - Ecology NWTPH-Gx and NWTPH-Dx<br>VOCs - EPA -8260B<br>SVOCs - EPA 8270 SIM<br>PCBs - EPA 8082<br>PP metals/chromiumVI - EPA 6000/7000 series<br>TBT - Krone (GC/MS)      | TPH - Ecology NWTPH-Gx and NWTPH-Dx<br>VOCs - EPA 8260B<br>SVOCs - EPA 8270C<br>TAL metals - EPA 6000/7000 series                                                                                                                                                        | EPA and NWTPH Methods.<br>TPH - Ecology NWTPH-Gx and NWTPH-Dx<br>VOCs - EPA -8260B<br>SVOCs - EPA 8270 SIM<br>PCBs - EPA 8082<br>PP metals/chromiumVI - EPA 6000/7000 series                             | EPA and NWTPH Methods.<br>TPH - Ecology NWTPH-Gx and NWTPH-Dx<br>VOCs - EPA 8260B<br>SVOCs - EPA 8270C<br>TAL metals - EPA 6000/7000 series                                                                                                                              |                                          |
| Detection limits and qualifiers determined based on USEPA guidance                                         | Yes. Detailed in the QAPP. Qualifier identified in laboratory data report.                                                                                                                                | Yes. Qualifier identified in laboratory data rreport.                                                                                                                                   | summarized in QA narrative in laboratory data report.                                                                 | Yes. Detailed in QAPP. Qualifiers identified in laboratory data report.                                                                                                                                  | Yes. Detailed in QAPP. Qualifiers identified in laboratory data report.                                                                                                                                                                                                  | Yes. Detailed in QAPP. Qualifiers identified in laboratory data report.                                                                                                                                  | Yes. Detailed in QAPP. Qualifiers identified in laboratory data report.                                                                                                                                                                                                  |                                          |
| Measurement instruments and calibration procedures                                                         | Detailed in QAPP. Sampling under EPA Brownfields management, follows EPA procedures.                                                                                                                      | Some detail provided in data validation memo.                                                                                                                                           | Some detail providedin QA narrative in laboratory data report.                                                        | Yes. Detailed in QAPP.                                                                                                                                                                                   | Detailed in QAPP. Sampling under EPA Brownfields management, follows EPA procedures.                                                                                                                                                                                     | Yes. Detailed in QAPP.                                                                                                                                                                                   | Detailed in QAPP. Sampling under EPA Brownfields management, follows EPA procedures.                                                                                                                                                                                     |                                          |
| Quality Control and Data Validation                                                                        |                                                                                                                                                                                                           |                                                                                                                                                                                         |                                                                                                                       |                                                                                                                                                                                                          |                                                                                                                                                                                                                                                                          |                                                                                                                                                                                                          |                                                                                                                                                                                                                                                                          |                                          |
| Field/Lab quality control samples (duplicates, blanks)                                                     | Field rinsate and trip blanks (no issues in sediment samples) MS/MSD, serial dilution, internal standards.                                                                                                | Field trip blank.                                                                                                                                                                       | MS/MSD, LCS                                                                                                           | Field duplicate; method blanks, calibration blanks, sample blanks, MS/MSD, and LCS.                                                                                                                      | Laboratory blanks, rinsate blanks, trip blanks, MS/MSD.                                                                                                                                                                                                                  | Field duplicate, rinseate blank, and trip blanks; method blanks, calibration blanks, sample blanks, MS/MSD, and LCS.                                                                                     | Laboratory blanks, rinsate blanks, trip blanks, MS/MSD.                                                                                                                                                                                                                  |                                          |
| Analytical chemistry data must have been validated and qualified consistent with EPA functional guidelines | Data validation conducted. Data validation memo included as Appendix to data report. Procedures also detailed in QAPP.                                                                                    | Data validation conducted. Data validation memo included as Appendix to data report.                                                                                                    | QA summary by lab. Compounds with low matrix spike recoveries rejected or "J" qualified.                              | QA summary by lab.                                                                                                                                                                                       | QA/QC review and data validation documented in data report.                                                                                                                                                                                                              | QA summary by lab.                                                                                                                                                                                       | QA/QC review and data validation documented in data report.                                                                                                                                                                                                              |                                          |
| Laboratory data reports                                                                                    | Level II Data Package Available.                                                                                                                                                                          | Level II Data Package Available.                                                                                                                                                        | Partial Level II Data Package Available.                                                                              | Level II Data Package Available.                                                                                                                                                                         | Level II Data Package Available.                                                                                                                                                                                                                                         | Level II Data Package Available.                                                                                                                                                                         | Level II Data Package Available.                                                                                                                                                                                                                                         |                                          |

Notes:  
COC = chemical of concern  
EPA = U.S. Environmental Protection Agency  
GC/MS = gas chromatography-mass spectrometry

LCS = laboratory control sample  
MS/MSD = matrix spike/matrix spike duplicate  
NWTPH = Northwest total petroleum hydrocarbon

PAH = polycyclic aromatic hydrocarbon  
PCB = polychlorinated biphenyl  
PP = priority pollutant  
QA = quality assurance  
QAPP = Quality Assurance Project Plan  
QC = quality control  
SAP = Sampling and Analysis Plan  
SOP = standard operating procedure  
SQAPP = SAP/QAPP  
SVOC = semivolatile organic compound  
TAL = target analyte list  
TBT = tributyltin  
TPH = total petroleum hydrocarbons  
VOC = volatile organic compound

References:  
  
Washington State Department of Ecology (Ecology), 1995, Initial Investigation Inspection, Sesko Property, March 29, 1995.  
GeoEngineers, 2007a, Preliminary Upland Assessment Work Plan, McConkey/Sesko Site, June 1, 2007.  
  
Ecology & Environment, Inc. (E&E), 2008, Final Bremerton Gasworks Targeted Brownfields Assessment Sampling and Quality Assurance Project Plan, Prepared by E&E for EPA, March 5, 2008.  
  
Anchor QEA, 2011, Final Completion Report: Former Bremerton MGP Site, Incident Action and Time Critical Removal Action, Prepared for U.S. Coast Guard Sector Puget Sound Incident Management Division on behalf of Cascade Natural Gas Corporation, January 2011.

Table 7-2 - Summary of Data Quality Review for Existing Sediment and Tissue Data  
Bremerton Gas Works Site  
Bremerton, WA

|                                                                                                            | Study/Media                                                                                                                                                                                                                                                                                                                                       |                                                                                                                                                                                                                                                                                |                                                                                                                                                                                                                                              |                                                                                                                                                                                                                           |                                                                                                                                                                                                                     |                                                                                                                                                                                                                     |
|------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|                                                                                                            | 2010 and 2012 ENVVEST                                                                                                                                                                                                                                                                                                                             | 2005, 2007 NOAA Mussel Watch @ station SIWP                                                                                                                                                                                                                                    | 2001 303d Ecology Clam Crab                                                                                                                                                                                                                  | 2008-2009 PSAMP - Spatial/Temporal - Central Sound                                                                                                                                                                        | 1989-2013 PSAMP Long term/ temporal                                                                                                                                                                                 | 2009 - PSAMP Urban Waters Initiative - Bainbridge Basin                                                                                                                                                             |
|                                                                                                            | Mussel tissue. Data from 11 locations in Dyes Inlet and Sinclair Inlet considered for regional information.                                                                                                                                                                                                                                       | Mussel Tissue. Data from 1 location in Sinclair Inlet considered for regional information.                                                                                                                                                                                     | Clam and crab tissue. Data from 3 locations in Dyes Inlet considered for regional information.                                                                                                                                               | Sediment. Data from 11 locations in Dyes Inlet and Sinclair Inlet considered for regional information.                                                                                                                    | Sediment. Data from 1 location in Sinclair Inlet considered for regional information.                                                                                                                               | Sediment. Data from 18 locations in Dyes Inlet and Sinclair Inlet considered for regional information.                                                                                                              |
| Work Plan Documentation                                                                                    |                                                                                                                                                                                                                                                                                                                                                   |                                                                                                                                                                                                                                                                                |                                                                                                                                                                                                                                              |                                                                                                                                                                                                                           |                                                                                                                                                                                                                     |                                                                                                                                                                                                                     |
| Work Plan (SAP/QAPP)                                                                                       | Detailed SAP/QAPP developed with EPA and Ecology under the cooperative Environmental Investment (ENVVEST) program (Johnston et al. 2009; 2010).                                                                                                                                                                                                   | Detailed SAP/QAPP developed under NOAA National Status and Trends Program (NOAA 1993 and 2006).                                                                                                                                                                                | Ecology (2001) QAPP. Results summarized in the 2002 data report and queried from EIM.                                                                                                                                                        | Detailed programmatic QAPP (2009) developed cooperatively with State and Federal agencies. Event specific addenda (2010, 2011, 2012).                                                                                     | Detailed programmatic QAPP (2009) developed cooperatively with State and Federal agencies. Event specific addenda (2010, 2011, 2012).                                                                               | Detailed programmatic QAPP (2009) developed cooperatively with State and Federal agencies. Event specific addenda (2010, 2011, 2012) .                                                                              |
| Collection methods, purpose and representativeness                                                         | Hand collection of blue mussels (Mytilus spp.) via boat or from shore. Shucked, whole organism. Methods follow NOAA protocol. Location control details provided.                                                                                                                                                                                  | Hand collection of blue mussels (Mytilus spp.) via boat or from shore. Shucked, whole organism. Methods follow NOAA protocol.                                                                                                                                                  | Hand collection of male cancer crab tissue (Cancer gracilis) via crab pots (though Dungeness and Blue crabs targeted but none found); native and Japanese little neck clam tissue via hand digging (Protothaca staminea and Tapes japonica). | 0.1 m2 modified stainless steel van Veen, lowered via cable to open upon sediment contact. Targeted fine grained sediment, sample rejected in field if not fine-grained dominant during in-field visual inspection.       | 0.1 m2 modified stainless steel van Veen, lowered via cable to open upon sediment contact. Targeted fine grained sediment, sample rejected in field if not fine-grained dominant during in-field visual inspection. | 0.1 m2 modified stainless steel van Veen, lowered via cable to open upon sediment contact. Targeted fine grained sediment, sample rejected in field if not fine-grained dominant during in-field visual inspection. |
| Sample Location and Collection Methods                                                                     |                                                                                                                                                                                                                                                                                                                                                   |                                                                                                                                                                                                                                                                                |                                                                                                                                                                                                                                              |                                                                                                                                                                                                                           |                                                                                                                                                                                                                     |                                                                                                                                                                                                                     |
| Location method, accuracy and datum                                                                        | Location established with GPS; accuracy not specified. Table provided with coordinates. Datum not specified.                                                                                                                                                                                                                                      | Location established with GPS. Accuracy and datum not specified.                                                                                                                                                                                                               | Location established with GPS, accuracy not specified. Table provided with coordinates. Datum is NAD 83.                                                                                                                                     | Location established with differential GPS. with expected accuracy of better than 3 meters. Table provided with coordinates. Datum is NAD 83.                                                                             | Location established with differential GPS. with expected accuracy of better than 3 meters. Table provided with coordinates. Datum is NAD 83.                                                                       | Location established with differential GPS. with expected accuracy of better than 3 meters. Table provided with coordinates. Datum is NAD 83.                                                                       |
| Sample depths                                                                                              | Above MLLW - on rocks, piling, cabling, piers.                                                                                                                                                                                                                                                                                                    | Detailed in NOAA (1993) SAP. Depends on station, some shoreline, some underwater.                                                                                                                                                                                              | Crabs: via pots on surface<br>Clams: via hand digging within 100 sq ft of beach.                                                                                                                                                             | Top 2-3cm.                                                                                                                                                                                                                | Top 2-3cm.                                                                                                                                                                                                          | Top 2-3cm.                                                                                                                                                                                                          |
| Sample collection, processing and handling                                                                 | Field - Hand harvest, cut byssus threads with knife; hand brush off debris; 1-3 replicates per stations (reps within 150' radius of station loc; 30-50 mussels per replicate. Hand delivery to lab.<br>Lab - kept at -20C until measured and shucked with ceramic knife; rinsed with DI, composite by replicate then by station using Ti blender. | Field - Detailed in NOAA (1993) SAP. In general, some stations hand collection or with rake, some with bivalve dredge.<br>Lab - shell size and volume determined; shucked; homogenized using stainless steel blender with titanium blades. Chemically dried using hydromatrix. | Detailed in SAP.Crabs: Muscle tissue (no organs or shell). Clams: Non depurated. Both crabs and clams samples homogenized in stainless steel blender.                                                                                        | Field - stainless steel spoon from each grab; grabs composited into stainless steel bucket; salinity and sediment temp measured.                                                                                          | Field - stainless steel spoon from each grab; grabs composited into stainless steel bucket; salinity and sediment temp measured.                                                                                    | Field - stainless steel spoon from each grab; grabs composited into stainless steel bucket; salinity and sediment temp measured.                                                                                    |
| Holding time, preservation, and chain of custody                                                           | Requirements detailed in the QAPP. Holding times and preservation were met as documented in the data report. Chain of custody provided in the data report.                                                                                                                                                                                        | Procedures detailed in NOAA (1993) SAP. Actual COCs not available.                                                                                                                                                                                                             | Requirements detailed in the QAPP. Holding times and preservation were met as documented in the data report. Chain of custody provided in the data report.                                                                                   | Requirements detailed in the QAPP. Holding times and preservation were met as documented in the data report. Chain of custody provided in the data report.                                                                | Requirements detailed in the QAPP. Holding times and preservation were met as documented in the data report. Chain of custody provided in the data report.                                                          | Requirements detailed in the QAPP. Holding times and preservation were met as documented in the data report. Chain of custody provided in the data report.                                                          |
| Laboratory Analysis                                                                                        |                                                                                                                                                                                                                                                                                                                                                   |                                                                                                                                                                                                                                                                                |                                                                                                                                                                                                                                              |                                                                                                                                                                                                                           |                                                                                                                                                                                                                     |                                                                                                                                                                                                                     |
| Analytical methods are standard or EPA approved                                                            | Total Hg - EPA 7473m (EPA 1631 rev E in QAPP). Battelle SOPs for other metals and PCB congeners, PAHs - GC/MS Battelle SOP -015. Standard analytical methods. Lipids, moisture, C and N isotopes, trace metals, Hg, isotopes, 20 NS&T PCB congeners, parent and alkylated PAH.                                                                    | Lipids, moisture, C and N isotopes, trace metals, Hg, isotopes, 20 NS&T PCB congeners, parent and alkylated PAH. Detailed in specific analytical methods reports. Standard analytical methods.                                                                                 | Lipid, andimony, SVOCs, PAHs. USEPA and PSEP standard analytical methods.                                                                                                                                                                    | Grain size, TOC, metals, pesticides, chlorobenzenes, PAHs, phenolics, phthalates, PCBs, PBDEs, bPA, triclosan, and other misc. including HCBd, dibenzofuran, carbazole and tin. EPA and PSEP standard analytical methods. | USEPA and PSEP standard analytical methods.                                                                                                                                                                         | USEPA and PSEP standard analytical methods.                                                                                                                                                                         |
| Detection limits and qualifiers determined based on EPA guidance                                           | Yes. Detailed in QAPP and summarized in QA/QC narrative in data report.                                                                                                                                                                                                                                                                           | Yes. Detailed in QAPP and summarized in QA/QC narrative in data report.                                                                                                                                                                                                        | Yes. Detailed in QAPP and summarized in QA/QC narrative in data report.                                                                                                                                                                      | Yes. Detailed in QAPP and summarized in QA/QC narrative in data report.                                                                                                                                                   | Yes. Detailed in QAPP and summarized in QA/QC narrative in data report.                                                                                                                                             | Yes. Detailed in QAPP and summarized in QA/QC narrative in data report.                                                                                                                                             |
| Measurement instruments and calibration procedures                                                         | Detailed in QAPP.                                                                                                                                                                                                                                                                                                                                 | Detailed in QAPP.                                                                                                                                                                                                                                                              | Detailed in QAPP.                                                                                                                                                                                                                            | Detailed in QAPP.                                                                                                                                                                                                         | Detailed in QAPP.                                                                                                                                                                                                   | Detailed in QAPP.                                                                                                                                                                                                   |
| Quality Control and Data Validation                                                                        |                                                                                                                                                                                                                                                                                                                                                   |                                                                                                                                                                                                                                                                                |                                                                                                                                                                                                                                              |                                                                                                                                                                                                                           |                                                                                                                                                                                                                     |                                                                                                                                                                                                                     |
| Field/Lab quality control samples (duplicates, blanks)                                                     | B, BS, MS/MSD, LD, reference material.                                                                                                                                                                                                                                                                                                            | B, BS, MS/MSD, LD, reference material.                                                                                                                                                                                                                                         | Blank, MS/MSD.                                                                                                                                                                                                                               | Blind field split replicates, field blanks; lab replicates, MS/MSD, lab control, MB, reference material.                                                                                                                  | Blind field split replicates, field blanks; lab replicates, MS/MSD, lab control, MB, reference material.                                                                                                            | Blind field split replicates, field blanks; lab replicates, MS/MSD, lab control, MB, reference material.                                                                                                            |
| Analytical chemistry data must have been validated and qualified consistent with EPA functional guidelines | Data validation conducted. Details in case narratives.                                                                                                                                                                                                                                                                                            | Not available online.                                                                                                                                                                                                                                                          | Data validation conducted. Details in case narratives.                                                                                                                                                                                       | Data validation conducted. Details in case narratives.                                                                                                                                                                    | Data validation conducted. Details in case narratives.                                                                                                                                                              | Data validation conducted. Details in case narratives.                                                                                                                                                              |
| Laboratory data reports                                                                                    | Level II Data Package Available.                                                                                                                                                                                                                                                                                                                  | Not available online.                                                                                                                                                                                                                                                          | Case narrative text only.                                                                                                                                                                                                                    | Level II Data Package Available.                                                                                                                                                                                          | Only case narratives available through 2000. Online archives incomplete.                                                                                                                                            | Level II Data Package Available.                                                                                                                                                                                    |

Notes:  
B = Blank  
bPA = Bisphenol A  
BS = Blank spike  
COCs = chemical of concerns  
EPA = U.S. Environmental Protection Agency  
HCBd = Hexachlorobutadiene  
GPS = global positioning system  
LCS = Laboratory control sample  
MB = Method blank  
MS/MSD = Matrix spike/matrix spike duplicate  
MLLW = Mean lower-low water  
NOAA = National Oceanic and Atmospheric Administration  
PAHs = polycyclic aromatic hydrocarbons  
PBDE = Polybrominated diphenyl ether  
PCBs = polychlorinated biphenyls  
PSEP = Puget Sound Estuary Program  
QAPP = Quality Assurance Project Plan  
QA/QC = quality assurance/quality control  
SAP = Sampling and Analysis Plan  
SVOC = semivolatile organic compound  
TAL = Target analyte list  
TOC = Total organic carbon  
TPH = total petroleum hydrocarbons  
VOC = volatile organic compound

References:  
1989-2013 PSAMP  
2008-2009 PSAMP  
2009 PSAMP  
  
2010 and 2012 ENVVEST (Johnston 2010 and Brandenberger 2012)  
  
Johnston et al. 2009; 2010  
  
1993 SAP  
  
2005, 2007 NOAA Mussel Watch  
  
2001 303d Ecology Clam Crab

Striplin, P.L., 1988. Puget Sound Ambient Monitoring Program: Marine Sediment Quality Implementation Plan. Washington State Department of Ecology, Olympia, Washington. 57 pp. www.ecy.wa.gov/biblio/88e37.html. Also see QAPP addendum PSAMP (2009, 2010, 2011, and 2012).  
PSAMP. 2009. Quality Assurance Project Plan. The Puget Sound Assessment and Monitoring Program: Sediment Monitoring Component. August 2009. Publication No. 09-03-121  
PSAMP. 2010 Addendum to Quality Assurance Project Plan. The Puget Sound Assessment and Monitoring Program: Sediment Monitoring Component. August 2010. Publication No. 09-03-121-Addendum1  
PSAMP. 2011 Addendum to Quality Assurance Project Plan. The Puget Sound Assessment and Monitoring Program: Sediment Monitoring Component. August 2010. Publication No. 09-03-121-Addendum2  
PSAMP. 2012 Addendum to Quality Assurance Project Plan. The Puget Sound Assessment and Monitoring Program/Urban Waters Initiative: Sediment Monitoring in the San Juan Islands and Port Gardner/ Everett Harbor. December 2011. Publication No. 09-03-121-Addendum3  
Brandenberger JM, CR Suslick, LJ Kuo RK Johnston. 2012. Ambient Monitoring for Sinclair and Dyes Inlets, Puget Sound, Washington: Chemical Analyses for 2012 Regional Mussel Watch. Prepared for the U.S. Department of Energy. PNNL-21862. September 2012  
Johnston, RK, GH Rosen, JM Bandenberger, J.M. Wright, E. Mollerstuen, J. Young, and T. Tompkins. 2010. Sampling and Analysis Plan for Ambient Monitoring and Toxicity Testing for Sinclair and Dyes Inlets, Puget Sound, Washington. Prepared for Project ENVVEST, Puget Sound Naval Shipyard & Intermediate Maintenance Facility, Bremerton, WA. Revised Sept. 18, 2010.  
Johnston, R.K., G.H. Rosen, J.M. Brandenberger, V.S. Whitney, and J.M. Wright. 2009. Sampling and Analysis Plan for Ambient Monitoring and Toxicity Testing for Sinclair and Dyes Inlets, Puget Sound, Washington. ENVVEST Planning Document.  
National Oceanic and Atmospheric Administration (NOAA). 1993. Sampling and Analytical Methods of the National Status and Trends Program National Benthic Surveillance and Mussel Watch Projects 1984-1992. Volumes I through IV. NOAA Technical Memorandum NOS ORCA 71. G. G. Lauenstein and A. Y. Cantillo (Editors).  
NOAA. 2006a. Kimbrough, K. L., and G. G. Lauenstein (Editors). 2006. Major and Trace Element Analytical Methods of the National Status and Trends Program: 2000-2006. Silver Spring, MD. NOAA Technical Memorandum NOS NCCOS 29, 19 pp.  
NOAA. 2006b. Kimbrough, K. L., G. G. Lauenstein and W. E. Johnston (Editors). 2006. Organic Contaminant Analytical Methods of the National Status and Trends Program: Update 2000-2006. NOAA Technical Memorandum NOS NCCOS 30. 137 pp.  
NOAA. 2008. Kimbrough, K. L., W. E. Johnston, G. G. Lauenstein, J. D. Christensen and D. A. Apeti.. An Assessment of Two Decades of Contaminant Monitoring in the Nation's Coastal Zone. Silver Spring, MD. NOAA Technical. Memorandum NOS NCCOS 74. 105 pp.  
Washington State Department of Ecology (Ecology). 2002. Results of Sampling to Verify 303(d) Listings for Chemical Contaminants in Shellfish from Dyes Inlet and Port Washington Narrows. March 2002. Publication No. 02-03-011

Table 7-3 - Statistical Summary of Soil Data

Bremerton Gas Works Site  
Bremerton, Washington

| Chemical Group | Chemical Constituent           | Number of Locations | Number of Samples | Number of Detections | Maximum Detected Concentration (mg/kg) | Minimum Detected Concentration (mg/kg) | Soil Initial PRG (mg/kg) | Detected Concentrations Exceeding the Initial PRG | Results with Reporting Limit Concentrations that Exceed the Initial Soil PRG | Puget Sound Background Metals Concentration (mg/kg) <sup>1</sup> | Number of Detected Concentrations Exceeding Puget Sound Background | Number of Non-Detect Results with Reporting Limit Concentrations that Exceed Puget Sound Background |
|----------------|--------------------------------|---------------------|-------------------|----------------------|----------------------------------------|----------------------------------------|--------------------------|---------------------------------------------------|------------------------------------------------------------------------------|------------------------------------------------------------------|--------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------|
| TPH            | Gasoline Range Hydrocarbons    | 15                  | 59                | 11                   | 645                                    | 5                                      |                          |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | Diesel Range Hydrocarbons      | 15                  | 58                | 10                   | 36000                                  | 17.1                                   |                          |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | Oil Range Hydrocarbons         | 15                  | 58                | 11                   | 29000                                  | 18                                     |                          |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
| Metals         | Aluminum                       | 7                   | 42                | 42                   | 24100                                  | 5780                                   | 77000                    |                                                   |                                                                              | 32600                                                            |                                                                    |                                                                                                     |
|                | Antimony                       | 13                  | 31                | 2                    | 1.2                                    | 0.8                                    | 0.27                     | 2                                                 | 29                                                                           | 5                                                                |                                                                    | 12                                                                                                  |
|                | Arsenic                        | 15                  | 59                | 59                   | 48.4                                   | 0.5                                    | 0.61                     | 55                                                |                                                                              | 7                                                                | 2                                                                  |                                                                                                     |
|                | Barium                         | 7                   | 42                | 42                   | 120                                    | 23.9                                   | 330                      |                                                   |                                                                              | 255                                                              |                                                                    |                                                                                                     |
|                | Beryllium                      | 15                  | 59                | 42                   | 0.5                                    | 0.1                                    | 21                       |                                                   |                                                                              | 0.6                                                              |                                                                    | 7                                                                                                   |
|                | Cadmium                        | 15                  | 59                | 34                   | 1.6                                    | 0.2                                    | 0.36                     | 21                                                | 25                                                                           | 1                                                                | 4                                                                  |                                                                                                     |
|                | Calcium                        | 7                   | 42                | 42                   | 21300                                  | 1620                                   |                          |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | Chromium (Total)               | 15                  | 59                | 59                   | 60.8                                   | 14.6                                   | 26                       | 32                                                |                                                                              | 48                                                               | 11                                                                 |                                                                                                     |
|                | Chromium (VI)                  | 8                   | 17                | 0                    | NA                                     | NA                                     | 0.29                     |                                                   | 17                                                                           |                                                                  |                                                                    |                                                                                                     |
|                | Cobalt                         | 7                   | 42                | 42                   | 19                                     | 3.3                                    | 13                       | 13                                                |                                                                              | 11                                                               | 15                                                                 |                                                                                                     |
|                | Copper                         | 15                  | 59                | 59                   | 79.1                                   | 8                                      | 28                       | 18                                                |                                                                              | 36                                                               | 17                                                                 |                                                                                                     |
|                | Iron                           | 7                   | 42                | 42                   | 47800                                  | 9570                                   | 55000                    |                                                   |                                                                              | 36100                                                            | 3                                                                  |                                                                                                     |
|                | Lead                           | 15                  | 59                | 57                   | 246                                    | 0.6                                    | 11                       | 7                                                 |                                                                              | 24                                                               | 6                                                                  |                                                                                                     |
|                | Magnesium                      | 7                   | 42                | 42                   | 14900                                  | 1380                                   |                          |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | Manganese                      | 7                   | 42                | 42                   | 824                                    | 170                                    | 220                      | 26                                                |                                                                              | 1200                                                             |                                                                    |                                                                                                     |
|                | Mercury                        | 15                  | 59                | 14                   | 1.62                                   | 0.1                                    | 10                       |                                                   |                                                                              | 0.07                                                             | 14                                                                 | 45                                                                                                  |
|                | Nickel                         | 15                  | 59                | 59                   | 66.3                                   | 21.2                                   | 38                       | 27                                                |                                                                              | 48                                                               | 17                                                                 |                                                                                                     |
|                | Potassium                      | 7                   | 42                | 42                   | 2000                                   | 233                                    |                          |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | Selenium                       | 15                  | 59                | 0                    | NA                                     | NA                                     | 0.52                     |                                                   | 57                                                                           | 0.78                                                             |                                                                    | 42                                                                                                  |
|                | Silver                         | 15                  | 59                | 0                    | NA                                     | NA                                     | 4.2                      |                                                   |                                                                              | 0.61                                                             |                                                                    | 46                                                                                                  |
|                | Sodium                         | 7                   | 42                | 42                   | 565                                    | 120                                    |                          |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | Thallium                       | 15                  | 59                | 34                   | 5.7                                    | 1.1                                    | 0.78                     | 34                                                | 8                                                                            |                                                                  |                                                                    |                                                                                                     |
|                | Vanadium                       | 7                   | 42                | 42                   | 86                                     | 20.7                                   | 7.8                      | 42                                                |                                                                              | 45                                                               | 17                                                                 |                                                                                                     |
|                | Zinc                           | 15                  | 59                | 59                   | 376                                    | 18.9                                   | 46                       | 23                                                |                                                                              | 85                                                               | 5                                                                  |                                                                                                     |
| PAHs           | Acenaphthene                   | 18                  | 60                | 19                   | 31.2                                   | 0.0012                                 | 3400                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | Acenaphthylene                 | 23                  | 61                | 23                   | 460                                    | 0.00091                                | 682                      |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | Anthracene                     | 20                  | 61                | 24                   | 274                                    | 0.0012                                 | 17000                    |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | Benzo(g,h,i)perylene           | 19                  | 61                | 46                   | 79                                     | 0.00071                                | 119                      |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | Dibenzofuran                   | 15                  | 59                | 4                    | 0.37                                   | 0.017                                  | 78                       |                                                   | 2                                                                            |                                                                  |                                                                    |                                                                                                     |
|                | Fluoranthene                   | 22                  | 61                | 32                   | 572                                    | 0.00068                                | 2300                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | Fluorene                       | 20                  | 61                | 25                   | 404                                    | 0.0007                                 | 2300                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | Phenanthrene                   | 24                  | 61                | 39                   | 1490                                   | 0.00061                                | 45.7                     | 6                                                 |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | Pyrene                         | 21                  | 61                | 38                   | 913                                    | 0.0006                                 | 1700                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | 1-Methylnaphthalene            | 12                  | 17                | 10                   | 615                                    | 0.0144                                 | 16                       | 5                                                 |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | 2-Methylnaphthalene            | 13                  | 17                | 10                   | 978                                    | 0.0158                                 | 230                      | 2                                                 |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | Naphthalene                    | 10                  | 12                | 11                   | 953                                    | 0.00047                                | 3.6                      | 4                                                 |                                                                              |                                                                  |                                                                    |                                                                                                     |
| cPAHs          | Benz(a)anthracene              | 18                  | 61                | 29                   | 113                                    | 0.0011                                 | 0.15                     | 15                                                | 2                                                                            |                                                                  |                                                                    |                                                                                                     |
|                | Benzo(a)pyrene                 | 17                  | 61                | 40                   | 116                                    | 0.00053                                | 0.015                    | 21                                                |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | Benzo(b)fluoranthene           | 17                  | 61                | 29                   | 57.4                                   | 0.00085                                | 0.15                     | 16                                                | 1                                                                            |                                                                  |                                                                    |                                                                                                     |
|                | Benzo(k)fluoranthene           | 17                  | 61                | 36                   | 60.6                                   | 0.00056                                | 1.5                      | 10                                                |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | Chrysene                       | 17                  | 61                | 35                   | 146                                    | 0.00067                                | 15                       | 6                                                 |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | Dibenzo(a,h)anthracene         | 17                  | 61                | 36                   | 22.8                                   | 0.0008                                 | 0.015                    | 16                                                | 3                                                                            |                                                                  |                                                                    |                                                                                                     |
|                | Indeno(1,2,3-cd)pyrene         | 17                  | 61                | 44                   | 58.5                                   | 0.00066                                | 0.15                     | 15                                                | 1                                                                            |                                                                  |                                                                    |                                                                                                     |
|                | Total cPAHs TEQ (ND = 0)       | 17                  | 61                | 50                   | 149                                    | 0.000066                               | 0.015                    | 21                                                |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | Total cPAHs TEQ (ND = 1/2 RDL) | 17                  | 61                | 50                   | 149                                    | 0.000842                               | 0.015                    | 22                                                |                                                                              |                                                                  |                                                                    |                                                                                                     |

Table 7-3 - Statistical Summary of Soil Data

Bremerton Gas Works Site  
Bremerton, Washington

| Chemical Group | Chemical Constituent              | Number of Locations | Number of Samples | Number of Detections | Maximum Detected Concentration (mg/kg) | Minimum Detected Concentration (mg/kg) | Soil Initial PRG (mg/kg) | Detected Concentrations Exceeding the Initial PRG | Results with Reporting Limit Concentrations that Exceed the Initial Soil PRG | Puget Sound Background Metals Concentration (mg/kg) <sup>1</sup> | Number of Detected Concentrations Exceeding Puget Sound Background | Number of Non-Detect Results with Reporting Limit Concentrations that Exceed Puget Sound Background |
|----------------|-----------------------------------|---------------------|-------------------|----------------------|----------------------------------------|----------------------------------------|--------------------------|---------------------------------------------------|------------------------------------------------------------------------------|------------------------------------------------------------------|--------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------|
| Other SVOCs    | 1,1'-Biphenyl                     | 7                   | 42                | 5                    | 0.98                                   | 0.014                                  | 51                       |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | 1,2,4,5-Tetrachlorobenzene        | 7                   | 42                | 0                    | NA                                     | NA                                     | 18                       |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | 1,2,4-Trichlorobenzene            | 15                  | 59                | 2                    | 0.00023                                | 0.00014                                | 22                       |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | 1,2-Dichlorobenzene               | 1                   | 1                 | 0                    | NA                                     | NA                                     | 1900                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | 1,3-Dichlorobenzene               | 7                   | 40                | 0                    | NA                                     | NA                                     | 37.7                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | 1,4-Dichlorobenzene               | 1                   | 1                 | 0                    | NA                                     | NA                                     | 2.4                      |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | 1,4-Dioxane                       | 7                   | 42                | 0                    | NA                                     | NA                                     | 4.6                      |                                                   | 2                                                                            |                                                                  |                                                                    |                                                                                                     |
|                | 2,3,4,6-Tetrachlorophenol         | 7                   | 42                | 0                    | NA                                     | NA                                     | 1800                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | 2,4,5-Trichlorophenol             | 15                  | 59                | 0                    | NA                                     | NA                                     | 6100                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | 2,4,6-Trichlorophenol             | 15                  | 59                | 0                    | NA                                     | NA                                     | 44                       |                                                   | 2                                                                            |                                                                  |                                                                    |                                                                                                     |
|                | 2,4-Dichlorophenol                | 15                  | 59                | 0                    | NA                                     | NA                                     | 180                      |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | 2,4-Dimethylphenol                | 15                  | 59                | 1                    | 0.031                                  | 0.031                                  | 1200                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | 2,4-Dinitrophenol                 | 15                  | 59                | 0                    | NA                                     | NA                                     | 120                      |                                                   | 2                                                                            |                                                                  |                                                                    |                                                                                                     |
|                | 2-Chloronaphthalene               | 15                  | 59                | 0                    | NA                                     | NA                                     | 6300                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | 2-Chlorophenol                    | 15                  | 59                | 0                    | NA                                     | NA                                     | 390                      |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | 2-Methylphenol                    | 8                   | 17                | 0                    | NA                                     | NA                                     | 3100                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | 2-Nitroaniline                    | 15                  | 59                | 0                    | NA                                     | NA                                     | 610                      |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | 2-Nitrophenol                     | 15                  | 59                | 0                    | NA                                     | NA                                     | 1.6                      |                                                   | 8                                                                            |                                                                  |                                                                    |                                                                                                     |
|                | 3 & 4 Methylphenol                | 8                   | 17                | 0                    | NA                                     | NA                                     |                          |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | 3,3'-Dichlorobenzidine            | 15                  | 59                | 0                    | NA                                     | NA                                     | 1.1                      |                                                   | 17                                                                           |                                                                  |                                                                    |                                                                                                     |
|                | 3-Nitroaniline                    | 15                  | 59                | 0                    | NA                                     | NA                                     | 3.16                     |                                                   | 7                                                                            |                                                                  |                                                                    |                                                                                                     |
|                | 4,6-Dinitro-2-methylphenol        | 15                  | 59                | 0                    | NA                                     | NA                                     | 4.9                      |                                                   | 7                                                                            |                                                                  |                                                                    |                                                                                                     |
|                | 4-Bromophenyl phenyl ether        | 15                  | 59                | 0                    | NA                                     | NA                                     |                          |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | 4-Chloro-3-methylphenol           | 15                  | 59                | 0                    | NA                                     | NA                                     | 6100                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | 4-Chloroaniline                   | 15                  | 59                | 0                    | NA                                     | NA                                     | 2.4                      |                                                   | 8                                                                            |                                                                  |                                                                    |                                                                                                     |
|                | 4-Chlorophenyl phenyl ether       | 15                  | 59                | 0                    | NA                                     | NA                                     |                          |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | 4-Methylphenol                    | 7                   | 42                | 0                    | NA                                     | NA                                     | 6100                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | 4-Nitroaniline                    | 15                  | 59                | 0                    | NA                                     | NA                                     | 24                       |                                                   | 2                                                                            |                                                                  |                                                                    |                                                                                                     |
|                | 4-Nitrophenol                     | 15                  | 59                | 0                    | NA                                     | NA                                     | 5.12                     |                                                   | 7                                                                            |                                                                  |                                                                    |                                                                                                     |
|                | Acetophenone                      | 7                   | 42                | 2                    | 1.5                                    | 0.03                                   | 7800                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | Aniline                           | 8                   | 17                | 0                    | NA                                     | NA                                     | 85                       |                                                   | 2                                                                            |                                                                  |                                                                    |                                                                                                     |
|                | Atrazine                          | 7                   | 42                | 0                    | NA                                     | NA                                     | 2.1                      |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | Benzaldehyde                      | 7                   | 42                | 0                    | NA                                     | NA                                     | 7800                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | Benzidine                         | 7                   | 42                | 0                    | NA                                     | NA                                     | 0.0005                   |                                                   | 42                                                                           |                                                                  |                                                                    |                                                                                                     |
|                | Benzoic acid                      | 8                   | 17                | 0                    | NA                                     | NA                                     | 240000                   |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | Benzyl alcohol                    | 8                   | 17                | 0                    | NA                                     | NA                                     | 6100                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | Benzyl butyl phthalate            | 15                  | 59                | 5                    | 0.029                                  | 0.015                                  | 260                      |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | Bis(2-chloro-1-methylethyl) ether | 15                  | 59                | 0                    | NA                                     | NA                                     | 4.6                      |                                                   | 4                                                                            |                                                                  |                                                                    |                                                                                                     |
|                | Bis(2-chloroethoxy)methane        | 15                  | 59                | 0                    | NA                                     | NA                                     | 180                      |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | Bis(2-chloroethyl) ether          | 15                  | 59                | 0                    | NA                                     | NA                                     | 0.21                     |                                                   | 17                                                                           |                                                                  |                                                                    |                                                                                                     |
|                | Bis(2-ethylhexyl) phthalate       | 15                  | 59                | 39                   | 0.29                                   | 0.069                                  | 35                       |                                                   | 2                                                                            |                                                                  |                                                                    |                                                                                                     |
|                | Caprolactam                       | 7                   | 42                | 1                    | 0.015                                  | 0.015                                  | 30000                    |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | Carbazole                         | 15                  | 59                | 5                    | 0.49                                   | 0.019                                  |                          |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | Dibenzofuran                      | 15                  | 59                | 4                    | 0.37                                   | 0.017                                  | 78                       |                                                   | 2                                                                            |                                                                  |                                                                    |                                                                                                     |
|                | Diethyl phthalate                 | 15                  | 59                | 0                    | NA                                     | NA                                     | 49000                    |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | Dimethyl phthalate                | 15                  | 59                | 0                    | NA                                     | NA                                     | 734                      |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | Di-n-butyl phthalate              | 15                  | 59                | 3                    | 0.016                                  | 0.013                                  | 6100                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | Di-n-octyl phthalate              | 15                  | 59                | 0                    | NA                                     | NA                                     | 610                      |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                | Hexachlorobenzene                 | 15                  | 59                | 0                    | NA                                     | NA                                     | 0.3                      |                                                   | 17                                                                           |                                                                  |                                                                    |                                                                                                     |
|                | Hexachlorobutadiene               | 1                   | 1                 | 0                    | NA                                     | NA                                     | 6.2                      |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |

Table 7-3 - Statistical Summary of Soil Data

Bremerton Gas Works Site  
Bremerton, Washington

| Chemical Group          | Chemical Constituent             | Number of Locations | Number of Samples | Number of Detections | Maximum Detected Concentration (mg/kg) | Minimum Detected Concentration (mg/kg) | Soil Initial PRG (mg/kg) | Detected Concentrations Exceeding the Initial PRG | Results with Reporting Limit Concentrations that Exceed the Initial Soil PRG | Puget Sound Background Metals Concentration (mg/kg) <sup>1</sup> | Number of Detected Concentrations Exceeding Puget Sound Background | Number of Non-Detect Results with Reporting Limit Concentrations that Exceed Puget Sound Background |
|-------------------------|----------------------------------|---------------------|-------------------|----------------------|----------------------------------------|----------------------------------------|--------------------------|---------------------------------------------------|------------------------------------------------------------------------------|------------------------------------------------------------------|--------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------|
| Other SVOCs (continued) | Hexachlorocyclopentadiene        | 15                  | 59                | 0                    | NA                                     | NA                                     | 370                      |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                         | Hexachloroethane                 | 15                  | 56                | 0                    | NA                                     | NA                                     | 12                       |                                                   | 2                                                                            |                                                                  |                                                                    |                                                                                                     |
|                         | Isophorone                       | 15                  | 59                | 1                    | 6.3                                    | 6.3                                    | 510                      |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                         | Nitrobenzene                     | 8                   | 17                | 0                    | NA                                     | NA                                     | 4.8                      |                                                   | 4                                                                            |                                                                  |                                                                    |                                                                                                     |
|                         | N-Nitrosodimethylamine           | 7                   | 42                | 0                    | NA                                     | NA                                     | 0.0023                   |                                                   | 42                                                                           |                                                                  |                                                                    |                                                                                                     |
|                         | N-Nitroso-di-n-propylamine       | 15                  | 59                | 0                    | NA                                     | NA                                     | 0.069                    |                                                   | 17                                                                           |                                                                  |                                                                    |                                                                                                     |
|                         | N-Nitrosodiphenylamine           | 15                  | 59                | 0                    | NA                                     | NA                                     | 99                       |                                                   | 1                                                                            |                                                                  |                                                                    |                                                                                                     |
|                         | Pentachlorophenol                | 15                  | 59                | 3                    | 0.0036                                 | 0.00081                                | 0.89                     |                                                   | 10                                                                           |                                                                  |                                                                    |                                                                                                     |
|                         | Phenol                           | 15                  | 59                | 6                    | 0.1                                    | 0.023                                  | 18000                    |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                         | 2,4-Dinitrotoluene               | 8                   | 17                | 0                    | NA                                     | NA                                     | 1.6                      |                                                   | 8                                                                            |                                                                  |                                                                    |                                                                                                     |
|                         | 2,6-Dinitrotoluene               | 8                   | 17                | 0                    | NA                                     | NA                                     | 0.0328                   |                                                   | 17                                                                           |                                                                  |                                                                    |                                                                                                     |
| VOCs                    | 1,1,1,2-Tetrachloroethane        | 15                  | 59                | 0                    | NA                                     | NA                                     | 1.9                      |                                                   | 2                                                                            |                                                                  |                                                                    |                                                                                                     |
|                         | 1,1,1-Trichloroethane            | 15                  | 59                | 0                    | NA                                     | NA                                     | 8700                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                         | 1,1,2 - Trichlorotrifluoroethane | 7                   | 42                | 0                    | NA                                     | NA                                     | 43000                    |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                         | 1,1,2,2-Tetrachloroethane        | 15                  | 59                | 0                    | NA                                     | NA                                     | 0.56                     |                                                   | 3                                                                            |                                                                  |                                                                    |                                                                                                     |
|                         | 1,1,2-Trichloroethane            | 15                  | 59                | 0                    | NA                                     | NA                                     | 1.1                      |                                                   | 2                                                                            |                                                                  |                                                                    |                                                                                                     |
|                         | 1,1-Dichloroethane               | 15                  | 59                | 0                    | NA                                     | NA                                     | 3.3                      |                                                   | 2                                                                            |                                                                  |                                                                    |                                                                                                     |
|                         | 1,1-Dichloroethene               | 15                  | 57                | 0                    | NA                                     | NA                                     | 240                      |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                         | 1,1-Dichloropropene              | 8                   | 17                | 0                    | NA                                     | NA                                     |                          |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                         | 1,2,3-Trichlorobenzene           | 15                  | 59                | 6                    | 0.00017                                | 0.00013                                | 49                       |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                         | 1,2,3-Trichloropropane           | 15                  | 59                | 0                    | NA                                     | NA                                     | 0.005                    |                                                   | 11                                                                           |                                                                  |                                                                    |                                                                                                     |
|                         | 1,2,4-Trimethylbenzene           | 15                  | 59                | 9                    | 13.2                                   | 0.014                                  | 62                       |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                         | 1,2-Dibromo-3-chloropropane      | 15                  | 59                | 0                    | NA                                     | NA                                     | 0.0054                   |                                                   | 18                                                                           |                                                                  |                                                                    |                                                                                                     |
|                         | 1,2-Dibromoethane (EDB)          | 15                  | 59                | 0                    | NA                                     | NA                                     | 0.034                    |                                                   | 11                                                                           |                                                                  |                                                                    |                                                                                                     |
|                         | 1,2-Dichloroethane (EDC)         | 15                  | 59                | 0                    | NA                                     | NA                                     | 0.43                     |                                                   | 4                                                                            |                                                                  |                                                                    |                                                                                                     |
|                         | 1,2-Dichloropropane              | 15                  | 58                | 0                    | NA                                     | NA                                     | 0.94                     |                                                   | 2                                                                            |                                                                  |                                                                    |                                                                                                     |
|                         | 1,3,5-Trimethylbenzene           | 15                  | 59                | 8                    | 5.5                                    | 0.026                                  | 780                      |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                         | 1,3-Dichlorobenzene              | 7                   | 40                | 0                    | NA                                     | NA                                     | 37.7                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                         | 1,3-Dichloropropane              | 8                   | 17                | 0                    | NA                                     | NA                                     | 1600                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                         | 1,4-Difluorobenzene              | 1                   | 1                 | 1                    | 2                                      | 2                                      |                          |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                         | 2,2-Dichloropropane              | 8                   | 17                | 0                    | NA                                     | NA                                     |                          |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                         | 2-Butanone                       | 15                  | 59                | 2                    | 2.4                                    | 0.015                                  | 28000                    |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                         | 2-Chlorotoluene                  | 8                   | 17                | 0                    | NA                                     | NA                                     | 1600                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                         | 2-Hexanone                       | 15                  | 59                | 0                    | NA                                     | NA                                     | 12.6                     |                                                   | 2                                                                            |                                                                  |                                                                    |                                                                                                     |
|                         | 4-Chlorotoluene                  | 8                   | 17                | 0                    | NA                                     | NA                                     | 1600                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                         | 4-Methyl-2-pentanone             | 15                  | 59                | 0                    | NA                                     | NA                                     | 5300                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                         | Acetone                          | 15                  | 59                | 30                   | 0.064                                  | 0.0065                                 | 61000                    |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                         | Benzene                          | 15                  | 59                | 22                   | 12                                     | 0.00069                                | 1.1                      | 3                                                 |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                         | Bromobenzene                     | 8                   | 17                | 0                    | NA                                     | NA                                     | 300                      |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                         | Bromochloromethane               | 15                  | 59                | 0                    | NA                                     | NA                                     | 160                      |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                         | Bromodichloromethane             | 15                  | 59                | 0                    | NA                                     | NA                                     | 0.27                     |                                                   | 5                                                                            |                                                                  |                                                                    |                                                                                                     |
|                         | Bromoform                        | 15                  | 59                | 0                    | NA                                     | NA                                     | 15.9                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                         | Bromomethane                     | 15                  | 58                | 0                    | NA                                     | NA                                     | 7.3                      |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                         | Carbon disulfide                 | 15                  | 59                | 4                    | 0.0075                                 | 0.0043                                 | 820                      |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                         | Carbon tetrachloride             | 15                  | 59                | 0                    | NA                                     | NA                                     | 0.61                     |                                                   | 2                                                                            |                                                                  |                                                                    |                                                                                                     |
|                         | Chlorobenzene                    | 15                  | 59                | 0                    | NA                                     | NA                                     | 290                      |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                         | Chlorobenzene-d5                 | 1                   | 1                 | 1                    | 2                                      | 2                                      |                          |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                         | Chloroethane                     | 15                  | 59                | 0                    | NA                                     | NA                                     | 15000                    |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                         | Chloroform                       | 15                  | 59                | 3                    | 0.044                                  | 0.00048                                | 0.29                     |                                                   | 5                                                                            |                                                                  |                                                                    |                                                                                                     |
|                         | Chloromethane                    | 15                  | 59                | 0                    | NA                                     | NA                                     | 120                      |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |

Table 7-3 - Statistical Summary of Soil Data

Bremerton Gas Works Site  
Bremerton, Washington

| Chemical Group      | Chemical Constituent           | Number of Locations | Number of Samples | Number of Detections | Maximum Detected Concentration (mg/kg) | Minimum Detected Concentration (mg/kg) | Soil Initial PRG (mg/kg) | Detected Concentrations Exceeding the Initial PRG | Results with Reporting Limit Concentrations that Exceed the Initial Soil PRG | Puget Sound Background Metals Concentration (mg/kg) <sup>1</sup> | Number of Detected Concentrations Exceeding Puget Sound Background | Number of Non-Detect Results with Reporting Limit Concentrations that Exceed Puget Sound Background |
|---------------------|--------------------------------|---------------------|-------------------|----------------------|----------------------------------------|----------------------------------------|--------------------------|---------------------------------------------------|------------------------------------------------------------------------------|------------------------------------------------------------------|--------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------|
| VOCs<br>(continued) | cis-1,2-Dichloroethene (DCE)   | 15                  | 59                | 0                    | NA                                     | NA                                     | 160                      |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                     | cis-1,3-Dichloropropene        | 15                  | 59                | 3                    | 0.93                                   | 0.00063                                | 0.398                    | 1                                                 | 4                                                                            |                                                                  |                                                                    |                                                                                                     |
|                     | Cyclohexane                    | 7                   | 42                | 0                    | NA                                     | NA                                     | 7000                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                     | Dibromochloromethane           | 15                  | 59                | 0                    | NA                                     | NA                                     | 0.68                     |                                                   | 2                                                                            |                                                                  |                                                                    |                                                                                                     |
|                     | Dibromomethane                 | 8                   | 17                | 0                    | NA                                     | NA                                     | 25                       |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                     | Dichlorodifluoromethane        | 15                  | 59                | 0                    | NA                                     | NA                                     | 94                       |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                     | Ethylbenzene                   | 15                  | 59                | 16                   | 24                                     | 0.00073                                | 5.4                      | 1                                                 |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                     | Hexachlorobutadiene            | 1                   | 1                 | 0                    | NA                                     | NA                                     | 6.2                      |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                     | Hexachloroethane               | 15                  | 56                | 0                    | NA                                     | NA                                     | 12                       |                                                   | 2                                                                            |                                                                  |                                                                    |                                                                                                     |
|                     | Isopropylbenzene               | 15                  | 59                | 7                    | 1.6                                    | 0.00094                                | 2100                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                     | Methyl acetate                 | 7                   | 42                | 1                    | 0.16                                   | 0.16                                   | 78000                    |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                     | Methyl tert-butyl ether (MTBE) | 15                  | 59                | 0                    | NA                                     | NA                                     | 43                       |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                     | Methylcyclohexane              | 7                   | 42                | 3                    | 0.0038                                 | 0.00037                                |                          |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                     | Methylene chloride             | 15                  | 59                | 24                   | 1.3                                    | 0.00058                                | 56                       |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                     | n-Butylbenzene                 | 8                   | 17                | 2                    | 1.96                                   | 1.78                                   | 3900                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                     | n-Hexane                       | 8                   | 17                | 1                    | 0.00121                                | 0.00121                                | 570                      |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                     | n-Propylbenzene                | 8                   | 17                | 2                    | 0.952                                  | 0.792                                  | 3400                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                     | Pentafluorobenzene             | 2                   | 3                 | 3                    | 2                                      | 0.04                                   |                          |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                     | p-Isopropyltoluene             | 8                   | 17                | 4                    | 1.65                                   | 0.493                                  |                          |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                     | sec-Butylbenzene               | 8                   | 17                | 2                    | 0.915                                  | 0.748                                  | 7800                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                     | Styrene                        | 15                  | 59                | 4                    | 0.07                                   | 0.000814                               | 6300                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                     | tert-Butylbenzene              | 8                   | 17                | 0                    | NA                                     | NA                                     | 7800                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                     | Tetrachloroethene (PCE)        | 15                  | 59                | 3                    | 0.00059                                | 0.00044                                | 22                       |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                     | Toluene                        | 15                  | 59                | 30                   | 7.5                                    | 0.00026                                | 5000                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                     | trans-1,2-Dichloroethene       | 15                  | 59                | 0                    | NA                                     | NA                                     | 150                      |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                     | trans-1,3-Dichloropropene      | 15                  | 59                | 3                    | 0.93                                   | 0.00063                                | 0.398                    | 1                                                 | 4                                                                            |                                                                  |                                                                    |                                                                                                     |
|                     | Trichloroethene (TCE)          | 15                  | 59                | 3                    | 0.00147                                | 0.00044                                | 0.91                     |                                                   | 2                                                                            |                                                                  |                                                                    |                                                                                                     |
|                     | Trichlorofluoromethane         | 15                  | 59                | 13                   | 0.0078                                 | 0.0006                                 | 790                      |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                     | Vinyl chloride                 | 15                  | 59                | 0                    | NA                                     | NA                                     | 0.06                     |                                                   | 11                                                                           |                                                                  |                                                                    |                                                                                                     |
|                     | m,p-Xylenes                    | 13                  | 50                | 9                    | 57                                     | 0.00052                                | 630                      |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                     | o-Xylene                       | 13                  | 50                | 8                    | 55                                     | 0.00049                                | 690                      |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                     | Xylenes (total)                | 8                   | 17                | 7                    | 16.7                                   | 0.353                                  | 630                      |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
| PCBs                | Aroclor 1016                   | 8                   | 17                | 0                    | NA                                     | NA                                     | 3.9                      |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                     | Aroclor 1221                   | 8                   | 17                | 0                    | NA                                     | NA                                     | 0.14                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                     | Aroclor 1232                   | 8                   | 17                | 0                    | NA                                     | NA                                     | 0.14                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                     | Aroclor 1242                   | 8                   | 17                | 0                    | NA                                     | NA                                     | 0.22                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                     | Aroclor 1248                   | 8                   | 17                | 0                    | NA                                     | NA                                     | 0.22                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                     | Aroclor 1254                   | 8                   | 17                | 0                    | NA                                     | NA                                     | 0.22                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                     | Aroclor 1260                   | 8                   | 17                | 0                    | NA                                     | NA                                     | 0.22                     |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                     | Aroclor 1262                   | 8                   | 17                | 0                    | NA                                     | NA                                     |                          |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |
|                     | Aroclor 1268                   | 8                   | 17                | 0                    | NA                                     | NA                                     |                          |                                                   |                                                                              |                                                                  |                                                                    |                                                                                                     |

**Notes:**

<sup>1</sup> Background metals concentrations based on Puget Sound (when available) or Washington State background (Ecology 1994).

cPAHs = carcinogenic polycyclic aromatic hydrocarbons

PAHs = polycyclic aromatic hydrocarbons

PCBs = polychlorinated biphenyls

SVOCs = semi-volatile organic compounds

TPH = total petroleum hydrocarbons

VOCs = volatile organic compounds

PRG = preliminary remediation goal

mg/kg = milligrams per kilogram

NA = Not applicable, as there are no detections.



Table 7-4 - Statistical Summary of Groundwater Data

Bremerton Gas Works Site  
Bremerton, Washington

| Chemical Group | Chemical Constituent           | Number of Locations | Number of Samples | Number of Detections | Maximum Detected Concentration (ug/L) | Minimum Detected Concentration (ug/L) | Groundwater Initial PRG (ug/L) | Number of Detected Concentrations Exceeding the Groundwater Initial PRG | Number of Non-Detect Results with Reporting Limit Concentrations that Exceed the Groundwater Initial PRG | Surface Water Initial PRG (ug/L) | Number of Detected Concentrations Exceeding the Surface Water Initial PRG | Number of Non-Detect Results with Reporting Limit Concentrations that Exceed the Surface Water Initial PRG |
|----------------|--------------------------------|---------------------|-------------------|----------------------|---------------------------------------|---------------------------------------|--------------------------------|-------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------|----------------------------------|---------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------|
| TPH            | Gasoline Range Hydrocarbons    | 10                  | 10                | 7                    | 10600                                 | 63.5                                  |                                |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                | Diesel Range Hydrocarbons      | 11                  | 11                | 6                    | 18500                                 | 170                                   |                                |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                | Oil Range Hydrocarbons         | 11                  | 11                | 1                    | 160                                   | 160                                   |                                |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
| Metals (Total) | Antimony                       | 10                  | 10                | 2                    | 0.4                                   | 0.3                                   | 6                              |                                                                         |                                                                                                          | 640                              |                                                                           |                                                                                                            |
|                | Arsenic                        | 10                  | 10                | 10                   | 26                                    | 0.6                                   | 0.045                          | 10                                                                      |                                                                                                          | 0.14                             | 10                                                                        |                                                                                                            |
|                | Barium                         | 2                   | 2                 | 2                    | 173                                   | 35.7                                  | 2000                           |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                | Beryllium                      | 10                  | 10                | 3                    | 1.08                                  | 0.37                                  | 4                              |                                                                         |                                                                                                          | 0.66                             | 2                                                                         | 7                                                                                                          |
|                | Cadmium                        | 10                  | 10                | 2                    | 0.16                                  | 0.05                                  | 5                              |                                                                         |                                                                                                          | 8.8                              |                                                                           |                                                                                                            |
|                | Chromium (Total)               | 10                  | 10                | 10                   | 228                                   | 1.34                                  | 100                            | 2                                                                       |                                                                                                          | 42                               | 3                                                                         |                                                                                                            |
|                | Chromium (VI)                  | 8                   | 8                 | 7                    | 90                                    | 6                                     | 0.031                          | 7                                                                       | 1                                                                                                        | 50                               | 2                                                                         |                                                                                                            |
|                | Cobalt                         | 2                   | 2                 | 2                    | 8.3                                   | 1.4                                   | 4.7                            | 1                                                                       |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                | Copper                         | 10                  | 10                | 10                   | 143                                   | 1.05                                  | 620                            |                                                                         |                                                                                                          | 3.1                              | 8                                                                         |                                                                                                            |
|                | Lead                           | 10                  | 10                | 8                    | 21.6                                  | 0.44                                  | 15                             | 2                                                                       |                                                                                                          | 8.1                              | 2                                                                         |                                                                                                            |
|                | Manganese                      | 2                   | 2                 | 2                    | 3020                                  | 98.1                                  | 320                            | 1                                                                       |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                | Mercury                        | 8                   | 8                 | 1                    | 0.246                                 | 0.246                                 | 0.63                           |                                                                         |                                                                                                          | 0.94                             |                                                                           |                                                                                                            |
|                | Nickel                         | 10                  | 10                | 10                   | 232                                   | 1.65                                  | 300                            |                                                                         |                                                                                                          | 8.2                              | 7                                                                         |                                                                                                            |
|                | Selenium                       | 10                  | 10                | 1                    | 3.64                                  | 3.64                                  | 50                             |                                                                         |                                                                                                          | 71                               |                                                                           |                                                                                                            |
|                | Silver                         | 10                  | 10                | 1                    | 0.07                                  | 0.07                                  | 71                             |                                                                         |                                                                                                          | 1.9                              |                                                                           |                                                                                                            |
|                | Thallium                       | 10                  | 10                | 1                    | 0.26                                  | 0.26                                  | 0.16                           | 1                                                                       | 9                                                                                                        | 0.47                             |                                                                           | 9                                                                                                          |
|                | Vanadium                       | 2                   | 2                 | 2                    | 78.2                                  | 3.7                                   | 63                             | 1                                                                       |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                | Zinc                           | 10                  | 10                | 8                    | 185                                   | 4.5                                   | 4700                           |                                                                         |                                                                                                          | 81                               | 2                                                                         |                                                                                                            |
| PAHs           | Acenaphthene                   | 9                   | 9                 | 5                    | 485                                   | 1.1                                   | 400                            | 1                                                                       |                                                                                                          | 990                              |                                                                           |                                                                                                            |
|                | Acenaphthylene                 | 10                  | 10                | 6                    | 34.9                                  | 0.222                                 |                                |                                                                         |                                                                                                          | 4840                             |                                                                           |                                                                                                            |
|                | Anthracene                     | 10                  | 10                | 5                    | 120                                   | 0.4                                   | 1300                           |                                                                         |                                                                                                          | 40000                            |                                                                           |                                                                                                            |
|                | Benzo(g,h,i)perylene           | 10                  | 10                | 5                    | 25.6                                  | 0.0979                                |                                |                                                                         |                                                                                                          | 7.64                             | 1                                                                         |                                                                                                            |
|                | Dibenzofuran                   | 10                  | 10                | 2                    | 31.8                                  | 0.29                                  | 5.8                            | 1                                                                       | 7                                                                                                        | 4                                | 1                                                                         | 7                                                                                                          |
|                | Fluoranthene                   | 10                  | 10                | 6                    | 122                                   | 0.26                                  | 630                            |                                                                         |                                                                                                          | 140                              |                                                                           |                                                                                                            |
|                | Fluorene                       | 10                  | 10                | 7                    | 184                                   | 0.102                                 | 220                            |                                                                         |                                                                                                          | 5300                             |                                                                           |                                                                                                            |
|                | Phenanthrene                   | 10                  | 10                | 5                    | 377                                   | 1.04                                  |                                |                                                                         |                                                                                                          | 1.5                              | 3                                                                         |                                                                                                            |
|                | Pyrene                         | 10                  | 10                | 7                    | 34.5                                  | 0.174                                 | 87                             |                                                                         |                                                                                                          | 4000                             |                                                                           |                                                                                                            |
|                | 1-Methylnaphthalene            | 8                   | 8                 | 4                    | 970                                   | 0.813                                 | 0.97                           | 3                                                                       | 1                                                                                                        | 2.1                              | 3                                                                         | 1                                                                                                          |
|                | 2-Methylnaphthalene            | 10                  | 10                | 6                    | 1430                                  | 0.13                                  | 27                             | 1                                                                       |                                                                                                          | 4.2                              | 1                                                                         |                                                                                                            |
|                | Naphthalene                    | 2                   | 2                 | 0                    | NA                                    | NA                                    | 0.14                           |                                                                         |                                                                                                          | 13                               |                                                                           |                                                                                                            |
|                | Benz(a)anthracene              | 10                  | 10                | 6                    | 39.3                                  | 0.0168                                | 0.029                          | 5                                                                       | 2                                                                                                        | 0.018                            | 5                                                                         | 2                                                                                                          |
| cPAHs          | Benzo(a)pyrene                 | 10                  | 10                | 6                    | 37.6                                  | 0.0247                                | 0.0029                         | 6                                                                       | 4                                                                                                        | 0.018                            | 6                                                                         | 2                                                                                                          |
|                | Benzo(b)fluoranthene           | 10                  | 10                | 4                    | 0.657                                 | 0.0968                                | 0.029                          | 4                                                                       | 3                                                                                                        | 0.018                            | 4                                                                         | 3                                                                                                          |
|                | Benzo(k)fluoranthene           | 10                  | 10                | 5                    | 0.615                                 | 0.0602                                | 0.29                           | 2                                                                       | 1                                                                                                        | 0.018                            | 5                                                                         | 3                                                                                                          |
|                | Chrysene                       | 10                  | 10                | 6                    | 40.8                                  | 0.0372                                | 2.9                            | 1                                                                       |                                                                                                          | 0.018                            | 6                                                                         | 2                                                                                                          |
|                | Dibenzo(a,h)anthracene         | 10                  | 10                | 4                    | 0.189                                 | 0.0437                                | 0.0029                         | 4                                                                       | 6                                                                                                        | 0.018                            | 4                                                                         | 3                                                                                                          |
|                | Indeno(1,2,3-cd)pyrene         | 10                  | 10                | 4                    | 0.467                                 | 0.0874                                | 0.029                          | 4                                                                       | 3                                                                                                        | 0.018                            | 4                                                                         | 3                                                                                                          |
|                | Total cPAHs TEQ (ND = 0)       | 10                  | 10                | 6                    | 41.9                                  | 0.0328                                | 0.0029                         | 6                                                                       |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                | Total cPAHs TEQ (ND = 1/2 RDL) | 10                  | 10                | 6                    | 43.8                                  | 0.0342                                | 0.0029                         | 6                                                                       |                                                                                                          |                                  |                                                                           |                                                                                                            |

Table 7-4 - Statistical Summary of Groundwater Data

Bremerton Gas Works Site  
Bremerton, Washington

| Chemical Group          | Chemical Constituent              | Number of Locations | Number of Samples | Number of Detections | Maximum Detected Concentration (ug/L) | Minimum Detected Concentration (ug/L) | Groundwater Initial PRG (ug/L) | Number of Detected Concentrations Exceeding the Groundwater Initial PRG | Number of Non-Detect Results with Reporting Limit Concentrations that Exceed the Groundwater Initial PRG | Surface Water Initial PRG (ug/L) | Number of Detected Concentrations Exceeding the Surface Water Initial PRG | Number of Non-Detect Results with Reporting Limit Concentrations that Exceed the Surface Water Initial PRG |
|-------------------------|-----------------------------------|---------------------|-------------------|----------------------|---------------------------------------|---------------------------------------|--------------------------------|-------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------|----------------------------------|---------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------|
| Other SVOCs             | 1,1'-Biphenyl                     | 2                   | 2                 | 0                    | NA                                    | NA                                    | 0.83                           |                                                                         |                                                                                                          | 14                               |                                                                           |                                                                                                            |
|                         | 1,2,4,5-Tetrachlorobenzene        | 2                   | 2                 | 0                    | NA                                    | NA                                    | 1.2                            |                                                                         |                                                                                                          | 1.1                              |                                                                           |                                                                                                            |
|                         | 1,2,4-Trichlorobenzene            | 10                  | 10                | 0                    | NA                                    | NA                                    | 0.99                           |                                                                         | 8                                                                                                        | 70                               |                                                                           |                                                                                                            |
|                         | 1,2,4-Trimethylbenzene            | 1                   | 1                 | 0                    | NA                                    | NA                                    | 15                             |                                                                         |                                                                                                          | 19                               |                                                                           |                                                                                                            |
|                         | 1,2-Dichlorobenzene               | 10                  | 10                | 0                    | NA                                    | NA                                    | 280                            |                                                                         |                                                                                                          | 1300                             |                                                                           |                                                                                                            |
|                         | 1,3-Dichlorobenzene               | 10                  | 10                | 0                    | NA                                    | NA                                    |                                |                                                                         |                                                                                                          | 960                              |                                                                           |                                                                                                            |
|                         | 1,4-Dichlorobenzene               | 10                  | 10                | 0                    | NA                                    | NA                                    | 0.42                           |                                                                         |                                                                                                          | 190                              |                                                                           |                                                                                                            |
| Other SVOCs (continued) | 2,3,4,6-Tetrachlorophenol         | 2                   | 2                 | 0                    | NA                                    | NA                                    | 170                            |                                                                         |                                                                                                          | 1.2                              |                                                                           |                                                                                                            |
|                         | 2,4,5-Trichlorophenol             | 10                  | 10                | 0                    | NA                                    | NA                                    | 890                            |                                                                         |                                                                                                          | 12                               |                                                                           |                                                                                                            |
|                         | 2,4,6-Trichlorophenol             | 10                  | 10                | 0                    | NA                                    | NA                                    | 3.5                            |                                                                         | 8                                                                                                        | 2.4                              |                                                                           | 8                                                                                                          |
|                         | 2,4-Dichlorophenol                | 10                  | 10                | 0                    | NA                                    | NA                                    | 35                             |                                                                         |                                                                                                          | 290                              |                                                                           |                                                                                                            |
|                         | 2,4-Dimethylphenol                | 10                  | 10                | 0                    | NA                                    | NA                                    | 270                            |                                                                         |                                                                                                          | 850                              |                                                                           |                                                                                                            |
|                         | 2,4-Dinitrophenol                 | 10                  | 10                | 0                    | NA                                    | NA                                    | 30                             |                                                                         |                                                                                                          | 5300                             |                                                                           |                                                                                                            |
|                         | 2-Chloronaphthalene               | 10                  | 10                | 0                    | NA                                    | NA                                    | 550                            |                                                                         |                                                                                                          | 1600                             |                                                                           |                                                                                                            |
|                         | 2-Chlorophenol                    | 10                  | 10                | 0                    | NA                                    | NA                                    | 71                             |                                                                         |                                                                                                          | 150                              |                                                                           |                                                                                                            |
|                         | 2-Methylphenol                    | 8                   | 8                 | 0                    | NA                                    | NA                                    | 720                            |                                                                         |                                                                                                          | 67                               |                                                                           |                                                                                                            |
|                         | 2-Nitroaniline                    | 10                  | 10                | 0                    | NA                                    | NA                                    | 150                            |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                         | 2-Nitrophenol                     | 10                  | 10                | 0                    | NA                                    | NA                                    |                                |                                                                         |                                                                                                          | 2940                             |                                                                           |                                                                                                            |
|                         | 3 & 4 Methylphenol                | 8                   | 8                 | 0                    | NA                                    | NA                                    | 1400                           |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                         | 3,3'-Dichlorobenzidine            | 10                  | 10                | 0                    | NA                                    | NA                                    | 0.11                           |                                                                         | 10                                                                                                       | 0.028                            |                                                                           | 10                                                                                                         |
|                         | 3-Nitroaniline                    | 10                  | 10                | 0                    | NA                                    | NA                                    |                                |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                         | 4,6-Dinitro-2-methylphenol        | 10                  | 10                | 0                    | NA                                    | NA                                    | 1.2                            |                                                                         | 8                                                                                                        | 280                              |                                                                           |                                                                                                            |
|                         | 4-Bromophenyl phenyl ether        | 10                  | 10                | 0                    | NA                                    | NA                                    |                                |                                                                         |                                                                                                          | 1.5                              |                                                                           | 8                                                                                                          |
|                         | 4-Chloro-3-methylphenol           | 10                  | 10                | 0                    | NA                                    | NA                                    | 1100                           |                                                                         |                                                                                                          | 34.8                             |                                                                           |                                                                                                            |
|                         | 4-Chloroaniline                   | 10                  | 10                | 0                    | NA                                    | NA                                    | 0.32                           |                                                                         | 10                                                                                                       | 232                              |                                                                           |                                                                                                            |
|                         | 4-Chlorophenyl phenyl ether       | 10                  | 10                | 0                    | NA                                    | NA                                    |                                |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                         | 4-Methylphenol                    | 2                   | 2                 | 0                    | NA                                    | NA                                    | 1400                           |                                                                         |                                                                                                          | 25                               |                                                                           |                                                                                                            |
|                         | 4-Nitroaniline                    | 10                  | 10                | 0                    | NA                                    | NA                                    | 3.3                            |                                                                         | 8                                                                                                        |                                  |                                                                           |                                                                                                            |
|                         | 4-Nitrophenol                     | 10                  | 10                | 0                    | NA                                    | NA                                    |                                |                                                                         |                                                                                                          | 60                               |                                                                           |                                                                                                            |
|                         | Acenaphthene                      | 9                   | 9                 | 5                    | 485                                   | 1.1                                   | 400                            | 1                                                                       |                                                                                                          | 990                              |                                                                           |                                                                                                            |
|                         | Acetophenone                      | 2                   | 2                 | 0                    | NA                                    | NA                                    | 1500                           |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                         | Aniline                           | 8                   | 8                 | 0                    | NA                                    | NA                                    | 12                             |                                                                         |                                                                                                          | 2.2                              |                                                                           | 8                                                                                                          |
|                         | Atrazine                          | 2                   | 2                 | 0                    | NA                                    | NA                                    | 0.26                           |                                                                         | 2                                                                                                        | 1.8                              |                                                                           |                                                                                                            |
|                         | Benzaldehyde                      | 2                   | 2                 | 0                    | NA                                    | NA                                    | 1500                           |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                         | Benzidine                         | 2                   | 2                 | 0                    | NA                                    | NA                                    | 0.000092                       |                                                                         | 2                                                                                                        | 3.9                              |                                                                           |                                                                                                            |
|                         | Benzoic acid                      | 8                   | 8                 | 0                    | NA                                    | NA                                    | 58000                          |                                                                         |                                                                                                          | 42                               |                                                                           |                                                                                                            |
|                         | Benzyl alcohol                    | 8                   | 8                 | 0                    | NA                                    | NA                                    | 1500                           |                                                                         |                                                                                                          | 8.6                              |                                                                           | 8                                                                                                          |
|                         | Benzyl butyl phthalate            | 10                  | 10                | 1                    | 0.33                                  | 0.33                                  | 14                             |                                                                         |                                                                                                          | 1900                             |                                                                           |                                                                                                            |
|                         | Bis(2-chloro-1-methylethyl) ether | 10                  | 10                | 0                    | NA                                    | NA                                    | 0.31                           |                                                                         | 10                                                                                                       | 65000                            |                                                                           |                                                                                                            |
|                         | Bis(2-chloroethoxy)methane        | 10                  | 10                | 0                    | NA                                    | NA                                    | 46                             |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                         | Bis(2-chloroethyl) ether          | 10                  | 10                | 0                    | NA                                    | NA                                    | 0.012                          |                                                                         | 10                                                                                                       | 0.53                             |                                                                           | 8                                                                                                          |
|                         | Bis(2-ethylhexyl) phthalate       | 10                  | 10                | 2                    | 0.5                                   | 0.33                                  | 4.8                            |                                                                         | 8                                                                                                        | 2.2                              |                                                                           | 8                                                                                                          |
|                         | Caprolactam                       | 2                   | 2                 | 1                    | 0.71                                  | 0.71                                  | 7700                           |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                         | Carbazole                         | 10                  | 10                | 1                    | 1.3                                   | 1.3                                   |                                |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                         | Diethyl phthalate                 | 10                  | 10                | 0                    | NA                                    | NA                                    | 11000                          |                                                                         |                                                                                                          | 44000                            |                                                                           |                                                                                                            |
|                         | Dimethyl phthalate                | 10                  | 10                | 0                    | NA                                    | NA                                    |                                |                                                                         |                                                                                                          | 1100000                          |                                                                           |                                                                                                            |
|                         | Di-n-butyl phthalate              | 10                  | 10                | 0                    | NA                                    | NA                                    | 670                            |                                                                         |                                                                                                          | 4500                             |                                                                           |                                                                                                            |
|                         | Di-n-octyl phthalate              | 10                  | 10                | 0                    | NA                                    | NA                                    | 160                            |                                                                         |                                                                                                          | 22                               |                                                                           |                                                                                                            |
|                         | Hexachlorobenzene                 | 10                  | 10                | 0                    | NA                                    | NA                                    | 0.042                          |                                                                         | 10                                                                                                       | 0.00029                          |                                                                           | 10                                                                                                         |
|                         | Hexachlorobutadiene               | 10                  | 10                | 0                    | NA                                    | NA                                    | 0.26                           |                                                                         | 8                                                                                                        | 18                               |                                                                           |                                                                                                            |
|                         | Hexachlorocyclopentadiene         | 10                  | 10                | 0                    | NA                                    | NA                                    | 22                             |                                                                         |                                                                                                          | 1100                             |                                                                           |                                                                                                            |
|                         | Hexachloroethane                  | 10                  | 10                | 0                    | NA                                    | NA                                    | 0.79                           |                                                                         | 8                                                                                                        | 3.3                              |                                                                           | 8                                                                                                          |
|                         | Isophorone                        | 10                  | 10                | 0                    | NA                                    | NA                                    | 67                             |                                                                         |                                                                                                          | 960                              |                                                                           |                                                                                                            |
|                         | Nitrobenzene                      | 8                   | 8                 | 0                    | NA                                    | NA                                    | 0.12                           |                                                                         | 8                                                                                                        | 690                              |                                                                           |                                                                                                            |
|                         | N-Nitrosodimethylamine            | 2                   | 2                 | 0                    | NA                                    | NA                                    | 0.00042                        |                                                                         | 2                                                                                                        | 330000                           |                                                                           |                                                                                                            |
|                         | N-Nitroso-di-n-propylamine        | 10                  | 10                | 0                    | NA                                    | NA                                    | 0.0093                         |                                                                         | 10                                                                                                       | 0.51                             |                                                                           | 8                                                                                                          |
|                         | N-Nitrosodiphenylamine            | 10                  | 10                | 0                    | NA                                    | NA                                    | 10                             |                                                                         | 1                                                                                                        | 6                                |                                                                           | 8                                                                                                          |
|                         | Pentachlorophenol                 | 10                  | 10                | 2                    | 11.4                                  | 0.1                                   | 0.035                          | 2                                                                       | 8                                                                                                        | 3                                | 1                                                                         | 7                                                                                                          |
|                         | Phenol                            | 10                  | 10                | 3                    | 81.6                                  | 75.5                                  | 4500                           |                                                                         |                                                                                                          | 860000                           |                                                                           |                                                                                                            |
|                         | 2,4-Dinitrotoluene                | 8                   | 8                 | 0                    | NA                                    | NA                                    | 0.2                            |                                                                         | 8                                                                                                        | 3.4                              |                                                                           | 8                                                                                                          |
|                         | 2,6-Dinitrotoluene                | 8                   | 8                 | 0                    | NA                                    | NA                                    | 0.042                          |                                                                         | 8                                                                                                        | 81                               |                                                                           |                                                                                                            |
|                         | 2-Methylnaphthalene               | 10                  | 10                | 6                    | 1430                                  | 0.13                                  | 27                             | 1                                                                       |                                                                                                          | 4.2                              | 1                                                                         |                                                                                                            |

Table 7-4 - Statistical Summary of Groundwater Data

Bremerton Gas Works Site  
Bremerton, Washington

| Chemical Group | Chemical Constituent             | Number of Locations | Number of Samples | Number of Detections | Maximum Detected Concentration (ug/L) | Minimum Detected Concentration (ug/L) | Groundwater Initial PRG (ug/L) | Number of Detected Concentrations Exceeding the Groundwater Initial PRG | Number of Non-Detect Results with Reporting Limit Concentrations that Exceed the Groundwater Initial PRG | Surface Water Initial PRG (ug/L) | Number of Detected Concentrations Exceeding the Surface Water Initial PRG | Number of Non-Detect Results with Reporting Limit Concentrations that Exceed the Surface Water Initial PRG |
|----------------|----------------------------------|---------------------|-------------------|----------------------|---------------------------------------|---------------------------------------|--------------------------------|-------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------|----------------------------------|---------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------|
| VOCs           | 1,1,1,2-Tetrachloroethane        | 10                  | 10                | 0                    | NA                                    | NA                                    | 0.5                            |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                | 1,1,1-Trichloroethane            | 10                  | 10                | 0                    | NA                                    | NA                                    | 200                            |                                                                         |                                                                                                          | 76                               |                                                                           |                                                                                                            |
|                | 1,1,2 - Trichlorotrifluoroethane | 2                   | 2                 | 0                    | NA                                    | NA                                    | 53000                          |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                | 1,1,2,2-Tetrachloroethane        | 10                  | 10                | 0                    | NA                                    | NA                                    | 0.066                          |                                                                         | 10                                                                                                       | 4                                |                                                                           |                                                                                                            |
|                | 1,1,2-Trichloroethane            | 10                  | 10                | 0                    | NA                                    | NA                                    | 0.24                           |                                                                         | 2                                                                                                        | 16                               |                                                                           |                                                                                                            |
|                | 1,1-Dichloroethane               | 10                  | 10                | 0                    | NA                                    | NA                                    | 2.4                            |                                                                         |                                                                                                          | 47                               |                                                                           |                                                                                                            |
|                | 1,1-Dichloroethene               | 9                   | 9                 | 0                    | NA                                    | NA                                    | 7                              |                                                                         |                                                                                                          | 7100                             |                                                                           |                                                                                                            |
|                | 1,1-Dichloropropene              | 8                   | 8                 | 0                    | NA                                    | NA                                    |                                |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                | 1,2,3-Trichlorobenzene           | 10                  | 10                | 0                    | NA                                    | NA                                    | 5.2                            |                                                                         |                                                                                                          | 8                                |                                                                           |                                                                                                            |
|                | 1,2,3-Trichloropropane           | 10                  | 10                | 0                    | NA                                    | NA                                    | 0.00065                        |                                                                         | 10                                                                                                       |                                  |                                                                           |                                                                                                            |
|                | 1,2,4-Trichlorobenzene           | 10                  | 10                | 0                    | NA                                    | NA                                    | 0.99                           |                                                                         | 8                                                                                                        | 70                               |                                                                           |                                                                                                            |
|                | 1,2,4-Trimethylbenzene           | 1                   | 1                 | 0                    | NA                                    | NA                                    | 15                             |                                                                         |                                                                                                          | 19                               |                                                                           |                                                                                                            |
|                | 1,2-Dibromo-3-chloropropane      | 10                  | 10                | 0                    | NA                                    | NA                                    | 0.00032                        |                                                                         | 10                                                                                                       |                                  |                                                                           |                                                                                                            |
|                | 1,2-Dibromoethane (EDB)          | 10                  | 10                | 0                    | NA                                    | NA                                    | 0.0065                         |                                                                         | 10                                                                                                       |                                  |                                                                           |                                                                                                            |
|                | 1,2-Dichlorobenzene              | 10                  | 10                | 0                    | NA                                    | NA                                    | 280                            |                                                                         |                                                                                                          | 1300                             |                                                                           |                                                                                                            |
|                | 1,2-Dichloroethane (EDC)         | 10                  | 10                | 3                    | 4.72                                  | 0.93                                  | 0.15                           | 3                                                                       | 7                                                                                                        | 37                               |                                                                           |                                                                                                            |
|                | 1,2-Dichloropropane              | 10                  | 10                | 0                    | NA                                    | NA                                    | 0.38                           |                                                                         |                                                                                                          | 15                               |                                                                           |                                                                                                            |
|                | 1,3,5-Trimethylbenzene           | 10                  | 10                | 5                    | 30                                    | 0.53                                  | 87                             |                                                                         |                                                                                                          | 71                               |                                                                           |                                                                                                            |
|                | 1,3-Dichlorobenzene              | 10                  | 10                | 0                    | NA                                    | NA                                    |                                |                                                                         |                                                                                                          | 960                              |                                                                           |                                                                                                            |
|                | 1,3-Dichloropropane              | 8                   | 8                 | 0                    | NA                                    | NA                                    | 290                            |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                | 1,4-Dichlorobenzene              | 10                  | 10                | 0                    | NA                                    | NA                                    | 0.42                           |                                                                         |                                                                                                          | 190                              |                                                                           |                                                                                                            |
|                | 2,2-Dichloropropane              | 8                   | 8                 | 0                    | NA                                    | NA                                    |                                |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                | 2-Butanone                       | 10                  | 10                | 0                    | NA                                    | NA                                    | 4900                           |                                                                         |                                                                                                          | 2200                             |                                                                           |                                                                                                            |
|                | 2-Chlorotoluene                  | 8                   | 8                 | 0                    | NA                                    | NA                                    | 180                            |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                | 2-Hexanone                       | 10                  | 10                | 0                    | NA                                    | NA                                    | 34                             |                                                                         |                                                                                                          | 99                               |                                                                           |                                                                                                            |
|                | 4-Chlorotoluene                  | 8                   | 8                 | 0                    | NA                                    | NA                                    | 190                            |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                | 4-Methyl-2-pentanone             | 10                  | 10                | 0                    | NA                                    | NA                                    | 1000                           |                                                                         |                                                                                                          | 170                              |                                                                           |                                                                                                            |
|                | Acetone                          | 10                  | 10                | 0                    | NA                                    | NA                                    | 12000                          |                                                                         |                                                                                                          | 1700                             |                                                                           |                                                                                                            |
|                | Benzene                          | 10                  | 10                | 8                    | 950                                   | 2.23                                  | 0.39                           | 8                                                                       |                                                                                                          | 51                               | 5                                                                         |                                                                                                            |
|                | Bromobenzene                     | 8                   | 8                 | 0                    | NA                                    | NA                                    | 54                             |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                | Bromochloromethane               | 10                  | 10                | 0                    | NA                                    | NA                                    | 83                             |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                | Bromodichloromethane             | 10                  | 10                | 0                    | NA                                    | NA                                    | 0.12                           |                                                                         | 10                                                                                                       | 17                               |                                                                           |                                                                                                            |
|                | Bromoform                        | 10                  | 10                | 0                    | NA                                    | NA                                    | 7.9                            |                                                                         |                                                                                                          | 140                              |                                                                           |                                                                                                            |
|                | Bromomethane                     | 10                  | 10                | 0                    | NA                                    | NA                                    | 7                              |                                                                         |                                                                                                          | 1500                             |                                                                           |                                                                                                            |
|                | Carbon disulfide                 | 10                  | 10                | 0                    | NA                                    | NA                                    | 720                            |                                                                         |                                                                                                          | 0.92                             |                                                                           |                                                                                                            |
|                | Carbon tetrachloride             | 10                  | 10                | 1                    | 0.66                                  | 0.66                                  | 0.39                           | 1                                                                       |                                                                                                          | 1.6                              |                                                                           |                                                                                                            |
|                | Chlorobenzene                    | 10                  | 10                | 0                    | NA                                    | NA                                    | 72                             |                                                                         |                                                                                                          | 1600                             |                                                                           |                                                                                                            |
|                | Chloroethane                     | 10                  | 10                | 0                    | NA                                    | NA                                    | 21000                          |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                | Chloroform                       | 10                  | 10                | 3                    | 2.84                                  | 0.2                                   | 0.19                           | 3                                                                       | 7                                                                                                        | 470                              |                                                                           |                                                                                                            |
|                | Chloromethane                    | 10                  | 10                | 0                    | NA                                    | NA                                    | 190                            |                                                                         |                                                                                                          | 2700                             |                                                                           |                                                                                                            |
|                | cis-1,2-Dichloroethene (DCE)     | 10                  | 10                | 3                    | 1.29                                  | 0.37                                  | 28                             |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                | cis-1,3-Dichloropropene          | 10                  | 10                | 0                    | NA                                    | NA                                    |                                |                                                                         |                                                                                                          | 21                               |                                                                           |                                                                                                            |
|                | Cyclohexane                      | 2                   | 2                 | 1                    | 0.38                                  | 0.38                                  | 13000                          |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                | Dibromochloromethane             | 10                  | 10                | 0                    | NA                                    | NA                                    | 0.15                           |                                                                         | 10                                                                                                       | 13                               |                                                                           |                                                                                                            |
|                | Dibromomethane                   | 8                   | 8                 | 0                    | NA                                    | NA                                    | 7.9                            |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                | Dichlorodifluoromethane          | 10                  | 10                | 0                    | NA                                    | NA                                    | 190                            |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                | Ethylbenzene                     | 10                  | 10                | 7                    | 322                                   | 0.53                                  | 1.3                            | 6                                                                       |                                                                                                          | 2100                             |                                                                           |                                                                                                            |
|                | Hexachlorobutadiene              | 10                  | 10                | 0                    | NA                                    | NA                                    | 0.26                           |                                                                         | 8                                                                                                        | 18                               |                                                                           |                                                                                                            |
|                | Hexachloroethane                 | 10                  | 10                | 0                    | NA                                    | NA                                    | 0.79                           |                                                                         | 8                                                                                                        | 3.3                              |                                                                           | 8                                                                                                          |
|                | Isopropylbenzene                 | 10                  | 10                | 6                    | 37.4                                  | 3                                     | 390                            |                                                                         |                                                                                                          | 2.6                              | 6                                                                         |                                                                                                            |
|                | Methyl acetate                   | 2                   | 2                 | 0                    | NA                                    | NA                                    | 16000                          |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                | Methyl tert-butyl ether (MTBE)   | 10                  | 10                | 0                    | NA                                    | NA                                    | 12                             |                                                                         |                                                                                                          | 11070                            |                                                                           |                                                                                                            |
|                | Methylcyclohexane                | 2                   | 2                 | 0                    | NA                                    | NA                                    |                                |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                | Methylene chloride               | 10                  | 10                | 0                    | NA                                    | NA                                    | 5                              |                                                                         |                                                                                                          | 590                              |                                                                           |                                                                                                            |
|                | n-Butylbenzene                   | 8                   | 8                 | 4                    | 5.3                                   | 0.48                                  | 780                            |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                | n-Hexane                         | 8                   | 8                 | 1                    | 1.17                                  | 1.17                                  | 250                            |                                                                         |                                                                                                          | 0.58                             | 1                                                                         | 7                                                                                                          |

Table 7-4 - Statistical Summary of Groundwater Data

Bremerton Gas Works Site  
Bremerton, Washington

| Chemical Group      | Chemical Constituent      | Number of Locations | Number of Samples | Number of Detections | Maximum Detected Concentration (ug/L) | Minimum Detected Concentration (ug/L) | Groundwater Initial PRG (ug/L) | Number of Detected Concentrations Exceeding the Groundwater Initial PRG | Number of Non-Detect Results with Reporting Limit Concentrations that Exceed the Groundwater Initial PRG | Surface Water Initial PRG (ug/L) | Number of Detected Concentrations Exceeding the Surface Water Initial PRG | Number of Non-Detect Results with Reporting Limit Concentrations that Exceed the Surface Water Initial PRG |
|---------------------|---------------------------|---------------------|-------------------|----------------------|---------------------------------------|---------------------------------------|--------------------------------|-------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------|----------------------------------|---------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------|
| VOCs<br>(continued) | n-Propylbenzene           | 8                   | 8                 | 4                    | 9.2                                   | 2.38                                  | 530                            |                                                                         |                                                                                                          | 128                              |                                                                           |                                                                                                            |
|                     | p-Isopropyltoluene        | 8                   | 8                 | 4                    | 8.44                                  | 0.27                                  |                                |                                                                         |                                                                                                          | 85                               |                                                                           |                                                                                                            |
|                     | sec-Butylbenzene          | 8                   | 8                 | 5                    | 4.43                                  | 0.32                                  | 1600                           |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                     | Styrene                   | 10                  | 10                | 0                    | NA                                    | NA                                    | 100                            |                                                                         |                                                                                                          | 32                               |                                                                           |                                                                                                            |
|                     | tert-Butylbenzene         | 8                   | 8                 | 0                    | NA                                    | NA                                    | 510                            |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                     | Tetrachloroethene (PCE)   | 10                  | 10                | 0                    | NA                                    | NA                                    | 5                              |                                                                         |                                                                                                          | 3.3                              |                                                                           |                                                                                                            |
|                     | Toluene                   | 10                  | 10                | 6                    | 41.9                                  | 0.45                                  | 860                            |                                                                         |                                                                                                          | 15000                            |                                                                           |                                                                                                            |
|                     | trans-1,2-Dichloroethene  | 10                  | 10                | 0                    | NA                                    | NA                                    | 86                             |                                                                         |                                                                                                          | 10000                            |                                                                           |                                                                                                            |
|                     | trans-1,3-Dichloropropene | 10                  | 10                | 0                    | NA                                    | NA                                    |                                |                                                                         |                                                                                                          | 21                               |                                                                           |                                                                                                            |
|                     | Trichloroethene (TCE)     | 10                  | 10                | 6                    | 4.79                                  | 0.33                                  | 0.44                           | 4                                                                       |                                                                                                          | 30                               |                                                                           |                                                                                                            |
|                     | Trichlorofluoromethane    | 10                  | 10                | 0                    | NA                                    | NA                                    | 1100                           |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                     | Vinyl chloride            | 10                  | 10                | 0                    | NA                                    | NA                                    | 0.015                          |                                                                         | 10                                                                                                       | 2.4                              |                                                                           |                                                                                                            |
|                     | m,p-Xylenes               | 10                  | 10                | 6                    | 383                                   | 0.74                                  | 190                            | 1                                                                       |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                     | o-Xylene                  | 10                  | 10                | 6                    | 211                                   | 4.91                                  | 190                            | 1                                                                       |                                                                                                          |                                  |                                                                           |                                                                                                            |
| PCBs                | Xylenes (total)           | 8                   | 8                 | 5                    | 593                                   | 8.29                                  | 190                            | 2                                                                       |                                                                                                          | 19                               | 4                                                                         |                                                                                                            |
|                     | Aroclor 1016              | 8                   | 8                 | 0                    | NA                                    | NA                                    | 0.96                           |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                     | Aroclor 1221              | 8                   | 8                 | 0                    | NA                                    | NA                                    | 0.004                          |                                                                         | 8                                                                                                        |                                  |                                                                           |                                                                                                            |
|                     | Aroclor 1232              | 8                   | 8                 | 0                    | NA                                    | NA                                    | 0.004                          |                                                                         | 8                                                                                                        |                                  |                                                                           |                                                                                                            |
|                     | Aroclor 1242              | 8                   | 8                 | 0                    | NA                                    | NA                                    | 0.034                          |                                                                         | 8                                                                                                        |                                  |                                                                           |                                                                                                            |
|                     | Aroclor 1248              | 8                   | 8                 | 0                    | NA                                    | NA                                    | 0.034                          |                                                                         | 8                                                                                                        |                                  |                                                                           |                                                                                                            |
|                     | Aroclor 1254              | 8                   | 8                 | 0                    | NA                                    | NA                                    | 0.034                          |                                                                         | 8                                                                                                        |                                  |                                                                           |                                                                                                            |
|                     | Aroclor 1260              | 8                   | 8                 | 0                    | NA                                    | NA                                    | 0.034                          |                                                                         | 8                                                                                                        |                                  |                                                                           |                                                                                                            |
|                     | Aroclor 1262              | 8                   | 8                 | 0                    | NA                                    | NA                                    |                                |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |
|                     | Aroclor 1268              | 8                   | 8                 | 0                    | NA                                    | NA                                    |                                |                                                                         |                                                                                                          |                                  |                                                                           |                                                                                                            |

**Notes:**  
cPAHs = carcinogenic polycyclic aromatic hydrocarbons  
NA = Not applicable, as there are no detections.  
PAHs = polycyclic aromatic hydrocarbons  
PCBs = polychlorinated biphenyls  
PRG = preliminary remediation goal  
SVOCs = semi-volatile organic compounds  
TPH = total petroleum hydrocarbons  
ug/L = micrograms per liter  
VOCs = volatile organic compounds

**Table 7-5 - Statistical Summary of Sediment Data**Bremerton Gas Works Site  
Bremerton, WA

| Chemical Group | Chemical Constituent           | Number of Locations | Number of Samples | Number of Detections | Maximum Detected Concentration (ug/kg) | Minimum Detected Concentration (ug/kg) | Sediment Initial PRG (ug/kg) | Puget Sound Background Sediment Metals Concentration <sup>1</sup> (ug/kg) | Number of Detected Concentrations Exceeding the Sediment Initial PRG | Number of Detected Concentrations Exceeding Puget Sound Background Metals Concentration |
|----------------|--------------------------------|---------------------|-------------------|----------------------|----------------------------------------|----------------------------------------|------------------------------|---------------------------------------------------------------------------|----------------------------------------------------------------------|-----------------------------------------------------------------------------------------|
| TPH            | Gasoline Range Hydrocarbons    | 5                   | 5                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                | Diesel Range Hydrocarbons      | 5                   | 5                 | 4                    | 240000                                 | 63000                                  |                              |                                                                           |                                                                      |                                                                                         |
|                | Oil Range Hydrocarbons         | 5                   | 5                 | 5                    | 620000                                 | 21000                                  |                              |                                                                           |                                                                      |                                                                                         |
| Metals         | Aluminum                       | 5                   | 5                 | 5                    | 9030000                                | 6020000                                |                              |                                                                           |                                                                      |                                                                                         |
|                | Antimony                       | 1                   | 1                 | 1                    | 3900                                   | 3900                                   | 2000                         | 5000                                                                      | 1                                                                    |                                                                                         |
|                | Arsenic                        | 5                   | 5                 | 5                    | 5100                                   | 1500                                   | 57000                        | 11000                                                                     |                                                                      |                                                                                         |
|                | Barium                         | 5                   | 5                 | 5                    | 47000                                  | 13300                                  |                              |                                                                           |                                                                      |                                                                                         |
|                | Beryllium                      | 5                   | 5                 | 5                    | 2700                                   | 1900                                   |                              |                                                                           |                                                                      |                                                                                         |
|                | Cadmium                        | 5                   | 5                 | 0                    | NA                                     | NA                                     | 5100                         | 1000                                                                      |                                                                      |                                                                                         |
|                | Calcium                        | 5                   | 5                 | 5                    | 33600000                               | 2390000                                |                              |                                                                           |                                                                      |                                                                                         |
|                | Chromium (Total)               | 5                   | 5                 | 5                    | 21200                                  | 16600                                  | 260000                       | 62000                                                                     |                                                                      |                                                                                         |
|                | Cobalt                         | 5                   | 5                 | 5                    | 26300                                  | 3000                                   | 50000                        | 11000                                                                     |                                                                      |                                                                                         |
|                | Copper                         | 5                   | 5                 | 5                    | 71700                                  | 8600                                   | 390000                       | 44000                                                                     |                                                                      |                                                                                         |
|                | Iron                           | 5                   | 5                 | 5                    | 15900000                               | 9730000                                | 20000000                     |                                                                           |                                                                      |                                                                                         |
|                | Lead                           | 5                   | 5                 | 5                    | 30000                                  | 8900                                   | 450000                       | 21000                                                                     |                                                                      |                                                                                         |
|                | Magnesium                      | 5                   | 5                 | 5                    | 4640000                                | 3350000                                |                              |                                                                           |                                                                      |                                                                                         |
|                | Manganese                      | 5                   | 5                 | 5                    | 180000                                 | 135000                                 | 460000                       |                                                                           |                                                                      |                                                                                         |
|                | Mercury                        | 3                   | 3                 | 3                    | 100                                    | 27.8                                   | 410                          | 200                                                                       |                                                                      |                                                                                         |
|                | Nickel                         | 5                   | 5                 | 5                    | 52600                                  | 21400                                  | 20900                        | 50000                                                                     | 5                                                                    | 1                                                                                       |
|                | Potassium                      | 5                   | 5                 | 5                    | 603000                                 | 415000                                 |                              |                                                                           |                                                                      |                                                                                         |
|                | Selenium                       | 5                   | 5                 | 1                    | 400                                    | 400                                    | 2000                         | 780                                                                       |                                                                      |                                                                                         |
|                | Silver                         | 5                   | 5                 | 0                    | NA                                     | NA                                     | 6100                         | 300                                                                       |                                                                      |                                                                                         |
|                | Sodium                         | 5                   | 5                 | 5                    | 1930000                                | 605000                                 |                              |                                                                           |                                                                      |                                                                                         |
|                | Thallium                       | 5                   | 5                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                | Vanadium                       | 5                   | 5                 | 5                    | 36500                                  | 21600                                  |                              | 45000                                                                     |                                                                      |                                                                                         |
|                | Zinc                           | 5                   | 5                 | 5                    | 79900                                  | 23200                                  | 410000                       | 93000                                                                     |                                                                      |                                                                                         |
| PAHs           | Acenaphthene                   | 48                  | 63                | 61                   | 160000                                 | 0.4                                    | 500                          |                                                                           | 16                                                                   |                                                                                         |
|                | Acenaphthylene                 | 51                  | 66                | 66                   | 840000                                 | 0.7                                    | 1300                         |                                                                           | 33                                                                   |                                                                                         |
|                | Anthracene                     | 51                  | 66                | 66                   | 680000                                 | 0.3                                    | 960                          |                                                                           | 41                                                                   |                                                                                         |
|                | Benzo(g,h,i)perylene           | 51                  | 66                | 66                   | 260000                                 | 0.9                                    | 670                          |                                                                           | 50                                                                   |                                                                                         |
|                | Dibenzofuran                   | 5                   | 5                 | 4                    | 74                                     | 58                                     | 540                          |                                                                           |                                                                      |                                                                                         |
|                | Fluoranthene                   | 46                  | 61                | 61                   | 1100000                                | 1.6                                    | 1700                         |                                                                           | 45                                                                   |                                                                                         |
|                | Fluorene                       | 51                  | 66                | 65                   | 600000                                 | 0.3                                    | 540                          |                                                                           | 36                                                                   |                                                                                         |
|                | Phenanthrene                   | 51                  | 66                | 66                   | 1700000                                | 2.6                                    | 1500                         |                                                                           | 46                                                                   |                                                                                         |
|                | Pyrene                         | 51                  | 66                | 66                   | 1400000                                | 1.6                                    | 2600                         |                                                                           | 48                                                                   |                                                                                         |
|                | 2-Methylnaphthalene            | 5                   | 5                 | 5                    | 1200                                   | 19                                     | 670                          |                                                                           | 1                                                                    |                                                                                         |
|                | Naphthalene                    | 46                  | 61                | 61                   | 1700000                                | 5.4                                    | 2100                         |                                                                           | 23                                                                   |                                                                                         |
|                | Benz(a)anthracene              | 51                  | 66                | 66                   | 310000                                 | 0.3                                    | 1300                         |                                                                           | 46                                                                   |                                                                                         |
|                | Benzo(a)pyrene                 | 51                  | 66                | 66                   | 400000                                 | 0.5                                    | 1600                         |                                                                           | 47                                                                   |                                                                                         |
|                | Benzo(b)fluoranthene           | 51                  | 66                | 66                   | 200000                                 | 0.4                                    | 10400                        |                                                                           | 17                                                                   |                                                                                         |
|                | Benzo(k)fluoranthene           | 51                  | 66                | 65                   | 93000                                  | 0.5                                    | 240                          |                                                                           | 50                                                                   |                                                                                         |
|                | Chrysene                       | 51                  | 66                | 66                   | 270000                                 | 0.5                                    | 1400                         |                                                                           | 47                                                                   |                                                                                         |
|                | Dibenzo(a,h)anthracene         | 51                  | 66                | 65                   | 38000                                  | 0.2                                    | 230                          |                                                                           | 46                                                                   |                                                                                         |
|                | Indeno(1,2,3-cd)pyrene         | 51                  | 66                | 66                   | 190000                                 | 0.4                                    | 600                          |                                                                           | 49                                                                   |                                                                                         |
|                | Total cPAHs TEQ (ND = 0)       | 51                  | 66                | 66                   | 509200                                 | 0.6                                    | 1600                         |                                                                           | 49                                                                   |                                                                                         |
|                | Total cPAHs TEQ (ND = 1/2 RDL) | 51                  | 66                | 66                   | 509200                                 | 0.9                                    | 1600                         |                                                                           | 49                                                                   |                                                                                         |
|                | Total HPAHs                    | 46                  | 61                | 61                   | 4361000                                | 6.2                                    | 12000                        |                                                                           | 45                                                                   |                                                                                         |
|                | Total LPAHs                    | 46                  | 61                | 61                   | 5596000                                | 10.1                                   | 5200                         |                                                                           | 39                                                                   |                                                                                         |
|                | Total PAHs                     | 46                  | 61                | 61                   | 8890000                                | 16.3                                   | 4022                         |                                                                           | 48                                                                   |                                                                                         |

**Table 7-5**Final Scoping Memorandum  
Page 1 of 4

**Table 7-5 - Statistical Summary of Sediment Data**Bremerton Gas Works Site  
Bremerton, WA

| Chemical Group | Chemical Constituent              | Number of Locations | Number of Samples | Number of Detections | Maximum Detected Concentration (ug/kg) | Minimum Detected Concentration (ug/kg) | Sediment Initial PRG (ug/kg) | Puget Sound Background Sediment Metals Concentration <sup>1</sup> (ug/kg) | Number of Detected Concentrations Exceeding the Sediment Initial PRG | Number of Detected Concentrations Exceeding Puget Sound Background Metals Concentration |
|----------------|-----------------------------------|---------------------|-------------------|----------------------|----------------------------------------|----------------------------------------|------------------------------|---------------------------------------------------------------------------|----------------------------------------------------------------------|-----------------------------------------------------------------------------------------|
| Other SVOCs    | 1,1'-Biphenyl                     | 5                   | 5                 | 4                    | 110                                    | 60                                     | 1220                         |                                                                           |                                                                      |                                                                                         |
|                | 1,2,4,5-Tetrachlorobenzene        | 5                   | 5                 | 0                    | NA                                     | NA                                     | 47000                        |                                                                           |                                                                      |                                                                                         |
|                | 1,2,4-Trichlorobenzene            | 8                   | 9                 | 0                    | NA                                     | NA                                     | 31                           |                                                                           |                                                                      |                                                                                         |
|                | 1,2-Dichlorobenzene               | 8                   | 9                 | 0                    | NA                                     | NA                                     | 35                           |                                                                           |                                                                      |                                                                                         |
|                | 1,3,5-Trimethylbenzene            | 1                   | 1                 | 1                    | 21                                     | 21                                     |                              |                                                                           |                                                                      |                                                                                         |
|                | 1,3-Dichlorobenzene               | 5                   | 5                 | 0                    | NA                                     | NA                                     | 842                          |                                                                           |                                                                      |                                                                                         |
|                | 1,4-Dichlorobenzene               | 2                   | 2                 | 2                    | 23                                     | 22                                     | 110                          |                                                                           |                                                                      |                                                                                         |
|                | 1,4-Dioxane                       | 5                   | 5                 | 0                    | NA                                     | NA                                     | 119                          |                                                                           |                                                                      |                                                                                         |
|                | 2,3,4,6-Tetrachlorophenol         | 5                   | 5                 | 0                    | NA                                     | NA                                     | 284                          |                                                                           |                                                                      |                                                                                         |
|                | 2,4,5-Trichlorophenol             | 5                   | 5                 | 0                    | NA                                     | NA                                     | 819                          |                                                                           |                                                                      |                                                                                         |
|                | 2,4,6-Trichlorophenol             | 5                   | 5                 | 0                    | NA                                     | NA                                     | 2650                         |                                                                           |                                                                      |                                                                                         |
|                | 2,4-Dichlorophenol                | 5                   | 5                 | 0                    | NA                                     | NA                                     | 117                          |                                                                           |                                                                      |                                                                                         |
|                | 2,4-Dimethylphenol                | 5                   | 5                 | 0                    | NA                                     | NA                                     | 29                           |                                                                           |                                                                      |                                                                                         |
|                | 2,4-Dinitrophenol                 | 5                   | 5                 | 0                    | NA                                     | NA                                     | 6.21                         |                                                                           |                                                                      |                                                                                         |
|                | 2-Chloronaphthalene               | 5                   | 5                 | 0                    | NA                                     | NA                                     | 417                          |                                                                           |                                                                      |                                                                                         |
|                | 2-Chlorophenol                    | 5                   | 5                 | 0                    | NA                                     | NA                                     | 344                          |                                                                           |                                                                      |                                                                                         |
|                | 2-Nitroaniline                    | 5                   | 5                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                | 2-Nitrophenol                     | 5                   | 5                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                | 3,3'-Dichlorobenzidine            | 5                   | 5                 | 0                    | NA                                     | NA                                     | 2060                         |                                                                           |                                                                      |                                                                                         |
|                | 3-Nitroaniline                    | 5                   | 5                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                | 4,6-Dinitro-2-methylphenol        | 5                   | 5                 | 0                    | NA                                     | NA                                     | 104                          |                                                                           |                                                                      |                                                                                         |
|                | 4-Bromophenyl phenyl ether        | 5                   | 5                 | 0                    | NA                                     | NA                                     | 1230                         |                                                                           |                                                                      |                                                                                         |
|                | 4-Chloro-3-methylphenol           | 5                   | 5                 | 0                    | NA                                     | NA                                     | 388                          |                                                                           |                                                                      |                                                                                         |
|                | 4-Chloroaniline                   | 5                   | 5                 | 0                    | NA                                     | NA                                     | 146                          |                                                                           |                                                                      |                                                                                         |
|                | 4-Chlorophenyl phenyl ether       | 5                   | 5                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                | 4-Methylphenol                    | 5                   | 5                 | 2                    | 17                                     | 17                                     | 670                          |                                                                           |                                                                      |                                                                                         |
|                | 4-Nitroaniline                    | 5                   | 5                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                | 4-Nitrophenol                     | 5                   | 5                 | 0                    | NA                                     | NA                                     | 13.3                         |                                                                           |                                                                      |                                                                                         |
|                | Acenaphthene                      | 48                  | 63                | 61                   | 160000                                 | 0.4                                    | 500                          |                                                                           | 16                                                                   |                                                                                         |
|                | Acetophenone                      | 5                   | 5                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                | Atrazine                          | 5                   | 5                 | 0                    | NA                                     | NA                                     | 6.62                         |                                                                           |                                                                      |                                                                                         |
|                | Benzaldehyde                      | 5                   | 5                 | 2                    | 38                                     | 19                                     |                              |                                                                           |                                                                      |                                                                                         |
|                | Benidine                          | 5                   | 5                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                | Benzyl butyl phthalate            | 5                   | 5                 | 0                    | NA                                     | NA                                     | 63                           |                                                                           |                                                                      |                                                                                         |
|                | Bis(2-chloro-1-methylethyl) ether | 5                   | 5                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                | Bis(2-chloroethoxy)methane        | 5                   | 5                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                | Bis(2-chloroethyl) ether          | 5                   | 5                 | 0                    | NA                                     | NA                                     | 3520                         |                                                                           |                                                                      |                                                                                         |
|                | Bis(2-ethylhexyl) phthalate       | 5                   | 5                 | 1                    | 42                                     | 42                                     | 1300                         |                                                                           |                                                                      |                                                                                         |
|                | Caprolactam                       | 5                   | 5                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                | Carbazole                         | 5                   | 5                 | 4                    | 110                                    | 69                                     |                              |                                                                           |                                                                      |                                                                                         |
|                | Dibenzofuran                      | 5                   | 5                 | 4                    | 74                                     | 58                                     | 540                          |                                                                           |                                                                      |                                                                                         |
|                | Diethyl phthalate                 | 5                   | 5                 | 0                    | NA                                     | NA                                     | 200                          |                                                                           |                                                                      |                                                                                         |
|                | Dimethyl phthalate                | 5                   | 5                 | 0                    | NA                                     | NA                                     | 71                           |                                                                           |                                                                      |                                                                                         |
|                | Di-n-butyl phthalate              | 5                   | 5                 | 0                    | NA                                     | NA                                     | 1400                         |                                                                           |                                                                      |                                                                                         |
|                | Di-n-octyl phthalate              | 5                   | 5                 | 0                    | NA                                     | NA                                     | 6200                         |                                                                           |                                                                      |                                                                                         |
|                | Hexachlorobenzene                 | 5                   | 5                 | 0                    | NA                                     | NA                                     | 22                           |                                                                           |                                                                      |                                                                                         |
|                | Hexachlorobutadiene               | 8                   | 9                 | 0                    | NA                                     | NA                                     | 11                           |                                                                           |                                                                      |                                                                                         |
|                | Hexachlorocyclopentadiene         | 5                   | 5                 | 0                    | NA                                     | NA                                     | 139                          |                                                                           |                                                                      |                                                                                         |
|                | Hexachloroethane                  | 3                   | 3                 | 0                    | NA                                     | NA                                     | 804                          |                                                                           |                                                                      |                                                                                         |
|                | Isophorone                        | 5                   | 5                 | 0                    | NA                                     | NA                                     | 432                          |                                                                           |                                                                      |                                                                                         |

**Table 7-5 - Statistical Summary of Sediment Data**Bremerton Gas Works Site  
Bremerton, WA

| Chemical Group          | Chemical Constituent             | Number of Locations | Number of Samples | Number of Detections | Maximum Detected Concentration (ug/kg) | Minimum Detected Concentration (ug/kg) | Sediment Initial PRG (ug/kg) | Puget Sound Background Sediment Metals Concentration <sup>1</sup> (ug/kg) | Number of Detected Concentrations Exceeding the Sediment Initial PRG | Number of Detected Concentrations Exceeding Puget Sound Background Metals Concentration |
|-------------------------|----------------------------------|---------------------|-------------------|----------------------|----------------------------------------|----------------------------------------|------------------------------|---------------------------------------------------------------------------|----------------------------------------------------------------------|-----------------------------------------------------------------------------------------|
| Other SVOCs (continued) | Naphthalene                      | 46                  | 61                | 61                   | 1700000                                | 5.4                                    | 2100                         |                                                                           | 23                                                                   |                                                                                         |
|                         | N-Nitrosodimethylamine           | 5                   | 5                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                         | N-Nitroso-di-n-propylamine       | 5                   | 5                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                         | N-Nitrosodiphenylamine           | 5                   | 5                 | 0                    | NA                                     | NA                                     | 28                           |                                                                           |                                                                      |                                                                                         |
|                         | Pentachlorophenol                | 5                   | 5                 | 5                    | 110                                    | 35                                     | 360                          |                                                                           |                                                                      |                                                                                         |
|                         | Phenol                           | 5                   | 5                 | 0                    | NA                                     | NA                                     | 420                          |                                                                           |                                                                      |                                                                                         |
|                         | 2-Methylnaphthalene              | 5                   | 5                 | 5                    | 1200                                   | 19                                     | 670                          |                                                                           | 1                                                                    |                                                                                         |
| VOCs                    | 1,1,1,2-Tetrachloroethane        | 8                   | 9                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                         | 1,1,1-Trichloroethane            | 8                   | 9                 | 0                    | NA                                     | NA                                     | 856                          |                                                                           |                                                                      |                                                                                         |
|                         | 1,1,2 - Trichlorotrifluoroethane | 8                   | 9                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                         | 1,1,2,2-Tetrachloroethane        | 8                   | 9                 | 0                    | NA                                     | NA                                     | 202                          |                                                                           |                                                                      |                                                                                         |
|                         | 1,1,2-Trichloroethane            | 8                   | 9                 | 0                    | NA                                     | NA                                     | 570                          |                                                                           |                                                                      |                                                                                         |
|                         | 1,1-Dichloroethane               | 8                   | 9                 | 0                    | NA                                     | NA                                     | 0.575                        |                                                                           |                                                                      |                                                                                         |
|                         | 1,1-Dichloroethene               | 8                   | 9                 | 0                    | NA                                     | NA                                     | 2780                         |                                                                           |                                                                      |                                                                                         |
|                         | 1,1-Dichloropropene              | 3                   | 4                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                         | 1,2,3-Trichlorobenzene           | 8                   | 9                 | 0                    | NA                                     | NA                                     | 858                          |                                                                           |                                                                      |                                                                                         |
|                         | 1,2,3-Trichloropropane           | 8                   | 9                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                         | 1,2,4-Trichlorobenzene           | 8                   | 9                 | 0                    | NA                                     | NA                                     | 31                           |                                                                           |                                                                      |                                                                                         |
|                         | 1,2,4-Trimethylbenzene           | 8                   | 9                 | 4                    | 980                                    | 2.4                                    |                              |                                                                           |                                                                      |                                                                                         |
|                         | 1,2-Dibromo-3-chloropropane      | 8                   | 9                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                         | 1,2-Dibromoethane (EDB)          | 8                   | 9                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                         | 1,2-Dichlorobenzene              | 8                   | 9                 | 0                    | NA                                     | NA                                     | 35                           |                                                                           |                                                                      |                                                                                         |
|                         | 1,2-Dichloroethane (EDC)         | 8                   | 9                 | 0                    | NA                                     | NA                                     | 260                          |                                                                           |                                                                      |                                                                                         |
|                         | 1,2-Dichloropropane              | 8                   | 9                 | 0                    | NA                                     | NA                                     | 333                          |                                                                           |                                                                      |                                                                                         |
|                         | 1,3,5-Trimethylbenzene           | 1                   | 1                 | 1                    | 21                                     | 21                                     |                              |                                                                           |                                                                      |                                                                                         |
|                         | 1,3-Dichlorobenzene              | 5                   | 5                 | 0                    | NA                                     | NA                                     | 842                          |                                                                           |                                                                      |                                                                                         |
|                         | 1,3-Dichloropropane              | 3                   | 4                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                         | 1,4-Dichloro-2-Butene            | 3                   | 4                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                         | 1,4-Dichlorobenzene              | 2                   | 2                 | 2                    | 23                                     | 22                                     | 110                          |                                                                           |                                                                      |                                                                                         |
|                         | 2,2-Dichloropropane              | 3                   | 4                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                         | 2-Butanone                       | 8                   | 9                 | 0                    | NA                                     | NA                                     | 42.4                         |                                                                           |                                                                      |                                                                                         |
|                         | 2-Chloroethyl Vinyl Ether        | 3                   | 4                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                         | 2-Chlorotoluene                  | 3                   | 4                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                         | 2-Hexanone                       | 8                   | 9                 | 0                    | NA                                     | NA                                     | 58.2                         |                                                                           |                                                                      |                                                                                         |
|                         | 4-Chlorotoluene                  | 3                   | 4                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                         | 4-Methyl-2-pentanone             | 8                   | 9                 | 0                    | NA                                     | NA                                     | 25.1                         |                                                                           |                                                                      |                                                                                         |
|                         | Acrolein                         | 3                   | 4                 | 0                    | NA                                     | NA                                     | 0.00152                      |                                                                           |                                                                      |                                                                                         |
|                         | Acrylonitrile                    | 3                   | 4                 | 0                    | NA                                     | NA                                     | 1.2                          |                                                                           |                                                                      |                                                                                         |
|                         | Benzene                          | 8                   | 9                 | 3                    | 8.1                                    | 1.5                                    | 137                          |                                                                           |                                                                      |                                                                                         |
|                         | Bromobenzene                     | 3                   | 4                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                         | Bromochloromethane               | 8                   | 9                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                         | Bromodichloromethane             | 8                   | 9                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                         | Bromoethane                      | 3                   | 4                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                         | Bromoform                        | 8                   | 9                 | 0                    | NA                                     | NA                                     | 1310                         |                                                                           |                                                                      |                                                                                         |
|                         | Bromomethane                     | 8                   | 9                 | 0                    | NA                                     | NA                                     | 1.37                         |                                                                           |                                                                      |                                                                                         |
|                         | Carbon disulfide                 | 8                   | 9                 | 1                    | 4.3                                    | 4.3                                    | 0.851                        |                                                                           | 1*                                                                   |                                                                                         |
|                         | Carbon tetrachloride             | 8                   | 9                 | 0                    | NA                                     | NA                                     | 7240                         |                                                                           |                                                                      |                                                                                         |
|                         | Chlorobenzene                    | 8                   | 9                 | 0                    | NA                                     | NA                                     | 162                          |                                                                           |                                                                      |                                                                                         |
|                         | Chloroethane                     | 8                   | 9                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                         | Chloroform                       | 8                   | 9                 | 0                    | NA                                     | NA                                     | 121                          |                                                                           |                                                                      |                                                                                         |

**Table 7-5 - Statistical Summary of Sediment Data**Bremerton Gas Works Site  
Bremerton, WA

| Chemical Group      | Chemical Constituent           | Number of Locations | Number of Samples | Number of Detections | Maximum Detected Concentration (ug/kg) | Minimum Detected Concentration (ug/kg) | Sediment Initial PRG (ug/kg) | Puget Sound Background Sediment Metals Concentration <sup>1</sup> (ug/kg) | Number of Detected Concentrations Exceeding the Sediment Initial PRG | Number of Detected Concentrations Exceeding Puget Sound Background Metals Concentration |
|---------------------|--------------------------------|---------------------|-------------------|----------------------|----------------------------------------|----------------------------------------|------------------------------|---------------------------------------------------------------------------|----------------------------------------------------------------------|-----------------------------------------------------------------------------------------|
| VOCs<br>(continued) | Chloromethane                  | 8                   | 9                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                     | cis-1,2-Dichloroethene (DCE)   | 8                   | 9                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                     | cis-1,3-Dichloropropene        | 8                   | 9                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                     | Cyclohexane                    | 5                   | 5                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                     | Dibromochloromethane           | 8                   | 9                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                     | Dibromomethane                 | 3                   | 4                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                     | Dichlorodifluoromethane        | 5                   | 5                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                     | Ethylbenzene                   | 8                   | 9                 | 2                    | 24                                     | 2.3                                    | 305                          |                                                                           |                                                                      |                                                                                         |
|                     | Hexachlorobutadiene            | 8                   | 9                 | 0                    | NA                                     | NA                                     | 11                           |                                                                           |                                                                      |                                                                                         |
|                     | Hexachloroethane               | 3                   | 3                 | 0                    | NA                                     | NA                                     | 804                          |                                                                           |                                                                      |                                                                                         |
|                     | Isopropylbenzene               | 8                   | 9                 | 2                    | 9                                      | 0.48                                   | 86                           |                                                                           |                                                                      |                                                                                         |
|                     | Methyl acetate                 | 5                   | 5                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                     | Methyl tert-butyl ether (MTBE) | 5                   | 5                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                     | Methylcyclohexane              | 5                   | 5                 | 1                    | 0.65                                   | 0.65                                   |                              |                                                                           |                                                                      |                                                                                         |
|                     | Methylene chloride             | 8                   | 9                 | 1                    | 1.8                                    | 1.8                                    | 159                          |                                                                           |                                                                      |                                                                                         |
|                     | Methyliodide                   | 3                   | 4                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                     | n-Butylbenzene                 | 3                   | 4                 | 1                    | 84                                     | 84                                     |                              |                                                                           |                                                                      |                                                                                         |
|                     | n-Propylbenzene                | 3                   | 4                 | 1                    | 8.3                                    | 8.3                                    |                              |                                                                           |                                                                      |                                                                                         |
|                     | p-Isopropyltoluene             | 3                   | 4                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                     | sec-Butylbenzene               | 3                   | 4                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                     | Styrene                        | 8                   | 9                 | 0                    | NA                                     | NA                                     | 7070                         |                                                                           |                                                                      |                                                                                         |
|                     | tert-Butylbenzene              | 3                   | 4                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                     | Tetrachloroethene (PCE)        | 8                   | 9                 | 0                    | NA                                     | NA                                     | 190                          |                                                                           |                                                                      |                                                                                         |
|                     | Toluene                        | 8                   | 9                 | 2                    | 1.5                                    | 0.51                                   | 1090                         |                                                                           |                                                                      |                                                                                         |
|                     | trans-1,2-Dichloroethene       | 8                   | 9                 | 0                    | NA                                     | NA                                     | 1050                         |                                                                           |                                                                      |                                                                                         |
|                     | trans-1,3-Dichloropropene      | 8                   | 9                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                     | Trichloroethene (TCE)          | 8                   | 9                 | 0                    | NA                                     | NA                                     | 8950                         |                                                                           |                                                                      |                                                                                         |
|                     | Trichlorofluoromethane         | 8                   | 9                 | 0                    | NA                                     | NA                                     |                              |                                                                           |                                                                      |                                                                                         |
|                     | Vinyl acetate                  | 3                   | 4                 | 0                    | NA                                     | NA                                     | 13                           |                                                                           |                                                                      |                                                                                         |
|                     | Vinyl chloride                 | 8                   | 9                 | 0                    | NA                                     | NA                                     | 202                          |                                                                           |                                                                      |                                                                                         |
|                     | m,p-Xylenes                    | 8                   | 9                 | 2                    | 2.9                                    | 1.7                                    |                              |                                                                           |                                                                      |                                                                                         |
|                     | o-Xylene                       | 8                   | 9                 | 2                    | 5.7                                    | 3.9                                    |                              |                                                                           |                                                                      |                                                                                         |
|                     | Naphthalene                    | 46                  | 61                | 61                   | 1700000                                | 5.4                                    | 2100                         |                                                                           | 23                                                                   |                                                                                         |

**Notes:**

\*Carbon disulfide is a common laboratory chemical. Based on the review of existing analytical data quality, these detections are considered to be the result of laboratory cross-contamination. The results are not considered representative of site conditions.

<sup>1</sup> Background metals concentrations based on Puget Sound (when available) or Washington State background (Ecology 1994).

cPAHs = carcinogenic polycyclic aromatic hydrocarbons

HPAH = high molecular weight PAH

LPAH = low molecular weight PAH

NA = Not applicable, as there are no detections.

PAHs = polycyclic aromatic hydrocarbons

PCBs = polychlorinated biphenyls

PRG = Preliminary Remediation Goal

SVOCs = semivolatile organic compounds

TPH = total petroleum hydrocarbons

VOCs = volatile organic compounds

ug/kg = micrograms per kilogram

**Table 7-5**Final Scoping Memorandum  
Page 4 of 4



**Table 8-1 - Nationwide MGP Site Summary**

Bremerton Gas Works Site  
Bremerton, Washington

| MGP Site Name & Location                    | Reference                                                                                                                                                                      | Geologic Conditions                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Groundwater / Surfacewater                                                                                                                                                                                                                                                                                                                                                             | Contaminants of Concern                | Remedial Actions                                                                                                                                                                     | Cleanup Status               |
|---------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------|
| Cold Spring MGP Site<br>Cold Spring, NY     | Record of Decision (2010)<br><a href="http://www.dec.ny.gov/docs/remediation_hudson_pdf/e340026arod.pdf">http://www.dec.ny.gov/docs/remediation_hudson_pdf/e340026arod.pdf</a> | <ul style="list-style-type: none"> <li>Subsurface soils consist of 11-13 feet of debris containing fill underlain by a 15 foot thick layer of clay, which overlies bedrock.</li> <li>Contamination confined to the fill material.</li> </ul>                                                                                                                                                                                                                                                                         | <ul style="list-style-type: none"> <li>Groundwater flows to the west, towards the Hudson River which is adjacent to the site.</li> <li>No contamination was observed in river sediments.</li> </ul>                                                                                                                                                                                    | <p>BTEX</p> <p>PAHs</p>                | Excavation and off-site treatment/disposal.                                                                                                                                          | Scheduled to begin late 2014 |
| Saranac Street MGP Site<br>Plattsburgh, NY  | <a href="http://www.dec.ny.gov/docs/remediation_hudson_pdf/rod51000701.pdf">http://www.dec.ny.gov/docs/remediation_hudson_pdf/rod51000701.pdf</a>                              | <ul style="list-style-type: none"> <li>Subsurface soils consist of up to 21 feet of debris containing fill underlain by up to 15 foot thick layer of sandy alluvium. Beneath the alluvium lies a layer of dense glacial till, which overlies limestone bedrock.</li> <li>Contamination present down to and into fractured bedrock.</li> </ul>                                                                                                                                                                        | <ul style="list-style-type: none"> <li>The Saranac River forms the southern, western, and northern site boundary.</li> <li>Coal tar discharged into the river along the northwestern and northern site boundaries.</li> </ul>                                                                                                                                                          | <p>BTEX</p> <p>PAHs</p>                | <p><i>In situ</i> stabilization;</p> <p>Soil and sediment excavation with off-site treatment/disposal;</p> <p>Bedrock tar collection wells.</p>                                      | Remedial Action complete     |
| Waterville MFG Plant<br>Waterville, NY      | <a href="http://www.dec.ny.gov/docs/remediation_hudson_pdf/633041_1.pdf">http://www.dec.ny.gov/docs/remediation_hudson_pdf/633041_1.pdf</a>                                    | <ul style="list-style-type: none"> <li>Subsurface soils consist of one foot of topsoil over a fill unit up to 12 feet thick consisting of a substantial amount of ash as well as brown sand and gravel, coal fragments and bricks. Below the fill is a unit of glacial outwash sand and silt ranging in thickness from 1 to 10 feet. A dense kame moraine silt and gravel deposit of depths from 4 to 12 feet was found below the outwash unit.</li> <li>Contamination present up to 14 feet below grade.</li> </ul> | <ul style="list-style-type: none"> <li>A western flowing tributary to Big Creek forms the southern edge of the property, approximately 150 feet south of the site.</li> <li>The depth to groundwater ranges from approximately 4 to 12 feet below grade. Groundwater flow through the site is to the south-southwest and discharges into the Big Creek tributary.</li> </ul>           | <p>BTEX</p> <p>PAHs</p>                | Excavation and Disposal;<br>Institutional Controls;<br>Soil Cap.                                                                                                                     | No Further Action required   |
| Cortland Homer Former MGP Site<br>Homer, NY | <a href="http://www.dec.ny.gov/docs/remediation_hudson_pdf/rod712005.pdf">http://www.dec.ny.gov/docs/remediation_hudson_pdf/rod712005.pdf</a>                                  | <ul style="list-style-type: none"> <li>Subsurface soils consist of a fill layer ranging from 6 inches to 10 feet and is underlain by outwash sand that varies in thickness from 20 to 40 feet. A confining silt/clay layer was observed beneath the outwash sand.</li> <li>Contamination present up to 37 feet below grade.</li> </ul>                                                                                                                                                                               | <ul style="list-style-type: none"> <li>The West Branch of the Tioughnioga River is located 150 feet east of the site parcels.</li> <li>Depth to groundwater at the site is approximately 5 feet below grade. Groundwater flow is in a east to east-southeast direction. Groundwater discharges into the river.</li> <li>River sediments have been impacted by contaminants.</li> </ul> | <p>BTEX</p> <p>PAHs</p> <p>Cyanide</p> | <p>Excavation and disposal of source area soils;</p> <p><i>In situ</i> stabilization of downgradient contaminated soils;</p> <p>NAPL collection trench;</p> <p>Sediment removal.</p> | Remedial Design complete     |

**Table 8-1 - Nationwide MGP Site Summary**

Bremeton Gas Works Site  
Bremerton, Washington

| MGP Site Name & Location                               | Reference                                                                                                                                                                                                                                                      | Geologic Conditions                                                                                                                                                                                                                                                                                                                    | Groundwater / Surfacewater                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Contaminants of Concern                    | Remedial Actions                                                                                                                                         | Cleanup Status                                         |
|--------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------|
| Tacoma Tar Pits<br>Tacoma, WA                          | <a href="http://yosemite.epa.gov/R10/CLEANUP.NSF/sites/TacomaTarPits/\$FILE/TTP-5Yr-Review-Sept03.pdf">http://yosemite.epa.gov/R10/CLEANUP.NSF/sites/TacomaTarPits/\$FILE/TTP-5Yr-Review-Sept03.pdf</a>                                                        | •Subsurface soils consist of several feet of fill underlain by a layered sequence of silts and sands.                                                                                                                                                                                                                                  | •The Puyallup River is just northeast of the site.<br><br>•Groundwater occurs several feet below ground surface at the Tacoma Tar Pits site. The groundwater levels at the site vary in response to the tidal action in Commencement Bay and adjacent waterways. Groundwater flow directions vary depending on location, season, and tide stage. In general however, groundwater typically flows east (northwest and central portions of the site) and south (southeast portion of the site). | BTEX<br><br>PAHs                           | Excavation and stabilization;<br><br>Stabilized material placed in an engineered waste pile on site;<br><br>Soil cap;<br><br>Groundwater pump and treat. | Ongoing O&M for cover and groundwater treatment system |
| Oakland MGP<br>Oakland, CA                             | <a href="http://www.envirostor.dtsc.ca.gov/public/profile_report.asp?global_id=01490012">http://www.envirostor.dtsc.ca.gov/public/profile_report.asp?global_id=01490012</a>                                                                                    | •Subsurface soils consisting of up to 5 feet of gravel/sand fill underlain by a sandy layer that extends up to 15 feet below grade with interbedded layers of silt and clay. The sandy layer is underlain by a fine-grained layer of clay and silt up to 20 feet below grade.<br><br>•Contamination present up to 21 feet below grade. | •Groundwater is 2 to 7.5 feet bgs and flows towards the Oakland Inner Harbor, which is approximately 1000 feet away.                                                                                                                                                                                                                                                                                                                                                                          | TPH<br><br>BTEX<br><br>PAHs<br><br>Cyanide | Soil cap.                                                                                                                                                | Ongoing O&M                                            |
| Glens Falls - Mohican Street<br>MGP<br>Glens Falls, NY | <a href="http://www.dec.ny.gov/docs/remediation_hudson_pdf/557016roda2.pdf">http://www.dec.ny.gov/docs/remediation_hudson_pdf/557016roda2.pdf</a>                                                                                                              | •Subsurface soil consists of fill underlain by glacial fluvial deposits of sand, silt, silty sand, sandy silt. A layer of silty clay overlies bedrock, which is encountered between 9-29 feet below grade.<br><br>•Contamination present up to 19 feet below grade.                                                                    | •The site is bounded to the south by the Glens Falls feeder canal.<br><br>•Groundwater is 2-14 feet below grade and flows towards the Glens Falls canal and Hudson River.<br><br>•Canal sediments are impacted.                                                                                                                                                                                                                                                                               | BTEX<br><br>PAHs                           | Excavation of source material;<br><br>Oxygen delivery system;<br><br>Soil cover;<br><br>Institutional controls;<br><br>Dredging and disposal.            | Remedial Action approved                               |
| Gastown MGP Site<br>Tonawanda, NY                      | <a href="http://www.dec.ny.gov/docs/remediation_hudson_pdf/rod915171text.pdf">http://www.dec.ny.gov/docs/remediation_hudson_pdf/rod915171text.pdf</a><br><br><a href="http://www.dec.ny.gov/chemical/58387.html">http://www.dec.ny.gov/chemical/58387.html</a> | •Subsurface soils consist of up to 22 feet of debris containing fill underlain by layers of sand and silt for an additional 24 feet below grade.<br><br>•Contamination present down into the sand/silt layers.                                                                                                                         | •The site is bounded to the north-northwest by Tonawanda Creek.<br><br>•Groundwater is approximately 6 feet below grade and flows to the north into Tonawanda Creek.<br><br>•Creek sediments have been impacted.                                                                                                                                                                                                                                                                              | BTEX<br><br>PAHs                           | Excavation and disposal;<br><br><i>In situ</i> stabilization;<br><br>NAPL collection wells.                                                              | Scheduled to begin in 2013                             |
| Former Sacramento MGP<br>Sacramento, CA                | <a href="http://www.pge.com/about/environment/taking-responsibility/mgp/sacramento.shtml">http://www.pge.com/about/environment/taking-responsibility/mgp/sacramento.shtml</a>                                                                                  | •Subsurface soils consist of up to 15 feet of fill underlain by a layer containing mostly silts and clayey silts to 25 feet below grade. A layer of unconsolidated sand extends from approximately 25 feet to 85 feet below grade.<br><br>•Contamination present up to 45 feet below grade.                                            | •The site is located adjacent to the Sacramento River.<br><br>•Groundwater is present approximately 18 feet below grade and flow is strongly influenced by the Sacramento River and flows to the east.                                                                                                                                                                                                                                                                                        | TPH<br><br>BTEX<br><br>PAHs                | Excavation and disposal;<br><br>Pump and treat;<br><br><i>In situ</i> stabilization.                                                                     | <i>In situ</i> stabilization implemented late 2012     |
| Former Red Bluff MGP<br>Red Bluff, CA                  | <a href="http://www.pge.com/about/environment/taking-responsibility/mgp/red-bluff.shtml">http://www.pge.com/about/environment/taking-responsibility/mgp/red-bluff.shtml</a>                                                                                    | •Subsurface soil consists of up between 3 and 28 feet of debris containing fill material underlain by a silty clay / clayey silt with interbedded sand, gravel, and finer-grained sediments.<br><br>•Contamination present in the fill material.                                                                                       | •The site is bound to the east by the Sacramento River.<br><br>•Groundwater is present between 4 and 39 feet below grade and is heavily influenced by river level. Groundwater flows either east, or west, depending on river stage.                                                                                                                                                                                                                                                          | TPH<br><br>BTEX<br><br>PAHs                | Excavation and disposal of shallow source soils;<br><br><i>In situ</i> stabilization of deeper source soils.                                             | Remedial Action approved                               |

**Table 8-1 - Nationwide MGP Site Summary**

Bremeton Gas Works Site  
Bremerton, Washington

| MGP Site Name & Location                   | Reference                                                                                                                                                                                                                                                       | Geologic Conditions                                                                                                                                                                                                                                                                                                                                                                                                         | Groundwater / Surfacewater                                                                                                                                                                                                                                                                                    | Contaminants of Concern         | Remedial Actions                                                                                                                                                                 | Cleanup Status                                                                     |
|--------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------|
| Georgia MGP                                | <a href="http://www.geiconsultants.com/stuff/contentmgr/files/0/50b92d14438556ba3621879700e41ab4/download/insitustabilization.pdf">http://www.geiconsultants.com/stuff/contentmgr/files/0/50b92d14438556ba3621879700e41ab4/download/insitustabilization.pdf</a> | <ul style="list-style-type: none"> <li>Subsurface soil consists of up to 22 feet of fill underlain by 15 feet of alluvium above weathered bedrock.</li> <li>Contamination present to the bedrock.</li> </ul>                                                                                                                                                                                                                | The site is bounded to the west by the Chattahoochee River.                                                                                                                                                                                                                                                   | BTEX<br><br>PAHs                | <i>In situ</i> stabilization;<br><br>Excavation and disposal;<br><br>Groundwater barrier.                                                                                        | Remedial Action complete                                                           |
| Nyack MGP Site<br>Nyack, NY                | <a href="http://www.dec.ny.gov/docs/remediation_hudson_pdf/rod34404601.pdf">http://www.dec.ny.gov/docs/remediation_hudson_pdf/rod34404601.pdf</a>                                                                                                               | <ul style="list-style-type: none"> <li>Subsurface soil consists of up to 13 feet of fill underlain by native silty sand and glacial till layers. Sandstone bedrock was encountered approximately 40 feet below grade.</li> <li>Contamination present to the bedrock.</li> </ul>                                                                                                                                             | <ul style="list-style-type: none"> <li>The site is bound to the north by the Hudson River.</li> <li>The bedrock is a productive aquifer with the groundwater flowing upward through the bedrock. Groundwater generally flows toward the Hudson River.</li> <li>River sediments have been impacted.</li> </ul> | BTEX<br><br>PAHs                | Excavation and disposal;<br><br><i>In situ</i> stabilization;<br><br><i>In situ</i> chemical oxidation;<br><br>Dredging and disposal.                                            | Upland solidification complete.<br><br>Sediment removal scheduled to begin in 2013 |
| Manitowoc Former MGP Site<br>Manitowoc, WI | <a href="http://www.epa.gov/region05/cleanup/manitowoc/pdfs/manitowoc-completion-report-20070725.pdf">http://www.epa.gov/region05/cleanup/manitowoc/pdfs/manitowoc-completion-report-20070725.pdf</a>                                                           | <ul style="list-style-type: none"> <li>Subsurface soil consists of 3-10 feet of miscellaneous sand/silt/clay fill material overlying glacial deposits of sand with varying amounts of gravel, silt, and clay. Unconsolidated materials extend to at least 40 feet below ground and bedrock is estimated to be approximately 48 to 50 feet below grade.</li> <li>Contamination present up to 27 feet below grade.</li> </ul> | <ul style="list-style-type: none"> <li>The site is bound to the northwest by the Manitowoc River.</li> <li>Groundwater is present between 5 and 22 feet below grade and flows towards the Manitowoc River.</li> <li>River sediments have been impacted.</li> </ul>                                            | BTEX<br><br>PAHs<br><br>Cyanide | Shallow excavation and disposal;<br><br><i>In situ</i> stabilization;<br><br>Pump and treat (carbon);<br><br><i>In situ</i> stabilization for sediments failed;<br><br>Dredging. | Pump and Treat O&M<br><br>Sediment dredging scheduled to begin December 2013       |
| Kinston MGP Site<br>Kinston, NC            | <a href="http://www.neuselibrary.org/Kinston%20MGP%20Remedial%20Action%20Plan.pdf">http://www.neuselibrary.org/Kinston%20MGP%20Remedial%20Action%20Plan.pdf</a>                                                                                                 | <ul style="list-style-type: none"> <li>Subsurface soils consist of gravel fill underlain by a fine to medium grained sand layer with some gravel and clay up to 21 feet below grade. The sandy layer is underlain by a silt/clay which extends up to 45 feet below grade, followed by a silty sand extending to 55 feet below grade.</li> <li>Contamination present up to 23 feet below grade.</li> </ul>                   | <ul style="list-style-type: none"> <li>The Neuse River borders more than 50% of the Site including the north, west, and southwest boundaries.</li> <li>Groundwater flow is to the southwest, towards the Neuse River.</li> <li>River sediments have been impacted.</li> </ul>                                 | BTEX<br><br>PAHs<br><br>Cyanide | <i>In situ</i> stabilization;<br><br>Institutional controls.                                                                                                                     | Remedy selected, awaiting implementation                                           |

## Notes:

BTEX = benzene, toluene, ethylbenzene, and xylenes

cPAHs = carcinogenic polycyclic aromatic hydrocarbons

MGP = manufactured gas plant

NAPL = non-aqueous phase liquid

O&amp;M = operation and maintenance

PAHs = polycyclic aromatic hydrocarbons

TPH = total petroleum hydrocarbons

**Table 8-2 - Summary of Preliminary Contaminants of Potential Concern**

Bremerton Gas Works Site  
Bremerton, Washington

| Preliminary Contaminants of Potential Concern |                           | Reason for Inclusion |   |   |   |   | Potential Sources of MGP-Related Contaminants<br>(see Note 1) |             |                                    |                            |                                       |                             |                        |          | Potential Human Health and Environmental Concerns<br>(see Note 2) |                      |                                          |                                         |                            |                                  |
|-----------------------------------------------|---------------------------|----------------------|---|---|---|---|---------------------------------------------------------------|-------------|------------------------------------|----------------------------|---------------------------------------|-----------------------------|------------------------|----------|-------------------------------------------------------------------|----------------------|------------------------------------------|-----------------------------------------|----------------------------|----------------------------------|
|                                               |                           |                      |   |   |   |   | Feedstocks and Fuels                                          |             |                                    | MGP Process Byproducts     |                                       |                             |                        |          |                                                                   |                      |                                          |                                         |                            |                                  |
|                                               |                           |                      |   |   |   |   | Contaminant Group                                             | Contaminant | Potential MGP-Related Constituents | Other Sources (see Note 3) | Detected in Previous Sampling Efforts | Detected Above Initial PRGs | Other EPA Contaminants | Gasoline | Diesel fuel oil                                                   | Coal/coke briquettes | Ash, clinker, cinder, slag, soot, bricks | Spent scrubber media (tarry wood chips) | Tar (potentially as DNAPL) | Light oil (potentially as LNAPL) |
| Volatile Organic Compounds                    | Benzene                   | X                    | X | X | X |   | X                                                             |             |                                    |                            |                                       | X                           | X                      | X        | X                                                                 | X                    | X                                        | X                                       | X                          |                                  |
|                                               | Toluene                   | X                    | X | X |   |   | X                                                             |             |                                    |                            |                                       | X                           | X                      | X        | X                                                                 | X                    |                                          | X                                       | X                          |                                  |
|                                               | Ethylbenzene              | X                    | X | X | X |   | X                                                             |             |                                    |                            |                                       | X                           | X                      | X        | X                                                                 | X                    |                                          | X                                       | X                          |                                  |
|                                               | Xylenes                   | X                    | X | X | X |   | X                                                             |             |                                    |                            |                                       | X                           | X                      | X        | X                                                                 | X                    |                                          | X                                       | X                          |                                  |
|                                               | 1,2,3-Trichlorobenzene    |                      |   | X |   |   |                                                               |             |                                    |                            |                                       |                             |                        |          |                                                                   |                      |                                          | X                                       |                            |                                  |
|                                               | 1,2,4-Trimethylbenzene    | X                    | X | X |   |   | X                                                             |             |                                    |                            |                                       | X                           | X                      | X        | X                                                                 | X                    |                                          | X                                       | X                          |                                  |
|                                               | 1,3,5-Trimethylbenzene    |                      |   | X |   |   |                                                               |             |                                    |                            |                                       |                             |                        |          |                                                                   |                      |                                          | X                                       |                            |                                  |
|                                               | 1,4-Dichlorobenzene       |                      |   | X |   |   |                                                               |             |                                    |                            |                                       |                             |                        |          |                                                                   |                      | X                                        | X                                       | X                          |                                  |
|                                               | 1,4-Difluorobenzene       |                      |   | X |   |   |                                                               |             |                                    |                            |                                       |                             |                        |          |                                                                   |                      |                                          | X                                       |                            |                                  |
|                                               | 1,2-Dichloroethane        |                      | X | X | X |   |                                                               |             |                                    |                            |                                       |                             |                        |          |                                                                   |                      |                                          | X                                       | X                          | X                                |
|                                               | 2-butanone                |                      |   | X |   |   |                                                               |             |                                    |                            |                                       |                             |                        |          |                                                                   |                      |                                          | X                                       | X                          |                                  |
|                                               | Acetone                   |                      |   | X |   |   |                                                               |             |                                    |                            |                                       |                             |                        |          |                                                                   |                      |                                          | X                                       | X                          |                                  |
|                                               | Carbon disulfide          |                      |   | X |   |   |                                                               |             |                                    |                            |                                       |                             |                        |          |                                                                   |                      |                                          | X                                       | X                          |                                  |
|                                               | Carbon Tetrachloride      |                      | X | X | X |   |                                                               |             |                                    |                            |                                       |                             |                        |          |                                                                   |                      |                                          | X                                       | X                          | X                                |
|                                               | Chlorobenzene-d5          |                      |   | X |   |   |                                                               |             |                                    |                            |                                       |                             |                        |          |                                                                   |                      |                                          |                                         | X                          | X                                |
|                                               | Chloroform                |                      | X | X | X |   |                                                               |             |                                    |                            |                                       |                             |                        |          |                                                                   |                      |                                          | X                                       | X                          | X                                |
|                                               | cis-1,3-Dichloropropene   |                      | X | X | X |   |                                                               |             |                                    |                            |                                       |                             |                        |          |                                                                   |                      |                                          | X                                       | X                          |                                  |
|                                               | cis-1,2-Dichloroethene    |                      |   | X |   |   |                                                               |             |                                    |                            |                                       |                             |                        |          |                                                                   |                      |                                          |                                         | X                          |                                  |
|                                               | Cyclohexane               |                      |   | X |   |   |                                                               |             |                                    |                            |                                       |                             |                        |          |                                                                   |                      |                                          |                                         | X                          |                                  |
|                                               | Isopropylbenzene          |                      |   | X |   |   |                                                               |             |                                    |                            |                                       |                             |                        |          |                                                                   |                      |                                          |                                         | X                          | X                                |
|                                               | Methyl acetate            |                      |   | X |   |   |                                                               |             |                                    |                            |                                       |                             |                        |          |                                                                   |                      |                                          |                                         | X                          |                                  |
|                                               | Methylcyclohexane         |                      |   | X |   |   |                                                               |             |                                    |                            |                                       |                             |                        |          |                                                                   |                      |                                          |                                         |                            |                                  |
|                                               | Methylene chloride        |                      |   |   | X |   |                                                               |             |                                    |                            |                                       |                             |                        |          |                                                                   |                      |                                          | X                                       | X                          | X                                |
|                                               | n-Butylbenzene            |                      |   | X |   |   |                                                               |             |                                    |                            |                                       |                             |                        |          |                                                                   |                      |                                          |                                         | X                          |                                  |
|                                               | n-Hexane                  |                      |   | X | X |   |                                                               |             |                                    |                            |                                       |                             |                        |          |                                                                   |                      |                                          |                                         | X                          | X                                |
|                                               | n-Propylbenzene           |                      |   | X |   |   |                                                               |             |                                    |                            |                                       |                             |                        |          |                                                                   |                      |                                          |                                         | X                          |                                  |
|                                               | Pentafluorobenzene        |                      |   | X |   |   |                                                               |             |                                    |                            |                                       |                             |                        |          |                                                                   |                      |                                          |                                         |                            |                                  |
|                                               | p-Isopropyltoluene        |                      |   | X |   |   |                                                               |             |                                    |                            |                                       |                             |                        |          |                                                                   |                      |                                          |                                         |                            |                                  |
|                                               | sec-Butylbenzene          |                      |   | X |   |   |                                                               |             |                                    |                            |                                       |                             |                        |          |                                                                   |                      |                                          |                                         | X                          |                                  |
|                                               | Styrene                   |                      |   | X |   |   |                                                               |             |                                    |                            |                                       |                             |                        |          |                                                                   |                      |                                          |                                         | X                          | X                                |
|                                               | Tetrachloroethene         |                      |   | X |   |   |                                                               |             |                                    |                            |                                       |                             |                        |          |                                                                   |                      |                                          | X                                       | X                          | X                                |
|                                               | trans-1,3-Dichloropropene |                      | X | X | X | X |                                                               |             |                                    |                            |                                       |                             |                        |          |                                                                   |                      |                                          | X                                       | X                          |                                  |
|                                               | Trichloroethene           |                      | X | X | X | X |                                                               |             |                                    |                            |                                       |                             |                        |          |                                                                   |                      |                                          | X                                       | X                          | X                                |
|                                               | Trichlorofluoromethane    |                      |   |   | X |   |                                                               |             |                                    |                            |                                       |                             |                        |          |                                                                   |                      |                                          |                                         | X                          | X                                |
| Polycyclic Aromatic Hydrocarbons              | Benzo(a)anthracene        | X                    | X | X | X |   |                                                               |             | X                                  | X                          | X                                     | X                           |                        | X        | X                                                                 | X                    | X                                        | X                                       | X                          |                                  |
|                                               | Benzo(b)fluoranthene      | X                    | X | X | X |   |                                                               |             | X                                  | X                          | X                                     | X                           |                        | X        | X                                                                 | X                    | X                                        | X                                       | X                          |                                  |
|                                               | Benzo(k)fluoranthene      | X                    | X | X | X |   |                                                               |             | X                                  | X                          | X                                     | X                           |                        | X        | X                                                                 | X                    | X                                        | X                                       | X                          |                                  |
|                                               | Benzo(a)pyrene            | X                    | X | X | X |   |                                                               |             | X                                  | X                          | X                                     | X                           |                        | X        | X                                                                 | X                    | X                                        | X                                       | X                          |                                  |
|                                               | Chrysene                  | X                    | X | X | X |   |                                                               |             | X                                  | X                          | X                                     | X                           |                        | X        | X                                                                 | X                    | X                                        | X                                       | X                          |                                  |
|                                               | Dibenz(a,h)anthracene     | X                    | X | X | X |   |                                                               |             | X                                  | X                          | X                                     | X                           |                        | X        | X                                                                 | X                    | X                                        | X                                       | X                          |                                  |
|                                               | Indeno(1,2,3-cd)pyrene    | X                    | X | X | X |   |                                                               |             | X                                  | X                          | X                                     | X                           |                        | X        | X                                                                 | X                    | X                                        | X                                       | X                          |                                  |
|                                               | Acenaphthene              | X                    | X | X | X |   |                                                               | X           | X                                  | X                          | X                                     | X                           |                        | X        | X                                                                 |                      |                                          | X                                       | X                          |                                  |
|                                               | Acenaphthylene            | X                    | X | X | X |   |                                                               | X           | X                                  | X                          | X                                     | X                           |                        | X        | X                                                                 |                      |                                          | X                                       | X                          |                                  |
|                                               | Anthracene                | X                    | X | X | X |   |                                                               | X           | X                                  | X                          | X                                     | X                           |                        | X        | X                                                                 |                      |                                          | X                                       | X                          |                                  |
|                                               | Benzo(g,h,i)perylene      | X                    | X | X | X |   |                                                               | X           | X                                  | X                          | X                                     | X                           |                        | X        | X                                                                 |                      |                                          | X                                       | X                          |                                  |
|                                               | Dibenzofuran              |                      |   | X | X |   |                                                               |             |                                    |                            |                                       |                             |                        |          |                                                                   |                      |                                          |                                         | X                          | X                                |
|                                               | Fluoranthene              | X                    | X | X | X |   |                                                               | X           | X                                  | X                          | X                                     | X                           |                        | X        | X                                                                 |                      |                                          | X                                       | X                          |                                  |
|                                               | Fluorene                  | X                    | X | X | X |   |                                                               | X           | X                                  | X                          | X                                     | X                           |                        | X        | X                                                                 |                      |                                          | X                                       | X                          |                                  |
|                                               | Phenanthrene              | X                    | X | X | X |   |                                                               | X           | X                                  | X                          | X                                     | X                           |                        | X        | X                                                                 |                      |                                          | X                                       | X                          |                                  |
|                                               | Pyrene                    | X                    | X | X | X |   |                                                               | X           | X                                  | X                          | X                                     | X                           |                        | X        | X                                                                 |                      |                                          | X                                       | X                          |                                  |
|                                               | Methylnaphthalene, 1-     | X                    | X | X | X |   | X                                                             | X           | X                                  | X                          | X                                     | X                           | X                      | X        | X                                                                 | X                    |                                          | X                                       | X                          |                                  |
|                                               | Methylnaphthalene, 2-     | X                    | X | X | X |   | X                                                             | X           | X                                  | X                          | X                                     | X                           | X                      | X        | X                                                                 | X                    |                                          | X                                       | X                          |                                  |
|                                               | Naphthalene               | X                    | X | X | X |   | X                                                             | X           | X                                  | X                          | X                                     | X                           | X                      | X        | X                                                                 | X                    |                                          | X                                       | X                          |                                  |

**Table 8-2**

Final Scoping Memorandum  
Page 1 of 2

**Table 8-2 - Summary of Preliminary Contaminants of Potential Concern**

 Bremerton Gas Works Site  
 Bremerton, Washington

| Preliminary Contaminants of Potential Concern |                             | Reason for Inclusion               |                            |                                       |                             |                        | Potential Sources of MGP-Related Contaminants<br>(see Note 1) |                 |                      |                                          |                                         |                            |                                  |                                             | Potential Human Health and Environmental Concerns<br>(see Note 2) |                                |                                           |                                  |   |
|-----------------------------------------------|-----------------------------|------------------------------------|----------------------------|---------------------------------------|-----------------------------|------------------------|---------------------------------------------------------------|-----------------|----------------------|------------------------------------------|-----------------------------------------|----------------------------|----------------------------------|---------------------------------------------|-------------------------------------------------------------------|--------------------------------|-------------------------------------------|----------------------------------|---|
|                                               |                             |                                    |                            |                                       |                             |                        | Feedstocks and Fuels                                          |                 |                      | MGP Process Byproducts                   |                                         |                            |                                  |                                             |                                                                   |                                |                                           |                                  |   |
| Contaminant Group                             | Contaminant                 | Potential MGP-Related Constituents | Other Sources (see Note 3) | Detected in Previous Sampling Efforts | Detected Above Initial PRGs | Other EPA Contaminants | Gasoline                                                      | Diesel fuel oil | Coal/coke briquettes | Ash, clinker, cinder, slag, soot, bricks | Spent scrubber media (tarry wood chips) | Tar (potentially as DNAPL) | Light oil (potentially as LNAPL) | Gas Liquor and Emulsion (tar-water mixture) | Spent purifier media (iron oxide, tarry wood chips)               | Human Health Risk (Carcinogen) | Other Human Health Risks (non-Carcinogen) | Toxicity to Ecological Receptors |   |
| Other Semi-volatile Organic Compounds         | 1,1'-Biphenyl               |                                    |                            | X                                     |                             |                        |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             |                                                                   | X                              | X                                         | X                                |   |
|                                               | 1,2,4-Trichlorobenzene      |                                    |                            | X                                     |                             |                        |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             |                                                                   | X                              | X                                         | X                                |   |
|                                               | 2,4-Dimethylphenol          |                                    |                            | X                                     |                             |                        |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             |                                                                   |                                | X                                         | X                                |   |
|                                               | 4-Methylphenol              |                                    |                            | X                                     |                             |                        |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             |                                                                   |                                |                                           | X                                |   |
|                                               | Acetophenone                |                                    |                            | X                                     |                             |                        |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             |                                                                   |                                | X                                         |                                  |   |
|                                               | Benzyl butyl phthalate      |                                    |                            | X                                     |                             |                        |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             |                                                                   | X                              | X                                         | X                                |   |
|                                               | Benzaldehyde                |                                    |                            | X                                     |                             |                        |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             |                                                                   |                                | X                                         |                                  |   |
|                                               | Bis(2-ethylhexyl) phthalate |                                    |                            | X                                     |                             |                        |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             |                                                                   | X                              | X                                         | X                                |   |
|                                               | Caprolactam                 |                                    |                            | X                                     |                             |                        |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             |                                                                   |                                | X                                         |                                  |   |
|                                               | Carbazole                   | X                                  |                            |                                       |                             |                        |                                                               |                 |                      |                                          |                                         | X                          | X                                |                                             | X                                                                 | X                              |                                           | X                                | X |
|                                               | creosols                    | X                                  |                            |                                       |                             |                        |                                                               |                 |                      |                                          |                                         | X                          | X                                |                                             | X                                                                 | X                              |                                           | X                                | X |
|                                               | Dibenzofuran                | X                                  |                            |                                       |                             |                        |                                                               |                 |                      |                                          |                                         | X                          | X                                |                                             | X                                                                 | X                              |                                           | X                                | X |
|                                               | Di-n-butyl phthalate        |                                    |                            |                                       | X                           |                        |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             |                                                                   |                                |                                           | X                                | X |
|                                               | Isophorone                  |                                    |                            |                                       | X                           |                        |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             |                                                                   |                                | X                                         | X                                | X |
| Pentachlorophenol                             |                             |                                    | X                          | X                                     | X                           |                        |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             |                                                                   | X                              | X                                         | X                                |   |
| Phenol                                        | X                           |                                    |                            |                                       |                             |                        |                                                               |                 |                      |                                          | X                                       | X                          |                                  | X                                           | X                                                                 |                                | X                                         | X                                |   |
| Metals <sup>4</sup>                           | Aluminum                    |                                    |                            |                                       | X                           |                        |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             |                                                                   |                                |                                           | X                                | X |
|                                               | Antimony                    |                                    |                            |                                       | X                           | X                      |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             |                                                                   |                                |                                           | X                                | X |
|                                               | Arsenic                     |                                    | X                          |                                       | X                           | X                      |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             |                                                                   |                                | X                                         | X                                | X |
|                                               | Barium                      |                                    |                            |                                       | X                           |                        |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             |                                                                   |                                |                                           | X                                | X |
|                                               | Beryllium                   |                                    |                            |                                       | X                           |                        |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             |                                                                   |                                |                                           | X                                | X |
|                                               | Cadmium                     |                                    | X                          |                                       | X                           | X                      |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             |                                                                   |                                |                                           | X                                | X |
|                                               | Chromium                    |                                    | X                          |                                       | X                           | X                      |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             |                                                                   |                                |                                           | X                                | X |
|                                               | Cobalt                      |                                    |                            |                                       | X                           | X                      |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             |                                                                   |                                |                                           | X                                | X |
|                                               | Copper                      |                                    | X                          |                                       | X                           | X                      |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             |                                                                   |                                |                                           | X                                | X |
|                                               | Iron                        |                                    |                            |                                       | X                           |                        |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             |                                                                   |                                |                                           | X                                | X |
|                                               | Lead                        |                                    | X                          |                                       | X                           | X                      |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             |                                                                   |                                |                                           | X                                | X |
|                                               | Manganese                   |                                    |                            |                                       | X                           | X                      |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             |                                                                   |                                |                                           | X                                | X |
|                                               | Mercury                     |                                    |                            |                                       | X                           |                        |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             |                                                                   |                                |                                           | X                                | X |
|                                               | Nickel                      |                                    | X                          |                                       | X                           | X                      |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             |                                                                   |                                |                                           | X                                | X |
|                                               | Selenium                    |                                    |                            |                                       | X                           |                        |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             |                                                                   |                                |                                           | X                                | X |
|                                               | Silver                      |                                    |                            |                                       | X                           |                        |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             |                                                                   |                                |                                           | X                                | X |
|                                               | Thallium                    |                                    |                            |                                       | X                           | X                      |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             |                                                                   |                                |                                           | X                                | X |
|                                               | Vanadium                    |                                    |                            |                                       | X                           | X                      |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             |                                                                   |                                |                                           | X                                | X |
| Zinc                                          |                             |                                    | X                          | X                                     | X                           |                        |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             |                                                                   |                                | X                                         | X                                |   |
| Polychlorinated Biphenyls (PCBs) <sup>5</sup> |                             |                                    |                            |                                       |                             | X                      |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             |                                                                   | X                              | X                                         | X                                |   |
| Pesticides <sup>6</sup>                       |                             |                                    |                            |                                       |                             | X                      |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             |                                                                   | X                              | X                                         | X                                |   |
| Other                                         | Cyanide, WAD                | X                                  |                            |                                       |                             |                        |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             | X                                                                 |                                | X                                         | X                                |   |
|                                               | Cyanide, total              | X                                  |                            |                                       |                             |                        |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             | X                                                                 |                                | X                                         | X                                |   |
|                                               | Sulfide                     | X                                  |                            |                                       |                             |                        |                                                               |                 |                      |                                          |                                         |                            |                                  |                                             |                                                                   |                                |                                           | X                                |   |

**Notes**

- 1) Contaminants of Potential Concern (COPCs) associated with MGP sources based on typical composition of MGP-related feedstocks and byproducts (see Section 2.3.1.1).
- 2) Potential Human Health and Environmental Concerns identified based on whether risk-based screening levels or potential ARARs for human health (carinogenic health effects), human health (non-carcinogenic health effects), or ecological health effects were identified during development of initial Preliminary Remediation Goals (PRGs) (see Section 6).
- 3) Other Sources include other historical operations at the site or regional sources of contamination.
- 4) Although previously detected at the Site, non-toxic metals (calcium, magnesium, sodium and potassium) are not included herein. Initial PRGs were not developed for these metals because they are essential nutrients that can be tolerated in high doses by living systems.
- 5) PCBs were previously analyzed for and not detected above reporting limits in soil or groundwater at the Site. However, the full standard list of PCB aroclors are COPCs for further evaluation.
- 6) The full standard list of pesticides, identified and quantified by EPA Method 8081B, are preliminary COPCs.

This table is not intended to be an exhaustive and complete preliminary list of Site COPCs. The RI/FS will include analysis of samples for the full standard list of analytes under each contaminant group. This list will be evaluated and revised as data is collected and specific contaminants can either be eliminated from the COPC list or are identified as Site COPCs.

**Table 8-2**

Table 8-3 - Remedial Technologies for NAPL

Bremerton Gas Works Site  
Bremerton, Washington

| NAPL General Response Actions | Remedial Technology                | Process Options                                                               | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |
|-------------------------------|------------------------------------|-------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Institutional Controls        | Access Restrictions                | Fences and warning signs to control Site access                               | Signs, fences, or other measures to prevent access to the Site.                                                                                                                                                                                                                                                                                                                                                                                                                                       |
|                               | Use Restrictions                   | Use restrictions and monitoring to prevent disturbance of engineered controls | Covenant placed on property that limits or prohibits activities that may interfere with a cleanup action or result in exposure to hazardous substances. Use and deed restrictions are often used in conjunction with other technology approaches.                                                                                                                                                                                                                                                     |
|                               |                                    | Deed restrictions addressing soil disturbance and/or groundwater wells        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
| In Situ Containment           | Vertical Barriers                  | Slurry Wall                                                                   | Control lateral movement of NAPL by excavating a trench and backfilling with a low-permeability material (e.g., bentonite slurry), or <i>in situ</i> mixing of bentonite with native soils.                                                                                                                                                                                                                                                                                                           |
|                               |                                    | Sheet Pile Wall                                                               | Control lateral movement of NAPL by installing (driving or vibrating) steel or plastic sheet piling.                                                                                                                                                                                                                                                                                                                                                                                                  |
|                               |                                    | Grout Curtain                                                                 | Control lateral movement of NAPL by pressure injecting hydraulic cements, clays, bentonite, and silicates into the formation through tightly spaced borings using jetting tools.                                                                                                                                                                                                                                                                                                                      |
| In Situ Treatment             | Low-Temperature Thermal Treatment  | Hot Water Injection                                                           | A variety of heating methods, heating to temperatures less the boiling point of water, increasing the mobility and solubility of NAPL. Contaminated liquids, including NAPL, are removed by pumping from wells, and contaminants are treated. Heating can be performed by injecting hot water in vertical wells, thermal conduction from vertical heated wells, or by electrical resistance when voltage is applied between subsurface electrodes.                                                    |
|                               |                                    | Electrical Resistance Heating                                                 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
|                               |                                    | Thermal Conductive Heating                                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
|                               | Mid-Temperature Thermal Treatment  | Steam Injection                                                               | The subsurface is heated to temperatures near the boiling point of water, volatilizing or destroying (by pyrolysis) volatile organic compounds. Contaminated vapors are collected using soil vapor extraction, contaminated liquids are removed by pumping from wells, and contaminants are treated. Heating can be performed by injecting steam in vertical wells, thermal conduction from vertical heated wells, or by electrical resistance when voltage is applied between subsurface electrodes. |
|                               |                                    | Electrical Resistance Heating                                                 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
|                               |                                    | Thermal Conductive Heating                                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
|                               | High-Temperature Thermal Treatment | Electrical Resistance Heating                                                 | The subsurface is heated to temperatures above the boiling point of water, volatilizing or destroying (by pyrolysis) volatile and semi-volatile organic compounds. Contaminated vapors are collected using soil vapor extraction, contaminated liquids are removed by pumping from wells, and contaminants are treated. Heating can be performed by thermal conduction from vertical heated wells, or by electrical resistance when voltage is applied between subsurface electrodes.                 |
|                               |                                    | Thermal Conductive Heating                                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
|                               | Stabilization                      | Solidification/ Stabilization                                                 | Soil containing NAPL is stabilized by adding amendments to solidify or immobilize contaminants. Potential amendments include polymers, pozzolans, and cement. Amendments can be mixed with soil <i>in situ</i> using large-diameter augers, soil mixers, or similar equipment.                                                                                                                                                                                                                        |
|                               | Chemical Treatment                 | Chemical oxidation                                                            | Chemical oxidation involves the injection of chemical oxidants into the subsurface to react with and destroy organic contaminants. Common oxidants include hydrogen peroxide, potassium permanganate, ozone, and sodium persulfate.                                                                                                                                                                                                                                                                   |
| Removal                       | NAPL Pumping                       | Pumping of NAPL from wells and trenches                                       | Pumping to remove NAPL that accumulates in a well or trench.                                                                                                                                                                                                                                                                                                                                                                                                                                          |
|                               | Surfactant Enhanced Recovery       | Pumping of mobilized NAPL                                                     | Surfactants are injected near NAPL zones in groundwater to mobilize the NAPL, and then the mobilized NAPL is extracted. May be applied with injection-withdrawal technique or with recirculating system.                                                                                                                                                                                                                                                                                              |
|                               | Excavation                         | Excavation                                                                    | NAPL is removed by excavating soil containing NAPL.                                                                                                                                                                                                                                                                                                                                                                                                                                                   |
| Ex Situ Treatment             | Thermal                            | Co-Burning                                                                    | Combustion of coal tar or tar contaminated soil with coal in utility boilers and cement kilns.                                                                                                                                                                                                                                                                                                                                                                                                        |
|                               |                                    | Incineration                                                                  | When soil or sediment containing NAPL is heated to temperatures above 1,400°F, contaminants are directly oxidized.                                                                                                                                                                                                                                                                                                                                                                                    |
| Disposal                      | Off-Site Management                | Recycling of recovered NAPL                                                   | Reuse of recovered product.                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |
|                               |                                    | Disposal of recovered NAPL via incineration                                   | Treatment of NAPL via incineration at a hazardous waste treatment facility.                                                                                                                                                                                                                                                                                                                                                                                                                           |

Notes:  
BTEx = benzene, toluene, ethylbenzene, and xylenes  
cPAHs = carcinogenic polycyclic aromatic hydrocarbons  
NAPL = non-aqueous phase liquid  
O&M = operation and maintenance  
PAHs = polycyclic aromatic hydrocarbons  
TPH = total petroleum hydrocarbons

Table 8-4 - Remedial Technologies for Soil

Bremerton Gas Works Site  
Bremerton, Washington

| Soil General Response  | Remedial Technology                | Process Options                                                               | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
|------------------------|------------------------------------|-------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Institutional Controls | Access Restrictions                | Fences and warning signs to control Site access                               | Signs, fences, or other measures to prevent access to the property.                                                                                                                                                                                                                                                                                                                                                                                                                                            |
|                        | Use Restrictions                   | Use restrictions and monitoring to prevent disturbance of engineered controls | Covenant placed on the property that limits or prohibits activities that may interfere with a cleanup action or result in exposure to hazardous substances.                                                                                                                                                                                                                                                                                                                                                    |
|                        |                                    | Deed restrictions addressing soil disturbance                                 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
| In Situ Containment    | Capping                            | Permeable soil cover                                                          | Placing clean soil on the surface provides a barrier that prevents exposure to underlying soil but allows storm water to infiltrate.                                                                                                                                                                                                                                                                                                                                                                           |
|                        |                                    | Low-permeability cap                                                          | Low-permeability caps may be constructed of low-permeability soil such as clay or an engineered material such as asphalt or concrete. This cap would not only prevent exposure to underlying soils, but would also minimize stormwater infiltration through potentially contaminated materials, thereby reducing mobility of contaminants located in the unsaturated soil zone. Engineered materials could also be used in areas requiring a durable surface, such as high-traffic areas.                      |
|                        |                                    | Impervious cap                                                                | Impervious caps may be constructed of low-permeability soil such as clay or an engineered material such as asphalt or concrete, overlain by an additional impermeable layer. This cap would not only prevent exposure to underlying soils, but would also prevent stormwater from infiltrating through potentially contaminated soils beneath the cap, thereby reducing mobility of contaminants located in the unsaturated soil zone. Often combined with barrier wall technology to fully encapsulate soils. |
| In Situ Treatment      | Physical Removal and Treatment     | Passive venting of soil vapors                                                | Passive soil venting is a less aggressive version of soil vapor extraction that is usually applied to prevent contaminated soil vapors from migrating into buildings or crawl spaces. In passive venting, soil vapors beneath a building foundation are vented to the atmosphere either through atmospheric pressure changes or by applying a low vacuum with a ventilation fan. Vented vapors can be passed through activated carbon for treatment if necessary.                                              |
|                        |                                    | Soil vapor extraction                                                         | Soil vapor extraction applies a vacuum to subsurface soil to volatilize contamination and extract soil vapor. Vapor stream is treated above ground to remove contamination before discharge.                                                                                                                                                                                                                                                                                                                   |
|                        | Low-Temperature Thermal Treatment  | Hot Water Injection                                                           | The subsurface is heated to temperatures less than the boiling point of water, increasing the mobility and solubility of NAPL and NAPL constituents. Contaminated liquids are removed by pumping from wells, and contaminants are treated. Heating can be performed by injecting steam in vertical wells, thermal conduction from vertical heated wells, or by electrical resistance when voltage is applied between subsurface electrodes.                                                                    |
|                        |                                    | Electrical Resistance Heating                                                 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
|                        |                                    | Thermal Conductive Heating                                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
|                        | Mid-Temperature Thermal Treatment  | Steam Injection                                                               | The subsurface is heated to temperatures near the boiling point of water, volatilizing or destroying (by pyrolysis) volatile organic compounds. Contaminated vapors are collected using soil vapor extraction, contaminated liquids are removed by pumping from wells, and contaminants are treated. Heating can be performed by injecting steam in vertical wells, thermal conduction from vertical heated wells, or by electrical resistance when voltage is applied between subsurface electrodes.          |
|                        |                                    | Electrical Resistance Heating                                                 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
|                        |                                    | Thermal Conductive Heating                                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
|                        | High-Temperature Thermal Treatment | Thermal Conductive Heating                                                    | The subsurface is heated to temperatures above the boiling point of water, volatilizing or destroying (by pyrolysis) volatile and semi-volatile organic compounds. Contaminated vapors are collected using soil vapor extraction, contaminated liquids are removed by pumping from wells, and contaminants are treated. Heating can be performed by thermal conduction from vertical heated wells, or by electrical resistance when voltage is applied between subsurface electrodes.                          |
|                        |                                    | Vitrification                                                                 | Soil is heated via electrical current to temperatures greater than 2,400°F, destroying contaminants and fusing soil into a glassy matrix.                                                                                                                                                                                                                                                                                                                                                                      |

Table 8-4

Table 8-4 - Remedial Technologies for Soil

Bremerton Gas Works Site  
Bremerton, Washington

| Soil General Response | Remedial Technology        | Process Options               | Description                                                                                                                                                                                                                                                                                                                                   |
|-----------------------|----------------------------|-------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| In Situ Treatment     | Stabilization              | Solidification/ Stabilization | Soil or sediment is stabilized by adding amendments to solidify or immobilize contaminants. Potential amendments include polymers, pozzolans, and cement. Amendments can be mixed with soil <i>in situ</i> using large-diameter augers, soil mixers, or similar equipment.                                                                    |
|                       | Chemical Treatment         | Chemical oxidation            | Chemical oxidation involves the injection of chemical oxidants into the subsurface to react with and destroy organic contaminants. Common oxidants include hydrogen peroxide, potassium permanganate, ozone, and sodium persulfate, which have been shown to destroy a wide range of contaminants in soil.                                    |
|                       | Bioremediation             | Bioventing                    | Bioventing supplies oxygen to unsaturated soil to increase aerobic biodegradation rates and may be designed to increase the air exchange rate through the soil.                                                                                                                                                                               |
|                       |                            | Amendment Injection           | Biodegradation of contaminants by indigenous soil microbes can be enhanced by amending soil with nutrients, moisture, and oxygen (typically provided by injecting air or solutions into wells or trenches).                                                                                                                                   |
| Removal               | Excavation                 | Excavation                    | Excavators, backhoes, and other conventional earth moving equipment are the most common equipment used to remove contaminated soil from upland areas.                                                                                                                                                                                         |
| Ex Situ Treatment     | Physical                   | Solidification/ Stabilization | Amendments are added to excavated soil or sediment to immobilize and/or bind contaminants within the stabilized product. Depending on the proportion of amending agents, the end product may take on the form of a quasi-soil/concrete material that could later be used as bulk fill.                                                        |
|                       | Thermal                    | Co-Burning                    | Combustion of Manufactured Gas Plant residues, such as coal tar and tar contaminated soil, with coal in utility boilers and cement kilns.                                                                                                                                                                                                     |
|                       |                            | Thermal desorption            | Low-temperature thermal desorption involves heating soils or sediments to temperatures between 200°F and 600°F until volatile and semivolatile chemicals of concern (COCs) such as benzene and naphthalene evaporate. Exhaust gases produced by the process are typically combusted.                                                          |
|                       |                            | Incineration                  | When soil is heated to temperatures above 1,400°F, contaminants are directly oxidized.                                                                                                                                                                                                                                                        |
|                       | Chemical/ Physical         | Particle washing              | In particle washing, soil is put in contact with an aqueous solution to remove contaminants from the soil particles. The suspension is often also used to separate fine particles from coarser particles, allowing beneficial use of the coarser fraction (if sufficiently clean) at the Site.                                                |
|                       |                            | Solvent extraction            | Solvent extraction is a variant of soil washing in which an organic solvent (rather than an aqueous solution) is put in contact with the soil to remove contaminants.                                                                                                                                                                         |
|                       | Bioremediation             | Landfarming                   | Microbial population potentially enhanced with nutrients, moisture, and bioaugmentation to treat contaminated soil on lined beds with tilling and irrigation.                                                                                                                                                                                 |
|                       |                            | Biopiles                      | Microbial population potentially enhanced with nutrients, moisture, aeration, and bioaugmentation to treat contaminated soil in stockpiles.                                                                                                                                                                                                   |
|                       |                            | Bioreactor                    | Microbial population potentially enhanced with nutrients, moisture, aeration, and bioaugmentation to treat contaminated soil in enclosed reactor vessels.                                                                                                                                                                                     |
|                       | Asphalt Batching           | Cold-Mix Asphalt Batching     | Encapsulation of contaminant by blending residues, wet aggregate and asphalt emulsion at ambient temperature.                                                                                                                                                                                                                                 |
|                       |                            | Hot-Mix Asphalt Batching      | Encapsulation of contaminant by blending residues, wet aggregate and asphalt emulsion at high temperature.                                                                                                                                                                                                                                    |
| Disposal              | Confined On-Site Disposal  | Confined On-site disposal     | Excavated soils exceeding applicable cleanup standards could potentially be placed on site in a specially designed upland confined disposal facility (CDF). Depending on the leachability of confined materials, the CDF could potentially include a liner and a liquid collection system to prevent leachate from contaminating groundwater. |
|                       | Off-Site Landfill Disposal | Subtitle D (Solid Waste)      | Contaminated soils from the Site may be transported to an off-site, permitted disposal facility. This disposal method provides for secure, long-term containment of hazardous and non-hazardous solid wastes.                                                                                                                                 |
|                       |                            | Subtitle C (Hazardous Waste)  |                                                                                                                                                                                                                                                                                                                                               |

Notes:  
BTEX = benzene, tolouene, ethylbenzene, and xylenes  
cPAHs = carcinogenic polycyclic aromatic hydrocarbons  
NAPL = non-aqueous phase liquid  
O&M = operation and maintenance  
PAHs = polycyclic aromatic hydrocarbons  
TPH = total petroleum hydrocarbons

Table 8-4



Table 8-5 - Remedial Technologies for Groundwater

Bremerton Gas Works Site  
Bremerton, Washington

| Groundwater General Response Actions | Remedial Technology           | Process Options                                  | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
|--------------------------------------|-------------------------------|--------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Institutional Controls               | Deed Restrictions             | Deed restrictions to preclude drinking water use | Covenant placed on property that limits or prohibits activities that may interfere with a cleanup action or result in exposure to hazardous substances.                                                                                                                                                                                                                                                                                                        |
|                                      |                               | Deed restrictions addressing groundwater wells   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
| Monitored Natural Attenuation        | Monitored Natural Attenuation | Groundwater Monitoring                           | Provides monitoring to document the presence and effectiveness of natural processes in removing or containing Site chemicals of concern (COCs).                                                                                                                                                                                                                                                                                                                |
| In Situ Containment                  | Vertical Barriers             | Slurry Wall                                      | Control lateral movement of contaminated groundwater by installing impermeable vertical barriers. Vertical barriers can be constructed of a variety of materials and installation techniques, including driving or vibrating steel sheet piling, excavation of a trench and backfilling with a low-permeability material (e.g., bentonite slurry), <i>in situ</i> mixing of bentonite with native soils, or pressure injecting hydraulic cement and bentonite. |
|                                      |                               | Sheet Pile Wall                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
|                                      |                               | Grout Curtain                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
|                                      | Pumping                       | Pumping from vertical wells or trenches          | Migration of contaminants dissolved in groundwater can be controlled by pumping groundwater from vertical wells or trenches, creating a capture zone within which groundwater flows toward the capture point.                                                                                                                                                                                                                                                  |
|                                      | Stormwater Controls           | Targeted Infiltration                            | A hydraulic barrier can be created by collecting and infiltrating stormwater and forming a local groundwater "mound."                                                                                                                                                                                                                                                                                                                                          |
|                                      |                               | Reduced Infiltration                             | Hydraulic controls can reduce localized infiltration and seepage of stormwater in impacted areas along the shoreline.                                                                                                                                                                                                                                                                                                                                          |
| In Situ Treatment                    | Permeable Reactive Barrier    | Sorptive/Reactive Wall                           | A 40-foot-deep trench may be excavated in the uplands and filled with a permeable material that sorbs dissolved-phase contaminants, facilitating further biodegradation and limiting contaminant migration toward marine sediment and surface water and offshore groundwater. A shallow trench could also excavated on the beach near the shoreline, but would be impacted by brackish water and tidally-influenced groundwater gradients.                     |
|                                      | Chemical Treatment            | Chemical Oxidation                               | Chemical oxidation involves the injection of oxidant solutions into saturated groundwater to react with and destroy organic contaminants. Common oxidants include hydrogen peroxide, potassium permanganate, ozone, and sodium persulfate.                                                                                                                                                                                                                     |
|                                      | Bioremediation                | Amendment Injection                              | Injecting compounds, such as peroxides, oxygen-releasing compound, or nutrients, that enhance degradation of contaminants.                                                                                                                                                                                                                                                                                                                                     |
|                                      |                               | Biosparging                                      | Biosparging involves the injection of oxygen, and sometimes nutrients, to groundwater to enhance aerobic bioattenuation of organic compounds. For volatile contaminants, soil vapor extraction or bioventing may be concurrently applied for unsaturated soil.                                                                                                                                                                                                 |
| Removal                              | Groundwater Extraction        | Pumping from Vertical Wells or Trenches          | Groundwater can be removed from the subsurface by pumping fluids from wells or trenches.                                                                                                                                                                                                                                                                                                                                                                       |
| Ex Situ Treatment                    | Physical/ Chemical            | Adsorption                                       | Granular activated carbon (GAC) can be used to remove organic contaminants. Contaminated groundwater is passed through a bed of GAC, and hydrophobic organic compounds in solution adsorb onto the carbon until the carbon becomes depleted or saturated. Depleted GAC may be regenerated or disposed off Site.                                                                                                                                                |
|                                      |                               | Air Stripping                                    | Contaminated groundwater and air are typically passed counter-currently through a tower, and volatile contaminants (such as benzene and, to a lesser extent, naphthalene) transfer from the water to the air. The contaminant-laden air is usually treated by activated carbon and then discharged to the atmosphere.                                                                                                                                          |
|                                      |                               | Advanced Oxidation Processes                     | Involves adding chemicals that directly oxidize organic contaminants in water. Process options include ozonation, hydrogen peroxide (with or without catalysts such as Fenton's Reagent or ultraviolet light), and permanganate.                                                                                                                                                                                                                               |
|                                      | Biological                    | Biotreatment                                     | Contaminated groundwater is passed through a biological reactor in which a contaminant-degrading microbial culture is maintained, generally by adding nutrients and oxygen and controlling temperature, pH, and other parameters. Process options include bioslurry reactors, fixed-film bioreactors, and constructed wetlands.                                                                                                                                |
| Disposal                             | Off-Site Management           | Discharge to Sanitary Sewer                      | Groundwater is discharged to the local sanitary sewer system. Pre-treatment of groundwater may not be required if concentrations of chemicals of concern (COCs) meet discharge criteria. Water containing high concentrations of solids (e.g., from construction dewatering) would likely need to be passed through a settling tank or filter to meet discharge requirements.                                                                                  |
|                                      |                               | Discharge to Surface Water                       | Extracted groundwater may also be discharged to surface water, although this discharge option would likely require a National Pollutant Discharge Elimination System (NPDES) permit. Water discharged to surface water would have to meet strict water quality requirements and would likely require treatment before discharge.                                                                                                                               |
|                                      | On-Site Management            | Re-introduction to Groundwater                   | Extracted groundwater may also be discharged on site to groundwater via infiltration galleries or injection wells. Contaminated groundwater would likely require treatment before discharge via this method.                                                                                                                                                                                                                                                   |

Notes:  
BTEX = benzene, toluene, ethylbenzene, and xylenes  
cPAHs = carcinogenic polycyclic aromatic hydrocarbons  
NAPL = non-aqueous phase liquid  
O&M = operation and maintenance  
PAHs = polycyclic aromatic hydrocarbons  
TPH = total petroleum hydrocarbons

Table 8-6 - Remedial Technologies for Sediment

Bremerton Gas Works Site  
Bremerton, Washington

| Sediment General Response Actions | Remedial Technology        | Process Options                                                                                                           | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
|-----------------------------------|----------------------------|---------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Institutional Controls            | Use Restrictions           | Governmental advisories and public outreach on fish/shellfish consumption                                                 | Institutional controls are measures undertaken to limit or prohibit activities that may interfere with a cleanup action or result in exposure to hazardous substances.                                                                                                                                                                                                                                                                                                         |
|                                   |                            | Easements or restrictive covenants to limit activities which may damage the remedy or increase the potential for exposure |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
|                                   |                            | Monitoring and notification of waterway users to restrict specific activities to protect the remedy                       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
| Monitored Natural Recovery        | Monitored Natural Recovery | Monitored Natural Recovery                                                                                                | A passive remedial approach which relies on monitoring of ongoing, natural processes (physical, biological, and/or chemical mechanisms) that act together to reduce the risk (bioavailability and/or toxicity) of the Site COCs. Monitoring is required to evaluate the effectiveness and frequently includes multiple lines of evidence.                                                                                                                                      |
|                                   | Enhanced Natural Recovery  | Thin-Layer Sand Placement                                                                                                 | Thin-layer placement normally accelerates natural recovery by adding a layer of clean sediment over contaminated sediment. The acceleration can occur through several processes, including increased dilution through bioturbation of clean sediment mixed with underlying contaminants. Thin-layer placement is typically different than the <i>in situ</i> isolation caps, because it is not designed to provide long-term isolation of contaminants from benthic organisms. |
| <i>In Situ</i> Containment        | Capping (Non-reactive)     | Engineered Sand Cap                                                                                                       | An engineered sand cap consists of a layer of granular material placed over contaminated sediments to contain and isolate them from the biologically active surface zone. Engineered caps may also include erosion protection or stability layers such as geosynthetics or armoring materials.                                                                                                                                                                                 |
|                                   |                            | Post-Dredge Residuals Management Layer                                                                                    | Similar to cap placement methods described above, with the exception that granular material is applied after dredging to manage residual contamination resulting from dredging. In some cases, a reactive media may be included in the residuals/backfill layer.                                                                                                                                                                                                               |
| <i>In Situ</i> Treatment          | Physical/ Chemical         | Permeable Reactive Cap                                                                                                    | A permeable reactive cap includes a reactive material (such as organoclay, coke, coal, or activated carbon) and similar to a sand cap is placed over contaminated sediments to isolate and contain the contaminated sediments. The reactive material also provides treatment by sorping or binding COCs (dissolved and/or NAPL) and further limiting migration into overlying sediment porewater and surface water.                                                            |
|                                   |                            | Stabilization                                                                                                             | This technology involves adding amendments to in situ sediment that immobilize and/or bind contaminants within the stabilized media.                                                                                                                                                                                                                                                                                                                                           |
|                                   | Bioremediation             | Amendment Injection                                                                                                       | Biodegradation of contaminants by indigenous soil microbes can be enhanced by amending soil with nutrients, moisture, and oxygen (typically provided by injecting into wells or trenches).                                                                                                                                                                                                                                                                                     |

Table 8-6 - Remedial Technologies for Sediment

Bremerton Gas Works Site  
Bremerton, Washington

| Sediment General Response Actions | Remedial Technology        | Process Options                             | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |
|-----------------------------------|----------------------------|---------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Removal                           | Dredging                   | Hydraulic                                   | Dredging is the removal of sediment in the wet and is primarily accomplished with hydraulic or mechanical equipment. Hydraulic dredging removes and transports sediment with entrained water in a slurry. Mechanical dredging uses mechanical equipment/force to dislodge and excavate sediment in the wet. Dredging effectiveness may be limited by resuspension, release of COCs (i.e., dissolved, particles, and sheens) to water and volatilization to air during dredging, and residual COCs remaining after dredging (USACE 2008). These effects may be reduced by use of containment (e.g., sheet pile, silt curtains) and best management practices. |
|                                   |                            | Mechanical                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
| Ex Situ Treatment                 | Physical                   | Physical Separation                         | The volume of excavated or dredged contaminated materials may be reduced by physically separating the materials into two or more fractions that can be handled separately.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |
|                                   |                            | Stabilization                               | This technology involves adding amendments to excavated sediment that immobilize and/or bind contaminants within the stabilized media.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
|                                   | Thermal                    | Thermal Desorption                          | Low-temperature thermal desorption involves heating soils or sediments to temperatures between 200°F and 600°F until volatile and semivolatile COCs such as benzene and naphthalene evaporate. Exhaust gases produced by the process are typically combusted.                                                                                                                                                                                                                                                                                                                                                                                                |
|                                   |                            | Incineration                                | When sediment is heated to temperatures above 1,400°F, contaminants are directly oxidized.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |
| Disposal                          | On-Site Beneficial Use     | Sand/Aggregate Reclamation                  | Dredged material with high sand contents that undergo particle separation may be available for use as concrete aggregate or general upland fill.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
|                                   |                            | Topsoil Feedstock                           | Dredged material may be used as non-organic feedstock for topsoil (i.e., material would be blended with organics).                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |
|                                   | Confined On-Site Disposal  | Confined On-site Disposal                   | Removed sediments exceeding applicable cleanup standards could potentially be placed on Site in a specially designed upland CDF. Depending on the leachability of confined materials, the CDF could potentially include a liner and a liquid collection system to prevent leachate from contaminating groundwater.                                                                                                                                                                                                                                                                                                                                           |
|                                   |                            | Near-shore Confined Disposal Facility (CDF) | Removed sediments exceeding applicable cleanup standards could potentially be placed on Site in a specially designed CDF built along the shoreline. Construction would require significant filling and conversion of aquatic lands.                                                                                                                                                                                                                                                                                                                                                                                                                          |
|                                   |                            | Contained Aquatic Disposal (CAD)            | Dredged sediments may be consolidated and disposed of in a deep aquatic excavation adjacent to the Site and capped with clean material.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |
|                                   | Off-Site Landfill Disposal | Subtitle D (Solid Waste)                    | Contaminated sediments from the Site may be transported to an off-Site, permitted disposal facility. This disposal method provides for secure, long-term containment of hazardous and non-hazardous solid wastes.                                                                                                                                                                                                                                                                                                                                                                                                                                            |
|                                   |                            | Subtitle C (Hazardous Waste)                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |

Notes:  
BTEX = benzene, toluene, ethylbenzene, and xylenes  
COCs = chemicals of concern  
cPAHs = carcinogenic polycyclic aromatic hydrocarbons  
NAPL = non-aqueous phase liquid  
O&M = operation and maintenance  
PAHs = polycyclic aromatic hydrocarbons  
TPH = total petroleum hydrocarbons

References: U.S. Army Corps of Engineers (USACE), 2008, Technical Guidelines for Environmental Dredging of Contaminated Sediments, ERDC/EL TR-08-29, September 2008.

**Table 9-1 - Summary of Existing Information and Data Gaps - Uplands**  
Bremerton Gas Works Site  
Bremerton, Washington

| Remdial Investigation/Feasbility Study Information Needs by Topic | Existing Information                                                                                                                                                                                  | Data Gaps                                                                                                                                                                                                                                                                                                                                                                                                      | Recommended Data Collection                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
|-------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>Physical Characteristics</b>                                   |                                                                                                                                                                                                       |                                                                                                                                                                                                                                                                                                                                                                                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |
| Characteristics of water-bearing zones                            | Soil stratigraphy and observed/measured groundwater occurrence from previous investigations identifies a water-bearing zone in clean to silty glacial sands at depths of 15 to 41 feet below surface. | <ul style="list-style-type: none"><li>• Measured/tested physical properties of soil comprising water-bearing zones and aquitards.</li><li>• Hydraulic conductivity of water-bearing zones and aquitards.</li><li>• Vertical extent of the shallow water-bearing zone.</li><li>• Presence, location, and nature of aquitards.</li><li>• Presence, location, and nature of deeper water-bearing zones.</li></ul> | <ul style="list-style-type: none"><li>• Soil borings to evaluate soil stratigraphy and identify water-bearing zones and aquitards.</li><li>• Soil samples from borings for laboratory measurement of physical parameters that may include grain size, porosity, bulk density, and total/fraction organic carbon.</li><li>• Slug tests at select site wells to measure hydraulic conductivity in each saturated stratigraphic horizon and in different water-bearing zones (if applicable).</li></ul> |
| Groundwater flow direction and gradient                           | Manual groundwater level measurements collected at eight wells in 2007 were used to evaluate groundwater flow direction and gradient.                                                                 | <ul style="list-style-type: none"><li>• Groundwater flow direction and horizontal/vertical gradients.</li><li>• Seasonal variability in water levels and groundwater gradients.</li><li>• Influence of precipitation/surface water infiltration on groundwater levels.</li><li>• Influence of tidal fluctuation on groundwater levels.</li></ul>                                                               | <ul style="list-style-type: none"><li>• Continuous water levels at site wells and in the Narrows using pressure transducers.</li><li>• Precipitation amounts recorded at area weather stations.</li></ul>                                                                                                                                                                                                                                                                                            |
| Groundwater geochemistry                                          | None.                                                                                                                                                                                                 | <ul style="list-style-type: none"><li>• Location of salt water intrusion and extent of groundwater-surface water interaction.</li></ul>                                                                                                                                                                                                                                                                        | <ul style="list-style-type: none"><li>• Groundwater samples will be collected from site wells for field measurements and laboratory analysis of conventional geochemical parameters, salinity.</li></ul>                                                                                                                                                                                                                                                                                             |
| <b>Nature and Extent of Contamination</b>                         |                                                                                                                                                                                                       |                                                                                                                                                                                                                                                                                                                                                                                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |
| Identify and evaluate source areas                                | Historical review of Gas Works operations identifies potential source areas.                                                                                                                          | <ul style="list-style-type: none"><li>• Identified potential source areas have not been sufficiently investigated.</li><li>• Potential locations of some potential sources (e.g., tar pits, transfer piping) are unknown or roughly estimated.</li></ul>                                                                                                                                                       | <ul style="list-style-type: none"><li>• Ground-penetrating radar to identify potential subsurface features.</li><li>• Advance soil borings and/or complete test pits in and around potential source areas, including former process and residuals management areas, including the tar pit, residue cistern, tar wells, and in the ravine fill area.</li><li>• Visually observe and record soil stratigraphy and indications of contamination.</li></ul>                                              |
| Evaluate COPCs to determine COCs                                  | Surface and subsurface soil and groundwater samples collected in 2007 and 2008 were analyzed for metals, petroleum hydrocarbons, SVOCs, VOCs and PCBs.                                                | <ul style="list-style-type: none"><li>• Presence of COPCs previously not evaluated (e.g., cyanide).</li></ul>                                                                                                                                                                                                                                                                                                  | <ul style="list-style-type: none"><li>• Soil and groundwater samples will be collected for chemical analysis of COPCs to refine COC list.</li></ul>                                                                                                                                                                                                                                                                                                                                                  |
| Define nature and extent of COCs in soil                          | Soil samples collected in 2007 and 2008 identified concentrations of metals, PAHs, and VOCs exceeding PRGs.                                                                                           | <ul style="list-style-type: none"><li>• Current nature and extent of COCs in soil.</li><li>• Presence, nature, and extent of COPCs previously not evaluated.</li></ul>                                                                                                                                                                                                                                         | <ul style="list-style-type: none"><li>• Soil samples will be collected from soil borings and test pits in source areas and surrounding the Site to establish horizontal and vertical limits to the extent of comtamination. Soils will be submitted for chemical analysis of COCs.</li></ul>                                                                                                                                                                                                         |

**Table 9-1 - Summary of Existing Information and Data Gaps - Uplands**  
Bremerton Gas Works Site  
Bremerton, Washington

| Remdial Investigation/Feasibility Study Information Needs by Topic | Existing Information                                                                                                                                                                                                                                                                                                                                     | Data Gaps                                                                                                                                                                                       | Recommended Data Collection                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
|--------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Define nature and extent of COCs in groundwater                    | Groundwater samples collected in 2007 and 2008 identified concentrations of metals, SVOCs, and VOCs exceeding PRGs.                                                                                                                                                                                                                                      | <ul style="list-style-type: none"><li>• Current nature and extent of COCs in groundwater.</li><li>• Seasonal variability of COCs in groundwater.</li></ul>                                      | <ul style="list-style-type: none"><li>• Groundwater samples may be collected from soil borings if encountered to evaluate presence of COCs and inform well placement.</li><li>• Install monitoring wells to evaluate impacts in source areas and establish horizontal and vertical limits to the extent of contamination. Groundwater samples will be collected from monitoring wells for chemical analysis of COCs.</li></ul>                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
| Define nature and extent of NAPL                                   | Previous investigations have indicated that NAPL may be present.                                                                                                                                                                                                                                                                                         | <ul style="list-style-type: none"><li>• Presence/absence of NAPL.</li><li>• Chemical composition of NAPL.</li><li>• Lateral and vertical boundaries of NAPL occurences.</li></ul>               | <ul style="list-style-type: none"><li>• Advance soil borings and/or complete test pits in former Gas Works operations and residuals management areas, including the tar pit, residue cistern, tar wells, and in the ravine fill area. Visually observe and record soil stratigraphy and NAPL occurrences.</li><li>• Include monitoring wells screened appropriately to monitor LNAPL (across water table) and DNAPL (above aquitards). Monitor wells for LNAPL and DNAPL presence.</li><li>• Submit representative soil samples and/or NAPL collected from soil borings, test pits, or wells for chemical analysis to characterize NAPL chemistry.</li><li>• If NAPL is identified to be present: advance additional soil borings for deeper NAPL occurences and test pits for shallow NAPL occurrences in areas requiring more precise definition of NAPL occurrences.</li></ul> |
| Evaluate potential for recontamination from other area sites       | Soil and groundwater samples that have been collected from borings and wells located upgradient of the Gas Works property show potential impacts in groundwater south of the property. Limited available data do not show impacts from bulk fuel facilities east of Pennsylvania Avenue or west of Thompson Drive extending onto the Gas Works property. | <ul style="list-style-type: none"><li>• Potential impact from adjacent bulk fuel facilities and upgradient industrial sites.</li></ul>                                                          | <ul style="list-style-type: none"><li>• Soil and groundwater data collected from soil borings, test pits, and monitoring wells upgradient of the former Gas Works property will be compared to evaluate the extent of contaminants exceeding screening criteria that are associated with the Gas Works site and potential contributions from other area contaminant sources.</li></ul>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |
| <b>Contaminant Fate and Transport</b>                              |                                                                                                                                                                                                                                                                                                                                                          |                                                                                                                                                                                                 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |
| NAPL migration pathways                                            | NAPL may be present in the subsurface. MGP-related products include both LNAPL and DNAPL.                                                                                                                                                                                                                                                                | <ul style="list-style-type: none"><li>• Nature and extent of NAPL (see above)</li><li>• NAPL mobility, including NAPL physical characteristics and soil lithology/physical properties</li></ul> | <ul style="list-style-type: none"><li>• Characterize soil characteristics, NAPL characteristics, and extent (see above).</li><li>• Recovery testing to evaluate potential mobility, if NAPL observed in monitoring wells.</li></ul>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |
| Soil-to-groundwater pathway                                        | Concentrations of Gas Works-associated constituents have been detected above soil and groundwater PRGs.                                                                                                                                                                                                                                                  | <ul style="list-style-type: none"><li>• Leaching potential from contaminated soils.</li></ul>                                                                                                   | <ul style="list-style-type: none"><li>• Include TOC in soil testing program.</li><li>• Collect groundwater chemistry data along groundwater flowpaths.</li></ul>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |

Table 9-1 - Summary of Existing Information and Data Gaps - Uplands

Bremerton Gas Works Site  
Bremerton, Washington

| Remdial Investigation/Feasibility Study Information Needs by Topic | Existing Information                                                                                                | Data Gaps                                                                                                                                                                                                                                                       | Recommended Data Collection                                                                                                                                                                                                                                                                                                                                                 |
|--------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Soil-to-surface water pathway                                      | Concentrations of Gas Works-associated constituents have been detected above soil PRGs.                             | <ul style="list-style-type: none"><li>Discharge of contamination through stormwater runoff.</li></ul>                                                                                                                                                           | <ul style="list-style-type: none"><li>Characterize contamination in exposed surface soil, catch basins sediments, and surface water discharging at outfalls.</li></ul>                                                                                                                                                                                                      |
| Groundwater-to-surface water pathway                               | Concentrations of Gas Works-associated constituents have been detected in groundwater above surface water PRGs.     | <ul style="list-style-type: none"><li>Groundwater transport parameters (velocity, pathway).</li><li>Attenuation parameters.</li></ul>                                                                                                                           | <ul style="list-style-type: none"><li>Include natural attenuation parameters in groundwater testing program.</li><li>Characterize hydrogeology and chemical nature and extent (see above). Data may be incorporated into hydrogeologic and fate and transport models.</li><li>Groundwater monitoring program to assess seasonal variability and long-term trends.</li></ul> |
| Soil-to-air and groundwater-to-air pathway                         | Concentrations of Gas Works-associated constituents have been detected above current soil and groundwater PRGs.     | <ul style="list-style-type: none"><li>Potential impacts to future indoor air.</li></ul>                                                                                                                                                                         | <ul style="list-style-type: none"><li>Soil and groundwater data to be used with vapor transport modeling.</li></ul>                                                                                                                                                                                                                                                         |
| Human Health and Ecological Risk Assessment                        |                                                                                                                     |                                                                                                                                                                                                                                                                 |                                                                                                                                                                                                                                                                                                                                                                             |
| Assess potential receptors and exposure pathways                   | Concentrations of Gas Works-associated constituents have been detected above current soil and groundwater criteria. | <ul style="list-style-type: none"><li>Potential risk to human health through direct contact with soil, ingestion of groundwater, and inhalation via vapor intrusion.</li><li>Potential risk to ecological receptors through direct contact with soil.</li></ul> | <ul style="list-style-type: none"><li>Soil and groundwater chemical analytical results will be compared to human health and ecological risk-based criteria.</li></ul>                                                                                                                                                                                                       |

Notes:

BTEX = benzene, toluene, ethylbenzene and xylenes

COC = chemical of concern

COPC = chemical of potential concern

Cs-137 = Cesium 137 isotope

CSL = Cleanup Screening Level

CSO = combined sewer overflow

DNAPL = dense non-aqueous phas liquid

LNAPL = light non-aqueous phase liquide

MGP = manufactured gas plant

NAPL = non-aqueous phase liquid

NOAA: National Oceanic and Atmospheric Administration

PAHs = Polycyclic aromatic hydrocarbons

PCB = polychlorinated biphenyl

PRG = preliminary remediation goal

SCO = Sediment Cleanup Objective

SMS = Washington Sediment Management Standards regulations (WAC-173-204)

SVOC = semivolitile organic compound

TOC = total organic carbon

VOC = volatile organic compound

Table 9-2 - Summary of Existing Information and Data Gaps - Sediments

Bremerton Gas Works Site  
Bremerton, Washington

| Remedial Investigation/Feasibility Study Information Needs<br>by Topic                                                                                                    | Existing Information                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Data Gaps                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | Recommended Data Collection                                                                                                                                                                                                                                                                                                                                                                          |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>Nature and Extent of Contamination</b>                                                                                                                                 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                                                                                                                                                                                                                                                                                                                                                                                                      |
| Assess presence of chemical contaminants associated with historical Gas Works operations.                                                                                 | <ul style="list-style-type: none"><li>• Gas Works operational history is well documented.</li><li>• MGP-associated contaminants typically include PAH compounds, selected VOCs (i.e., BTEX compounds), cyanide and dibenzofuran.</li><li>• Surface sediment PAH concentrations within the intertidal beach areas have been extensively sampled.</li><li>• Some testing for other parameters (SVOCs, metals, and VOCs) has also been performed on a more limited basis.</li></ul>                   | <ul style="list-style-type: none"><li>• Sampling has not been performed in areas offshore of the former Gas Works dock.</li><li>• Testing has not been performed for cyanide in sediments.</li><li>• Testing for alkylated PAHs has not been performed (these parameters are useful in discriminating PAH sources in sediments).</li></ul>                                                                                                                                                                                                                                                                                                                            | <ul style="list-style-type: none"><li>• Collect surface sediment samples from Gas Works dock area.</li><li>• Analyze sediment samples in selected areas for cyanide.</li><li>• Analyze sediments samples in selected areas for alkylated. PAH to document the "fingerprint" of MGP-associated PAH.</li></ul>                                                                                         |
| Identify chemical contaminants potentially associated with other historical activities within the Site.                                                                   | <ul style="list-style-type: none"><li>• Other potentially significant uses of the Site and vicinity include ravine fill, oil handling, CSO/stormwater discharges, adjacent marina operations and miscellaneous industrial operations on the Sesko and McConkey properties.</li><li>• Some testing for other parameters besides PAH compounds (semivolatiles, metals and VOCs) has been performed on a limited basis.</li></ul>                                                                     | <ul style="list-style-type: none"><li>• Sampling near non-MGP sources is not sufficient to finalize list of site-associated contaminants.</li><li>• Testing has not yet been performed offshore of former Sesko Oil dock.</li><li>• Testing for alkylated PAHs has not been performed (these parameters are useful in discriminating PAH sources in sediments).</li></ul>                                                                                                                                                                                                                                                                                             | <ul style="list-style-type: none"><li>• Collect surface sediment samples from former Sesko dock area.</li><li>• Analyze sediment samples in selected areas for additional parameters to finalize list of site-associated COCs.</li><li>• Analyze sediment samples in selected areas for alkylated PAH to evaluate "fingerprint" and potential presence of non-MGP sources within the Site.</li></ul> |
| Define the lateral extent of Site-associated COCs in surface sediment, including the boundary between Site-associated contamination, and contamination from other inputs. | <ul style="list-style-type: none"><li>• Surface sediment PAH concentrations within the intertidal beach areas have been extensively sampled.</li><li>• Some testing for other parameters (semivolatiles, metals and VOCs) has also been performed on a limited basis.</li><li>• Extensive data are available documenting sediment quality within Port Washington Narrows and Dyes Inlet. Those data indicate elevated PAH concentrations and the presence of certain other contaminants.</li></ul> | <ul style="list-style-type: none"><li>• The lateral extent of site-associated PAH contamination has not been determined within Port Washington Narrows.</li><li>• Given the presence of elevated PAH concentrations in other sediments, additional sampling and "fingerprint" data will be needed to define the boundary between Site-associated PAH contamination and PAH contamination from other inputs.</li><li>• If other site-associated COCs are confirmed, then the lateral extent of these COCs in surface sediments will need to be determined, including the boundary between Site-associated contamination and contamination from other inputs.</li></ul> | <ul style="list-style-type: none"><li>• Collect surface sediment samples from across the initial study area and analyze for selected parameters.</li><li>• Conduct surface sediment samples at selected locations outside the initial study area to evaluate other influences on sediment quality and the boundary between site-associated and other contaminant sources.</li></ul>                  |
| Define the vertical extent of Site-associated COCs in sub-surface sediment, including the potential presence of subsurface hydrocarbon deposits (i.e., sheen or NAPL).    | <ul style="list-style-type: none"><li>• Subsurface testing has been performed in the western portion of the intertidal beach to evaluate the vertical extent of PAH contamination and hydrocarbon sheen in that area. Results demonstrated that sediment contamination levels decreased rapidly (i.e., within a few feet) with depth, and the area containing subsurface hydrocarbon sheen was very limited.</li></ul>                                                                             | <ul style="list-style-type: none"><li>• Subsurface testing has not been performed in other areas of the beach. The depth of contamination is therefore not defined in those areas.</li><li>• No surface or subsurface testing has been performed areas offshore of the former MGP dock.</li><li>• Core sampling data are not yet sufficient to assess whether subsurface hydrocarbon deposits (sheen or NAPL) may be present in subsurface sediments other than in the western beach area.</li></ul>                                                                                                                                                                  | <ul style="list-style-type: none"><li>• Conduct sediment core sampling and chemical analysis within portions of the initial study area to assess the vertical extent of PAH contamination.</li><li>• Include sufficient core sampling locations in nearshore and offshore areas to assess the potential presence of susurface hydrocarbon deposits (sheen or NAPL).</li></ul>                        |

Table 9-2 - Summary of Existing Information and Data Gaps - Sediments

Bremerton Gas Works Site  
Bremerton, Washington

| Remedial Investigation/Feasibility Study Information Needs<br>by Topic                                                                                                | Existing Information                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Data Gaps                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | Recommended Data Collection                                                                                                                                                                                                                                                                                                                                                                                                                |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>Human Health &amp; Ecological Risk Assessment</b>                                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                            |
| Assess the site-specific partitioning behavior of PAHs in sediments.                                                                                                  | <ul style="list-style-type: none"><li>• Literature data can be used to estimate potential partitioning of PAH compounds between sediment and porewater. However, these methods may not capture site-specific factors.</li></ul>                                                                                                                                                                                                                                                                                                                                              | <ul style="list-style-type: none"><li>• No site-specific porewater testing has been performed to assess PAH partitioning behavior in sediments</li></ul>                                                                                                                                                                                                                                                                                                                                                  | <ul style="list-style-type: none"><li>• Conduct paired analysis of bulk sediment and porewater PAH concentrations in selected study areas for analysis of site-specific partitioning behavior.</li></ul>                                                                                                                                                                                                                                   |
| Assess potential impacts of site-associated COCs to benthic receptors.                                                                                                | <ul style="list-style-type: none"><li>• The potential for benthic impacts can be assessed using bulk sediment chemistry (to be defined as described above) along with toxicity threshold values such as the SMS SCO and CSL values, and/or the EPA narcosis toxicity model.</li><li>• Porewater PAH data may be used directly to assess potential benthic toxicity using the EPA narcosis toxicity model.</li></ul>                                                                                                                                                          | <ul style="list-style-type: none"><li>• Site-specific bioassay testing could be used along-side bulk sediment chemistry and porewater testing data to assess potential benthic impacts.</li><li>• The need for bioassay testing can be assessed after review of bulk sediment chemistry and porewater PAH data to be collected as described above.</li></ul>                                                                                                                                              | <ul style="list-style-type: none"><li>• Contingent Activity: If applicable, based on review of bulk sediment chemistry and porewater testing data, collect sediment samples from selected areas for confirmational bioassay testing. This testing could be used to verify predicted impacts and refine the lateral extent of those impacts.</li></ul>                                                                                      |
| Assess potential for site-associated sediment contaminants to accumulate in the tissues of aquatic organisms.                                                         | <ul style="list-style-type: none"><li>• Literature data can be used to estimate potential uptake of PAH or other contaminants in the tissues of aquatic organisms. Reliance on literature data may not capture site-specific factors.</li></ul>                                                                                                                                                                                                                                                                                                                              | <ul style="list-style-type: none"><li>• No site-specific tissue testing data or bioaccumulation testing data has been performed.</li></ul>                                                                                                                                                                                                                                                                                                                                                                | <ul style="list-style-type: none"><li>• Develop estimates of tissue concentrations based on bulk sediment and porewater testing data and literature-based biota-sediment accmulation factors.</li><li>• Contingent Activity: If warranted, use tissue testing (preferred) or laboratory bioaccumulation testing (alternate) to directly assess the potential accumulation of site-associated COCs in selected aquatic organisms.</li></ul> |
| Document the types and quantities of aquatic species present in the vicinity of the Site and potentially relevant to human health and/or ecological risk evaluations. | <ul style="list-style-type: none"><li>• Previous habitat and fish/shellfish resource surveys have been performed in the Port Washington Narrows and Dyes inlet areas, documenting locally-abundant fish and shellfish species.</li><li>• Information regarding current and proposed shellfish growing areas, and historical patterns of fishing and shellfish harvesting are available through state and tribal agencies.</li><li>• Patterns of tribal seafood consumption have been identified in previous surveys of the Suquamish, Tulalip and Squaxin nations.</li></ul> | <ul style="list-style-type: none"><li>• Additional information is required to document the habitat conditions and the types of seafood species present within Port Washington Narrows near the Site.</li><li>• The sustainable shellfish yield for the Site has not been defined. Such information will be helpful in applying shellfish consumption rates documented in the EPA Region 10 Tribal Framework for Selecting Fish and Shellfish Consumption Rates to the baseline risk assessment.</li></ul> | <ul style="list-style-type: none"><li>• Conduct surveys of aquatic habitat and fish/shellfish resources at and near the Site within Port Washington Narrows.</li><li>• Define the potential shellfish yield for the Site based on surveys of similar properites within the Port Washington Narrows area.</li></ul>                                                                                                                         |
| Evaluate potential site-associated water quality impacts as necessary to support exposure assessments in the human health and ecological risk assessments.            | <ul style="list-style-type: none"><li>• No surface water data are currently available for the Site.</li><li>• Regional studies have documented anthropogenic surface water contaminant inputs to Port Washington Narrows and Dyes Inlet, including but not limited to stormwater and CSO discharges. Any Site-specific sampling of surface water quality will need to consider potential off-site sources for measured water quality parameters.</li></ul>                                                                                                                   | <ul style="list-style-type: none"><li>• Surface water quality for the Site and vicinity are not currently available as required to support risk assessment data needs.</li></ul>                                                                                                                                                                                                                                                                                                                          | <ul style="list-style-type: none"><li>• Analyze surface water samples for site-associated COCs. Samples to be collected from both within the initial study area and at selected background stations within Port Washington Narrows east and west of the Site.</li></ul>                                                                                                                                                                    |




Table 9-2 - Summary of Existing Information and Data Gaps - Sediments

Bremerton Gas Works Site  
Bremerton, Washington

| Remedial Investigation/Feasibility Study Information Needs by Topic                                           | Existing Information                                                                                                                                                                                                                                                                           | Data Gaps                                                                                                                                                                                                                                            | Recommended Data Collection                                                                                                                                                                                                        |
|---------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Sediment Stability and Recovery Processes                                                                     |                                                                                                                                                                                                                                                                                                |                                                                                                                                                                                                                                                      |                                                                                                                                                                                                                                    |
| Assess potential near-bottom currents on long-term sediment stability within the Site and immediate vicinity. | <ul style="list-style-type: none"><li>• Peak tidal currents within Port Washington Narrows are understood from existing studies (e.g., NOAA tide and current data).</li><li>• Sediment texture and particle size will be defined during surface sediment testing as described above.</li></ul> | <ul style="list-style-type: none"><li>• Near-bottom tidal currents can be significantly different than open-water, mid-channel currents due to local and edge effects. No near-bottom current data are available for the Site or vicinity.</li></ul> | <ul style="list-style-type: none"><li>• Conduct empirical measurements of near-bottom and mid-channel tidal currents for use in an analysis of sediment stability.</li></ul>                                                       |
| Quantify sedimentation rates using geochronology cores and radio-dating.                                      | <ul style="list-style-type: none"><li>• Geochronology studies have been performed in several areas of Puget Sound, documenting a general pattern of sedimentation.</li></ul>                                                                                                                   | <ul style="list-style-type: none"><li>• Sedimentation rates can vary with location. No sedimentation rate data are available for Port Washington Narrows areas near the Site.</li></ul>                                                              | <ul style="list-style-type: none"><li>• Contingent Activity: If warranted, quantify net sedimentation rates near the Site using geochronology test methods (i.e., thin-section cores analyzed with Cs-137 radio-dating).</li></ul> |

Notes:  
BTEX = benzene, toluene, ethylbenzene and xylenes  
COC = chemical of concern  
Cs-137 = Cesium 137 isotope  
CSL = Cleanup Screening Level  
CSO = combined sewer overflow  
EPA = U.S. Environmental Protection Agency  
MGP = manufactured gas plant  
NAPL = Non-aqueous phase liquid  
NOAA = National Oceanic and Atmospheric Administration  
PAH = polycyclic aromatic hydrocarbons  
SCO = Sediment Cleanup Objective  
SMS = Washington State Sediment Management Standards regulations (WAC-173-204)  
SVOC = semi-olatile organic compound  
VOC = volatile organic compound

# FIGURES





Parcels of Interest

Kitsap County Tax Parcel Line

Former Gas Works Property

Industrial Land Use

Generalized Zoning for City of Bremerton

Commercial

Industrial

Mixed

Park

Residential



Property Location and Area Zoning


Final Scoping Memorandum  
Bremerton Gas Works Site  
Bremerton, Washington



FIRM:  
ASPECT  
DRAWN BY:  
JJP / HRL

FIGURE NO.  
2-1





**NOTE:**  
This figure depicts known and assumed information pertaining to the carbureted water-gas process for manufacturing gas at the Site. See Figure 2-3 for approximate locations of historical process locations.

Releases of contaminants (e.g. from leaks or spills) may have occurred from any of the illustrated process steps. Byproduct disposal or releases may also have occurred at undocumented locations within or outside of the gas works operational area. Refer to Section 5 – Preliminary Conceptual Model for discussion of potential sources of contamination and release mechanisms.

**Summary of Carbureted Water-Gas Process**  
Final Scoping Memorandum  
Bremerton Gas Works Site  
Bremerton, Washington

Aspect CONSULTING


ANCHOR OEA

FIRM: ASPECT  
DRAWN BY: JJP/HRL

FIGURE NO.  
**2-2**


\\VISO-PATH-1\projects\_8\Bremerton\_MGP\Delivered\Final Scoping Memo - Nov 2014\2-2 Summary of Carbureted Water Gas Process.usd | 12/18/2015









GIS Path: I:\projects\_8\Bremerton\_MGP\Deliverables\Final Scoping Memo - Nov 2014\2.3 MGP Operations Potential Source Areas.mxd || Coordinate System: NAD 1983 StatePlane Washington North FIPS 1601 Feet || Data Source: 12/26/2014 || User: jpepin || Print Date: 2/25/2015













-  Industrial Process Feature
-  Byproducts
-  Documented/Likely Disposal Mechanism

**Other Historical Industrial Processes**  
Final Scoping Memorandum  
Bremerton Gas Works Site  
Bremerton, State

|                                                                                                                   |                                                                                                            |                        |                          |
|-------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------|------------------------|--------------------------|
|  <b>Aspect</b><br>CONSULTING |  <b>ANCHOR</b><br>QEA | FIRM:<br>ASPECT        | FIGURE NO.<br><b>2-5</b> |
|                                                                                                                   |                                                                                                            | DRAWN BY:<br>JJP / HRL |                          |







- Legend**
- Fill
  - Marine Sediments - Silt, Sand & Mud
  - Recessional Glacial Outwash - Sand & Gravel
  - Glacial Till - Silt, Sand & Gravel
  - Advance Glacial Outwash - Sand & Gravel
  - Glaciolacustrine Deposits - Silt & Clay
  - Non-Glacial Fluvial Deposits - Sand
  - Non-Glacial Lacustrine Deposits - Silt, Fine Sand & Clay
  - Undifferentiated Quaternary Deposits
  - Bedrock

**Rousse 16J**

Well or Soil Boring Log and Approximate Projected Location (See Appendix B)

**Conceptual Regional Geologic Cross Section AA-AA'**

Final Scoping Memorandum

Bremerton Gas Works Site

Bremerton, Washington

**Aspect CONSULTING**

**ANCHOR OEA**

FIRM: ASPECT  
DRAWN BY: SCC


FIGURE NO. **3-2**












### Legend


- Glacial Till
- Glacial Sand to Silty Sand
- Older Glacial Silty Sand
- Non Glacial Silt and Sandy Silt
- Fill



Red indicates concentration of naphthalene above the applicable PRG.

ND = Not detected above lab detection limit.

MS = Medium Sheen



Scale: 1" = 50' Horiz  
1" = 10' Vert  
Vertical Exaggeration = 5X


### Generalized Geologic Cross Section B-B'

Final Scoping Memorandum  
Bremerton Gas Works Site  
Bremerton, Washington



FIRM:  
ASPECT  
DRAWN BY:  
PMB/SCC

FIGURE NO.  
**3-5**



Horizontal Scale: 1" = 30'  
Vertical Scale: 1" = 6'  
Vertical Exaggeration 5x

0 30 60  
Feet


**Generalized Geologic Cross Section C-C'**  
Final Scoping Memorandum  
Bremerton Gas Works Site  
Bremerton, Washington

FIRM:  
ASPECT


DRAWN BY:  
SCC


FIGURE NO.  
**3-6**


CAD Path: Q:\Bremerton MGP\080239-Bremerton MGP\2014-07 Cross Section\080239-CC.dwg Cross Section CC' | Coordinate System: NAD 1983 State Plane Washington North FIPS 4601 Feet | Date Saved: Nov 21, 2014 1:46pm | User: scudd








 Existing Monitoring Well


 Generalized Direction of Groundwater Flow  
(Geoengineers 2007b; Geoscience Management 2007)



 Kitsap County Tax Parcel


 Historical Structures (Lined in yellow denotes Gas Works)


 Former Gas Works Property








|                                                                                                                                                                                                                                             |                                                                                                                                                          |                                                                                                                                                                                     |                                                                                                                                                                           |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <ul style="list-style-type: none"><li>Interstates</li><li>Highways</li><li>PSDEM 2005 10-foot Contours<sup>1</sup></li><li>Parks</li><li>Bremerton Gas Works Site</li><li>Cities</li><li>Unincorporated Areas</li><li>City Limits</li></ul> | <p>Outfall Type<sup>2</sup></p> <ul style="list-style-type: none"><li>Combined Storm Drain/CSO Outfall</li><li>CSO Outfall</li><li>Storm Drain</li></ul> | <p>Outfall Size (inches)</p> <ul style="list-style-type: none"><li>8 - 12</li><li>13 - 24</li><li>25 - 36</li><li>37 - 48</li><li>49 - 60</li><li>61 - 72</li><li>73 - 84</li></ul> | <p><b>Dyes Inlet and Port Washington Narrows Bathymetry and Outfall Locations</b><br/>Final Scoping Memorandum<br/>Bremerton Gas Works Site<br/>Bremerton, Washington</p> |
| <div>Aspect CONSULTING</div> <div>ANCHOR QEA</div> <div>FIRM: ANCHOR QEA<br/>DRAWN BY: ckblinger</div>                                                                                                                                      |                                                                                                                                                          |                                                                                                                                                                                     | <p>FIGURE NO.<br/><b>3-9</b></p>                                                                                                                                          |

AO GIS Path: G:\Users\100719-01\_Bremerton\_MGP\Map\2014\_07\_Scoping\_Memo\Drawings\Info\Map\SLM.mxd || Coordinate System: NAD 1983 StatePlane Washington North FIPS 4601 Feet || Data Saved: 8/1/2014 || User: ckblinger || Print Date: 2/25/2015














Note: Not to Scale


## Preliminary Conceptual Site Model





Final Scoping Memorandum  
Former Bremerton Gas Works  
Bremerton, Washington



FIRM:  
ASPECT  
DRAWN BY:  
CB / RAA

FIGURE NO.  
**5-1**



-  Indicates Generalized Occurrence and Location of Groundwater
-  Conceptual Groundwater Flow Path
-  Indicates a Potential Release, Spill or Leak Location
-  Conceptual Representation of Subsurface Non-aqueous Phase Liquid (NAPL) Occurrence and Migration

Note: Not to Scale


## Conceptualized CSM Cross Section

Final Scoping Memorandum  
Former Bremerton Gas Works  
Bremerton, Washington



FIRM:  
ASPECT  
DRAWN BY:  
CB / RAA

FIGURE NO.  
**5-2**





**Notes:**

- Includes sediment porewater.
- The portions of Port Washington Narrows adjacent to the former gas works are currently listed as closed to shellfish harvesting (due to water quality concerns associated with combined sewer overflows and issues not related to the site) by the Washington Department of Health; however, exposures associated with shellfish harvesting will be evaluated to understand potential risks should shellfish harvest restrictions be lifted in the future.
- The Gas Works Property and the adjacent properties are zoned and used for industrial uses and the zoning is not expected to change; however, residential property exposures will be evaluated to understand potential implications should property uses be converted to residential at some point in the future.
- No water supply wells are located on or near the former gas works; however, groundwater ingestion is retained for screening pending further evaluation of groundwater beneficial uses.

## Human Health Conceptual Site Model

Final Scoping Memorandum  
Bremerton Gas Works Site  
Bremerton, Washington





## Aquatic Dependent Wildlife Conceptual Site Model

Final Scoping Memorandum  
Bremerton Gas Works Site  
Bremerton, Washington



FIRM:  
ANCHOR  
DRAWN BY:  
---

FIGURE NO.  
**5-4**



**Notes:**

The majority of the upland portion of the Former Gas Works Property is paved. Unpaved Areas include the adjacent bluff and form On-site freshwater is ephemeral and consists of ponding after rain events.

## Terrestrial Wildlife Conceptual Site Model

Final Scoping Memorandum  
Bremerton Gas Works Site  
Bremerton, Washington











Sample Location with No Data

Constituent not detected, detection limit exceeds screening level

< 0.0994 mg/kg

0.0994 - 9.94 mg/kg

9.94 - 99.4 mg/kg

> 99.4 mg/kg

Exploration ID

MW-1

(3.4)

Maximum Naphthalene Concentration (in mg/kg)

• 0.0994 mg/kg = surface soil Initial Preliminary Remediation Goal (PRG)

• Initial PRG is the lowest of applicable ecological and human health risk-based screening levels

• Data qualifier "U" indicates constituent not detected above stated reporting limit, minimum detection limit shown

Kitsap County Tax Parcel Line

Former Gas Works Property

Historical Structures

Locations and dimensions of historical features are based on historical information of varying accuracy, including maps and sketches not to scale.

**Naphthalene Concentrations in Surface Soil (0 to 10 Feet)**  
Final Scoping Memorandum  
Bremerton Gas Works Site  
Bremerton, Washington


| Sample ID    | Concentration (mg/kg) | Property            |
|--------------|-----------------------|---------------------|
| MW-1         | 3.4                   | McConkey Property   |
| MW-2         | 0.00607U              | Penn Plaza Property |
| MW-3         | 708                   | McConkey Property   |
| MW-4         | 0.0016                | McConkey Property   |
| MW-5         | 0.0059                | Sesko Property      |
| MW-6         | 0.00639U              | McConkey Property   |
| MW-7         | 0.243U                | McConkey Property   |
| MW-8         | 0.0022                | McConkey Property   |
| MP-01        | 0.67                  | McConkey Property   |
| MP-02        | 0.0022                | McConkey Property   |
| MP-03        | 0.00091U              | McConkey Property   |
| MP-04        | 270                   | McConkey Property   |
| SP-01        | 0.0016                | McConkey Property   |
| SP-02        | 0.0059                | Sesko Property      |
| SP-03        | 620                   | Sesko Property      |
| BGW-RE-HA-01 | 40                    | McConkey Property   |
| BGW-RE-GP-01 | 0.64                  | McConkey Property   |

Basemap Layer Credits || Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AEX, Getmapping, Aerogrid, IGN, IGP, swisstopo, and the GIS User Community

|  |  |                       |                          |
|--|--|-----------------------|--------------------------|
|  |  | FROM:<br>ASPECT       | FIGURE NO.<br><b>7-3</b> |
|  |  | DRAWN BY:<br>CB / HRL |                          |

GIS Path: I:\projects\_8\Bremerton\_MGP-Deliverables\Final Scoping Memo\_Nov 2014\7.3 Naphthalene\_surface\_soil.mxd | Coordinate System: NAD 1983 StatePlane Washington North FIPS 4601 Feet | Date Saved: 2/26/2015 | User: jpepin | Print Date: 3/2/2015





















Total Arsenic Concentrations

Sample Location with No Data

< 0.61 mg/kg

0.61 - 7 mg/kg

> 7 mg/kg

Exploration ID

MW-1

(3.4)

Maximum Arsenic Concentration (in mg/kg)

• 0.61 mg/kg = subsurface soil Initial Preliminary Remediation Goal (PRG)

• 7 mg/kg = Puget Sound Natural Background Soil Metals Concentration

• Initial PRG is the lowest of applicable human health risk-based screening levels

• Data qualifier "U" indicates constituent not detected above stated reporting limit, minimum detection limit shown

Kitsap County Tax Parcel Line

Former Gas Works Property

Historical Structures

Locations and dimensions of historical features are based on historical information of varying accuracy, including maps and sketches not to scale.

**Legend:**

- Sample Location with No Data
- < 0.61 mg/kg
- 0.61 - 7 mg/kg
- > 7 mg/kg

**Exploration ID**

**MW-1 (3.4)**

**Maximum Arsenic Concentration (in mg/kg)**

- 0.61 mg/kg = subsurface soil Initial Preliminary Remediation Goal (PRG)
- 7 mg/kg = Puget Sound Natural Background Soil Metals Concentration
- Initial PRG is the lowest of applicable human health risk-based screening levels
- Data qualifier "U" indicates constituent not detected above stated reporting limit, minimum detection limit shown

**Kitsap County Tax Parcel Line**

**Former Gas Works Property**

**Historical Structures**

Locations and dimensions of historical features are based on historical information of varying accuracy, including maps and sketches not to scale.

**Map Labels:**

- PORT WASHINGTON NARROWS
- Current Shoreline (OHW)
- BGW-RE-HA-01
- BGW-RE-GP-01
- MW-7 (1.01)
- MP04 (3.6)
- MW-8 (6.72)
- MW-5 (3.81)
- Sesko Property
- SP03 (4.6)
- MP03 (1)
- MP02 (0.8)
- MW-3 (1.27)
- MP01 (3.2)
- McConkey Property
- MW-2 (3.18)
- MW-4 (4.8)
- SP01 (1.8)
- Penn Plaza Property
- MW-1 (1.35)
- Thompson Ave
- Pennsylvania Ave
- DRIP TANK
- APPROX TAR PIT

**Scale:** 0, 50, 100 Feet. 1:600

**North Arrow:** N

Basemap Layer Credits || Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AEX, Getmapping, Aerogrid, IGN, IGP, swisstopo, and the GIS User Community

Arsenic Concentrations in Subsurface Soil (Below 10 ft)

Final Scoping Memorandum

Bremerton Gas Works Site

Bremerton, Washington

Aspect CONSULTING

ANCHOR OEA


FROM: ASPECT

DRAWN BY: CB / HRL


FIGURE NO. 7-8

GIS Path: I:\Projects\_8\Bremerton\_MGP\Deliverables\Final Scoping Memo\_Nov 2014\7-8 Arsenic subsoil.sxd | Coordinate System: NAD 1983 StatePlane Washington North TIPS 4601 Feet | Date Saved: 3/2/2015 | User: rpepin | Print Date: 3/2/2015
















Total Nickel Concentrations

Sample Location with No Data

< 1,500 mg/kg

> 1,500 mg/kg

Exploration ID

MW-1

(3.4)

Maximum Nickel Concentration (in mg/kg)

• 1,500 mg/kg = subsurface soil Initial Preliminary Remediation Goal (PRG)

• Initial PRG is the lowest of applicable human health risk-based screening levels

• Data qualifier "U" indicates constituent not detected above stated reporting limit, minimum detection limit shown

Kitsap County Tax Parcel Line

Former Gas Works Property

Historical Structures

Locations and dimensions of historical features are based on historical information of varying accuracy, including maps and sketches not to scale.

**Nickel Concentrations in Subsurface Soil (Below 10 Feet)**  
Final Scoping Memorandum  
Bremerton Gas Works Site  
Bremerton, Washington

| Sample ID | Nickel Concentration (mg/kg) |
|-----------|------------------------------|
| MW-1      | 3.4                          |
| MW-2      | 40.6                         |
| MW-3      | 36.2                         |
| MW-4      | 44.6                         |
| MW-5      | 61.1                         |
| MW-6      | 33.3                         |
| MW-7      | 43.3                         |
| MW-8      | 42.1                         |
| SP01      | 58.2                         |
| SP02      | 57.8                         |
| SP03      | 65.3                         |
| MP01      | 54                           |
| MP02      | 32.8                         |
| MP03      | 35                           |
| MP04      | 66.3                         |

**Legend:**  
● Sample Location with No Data  
● < 1,500 mg/kg  
● > 1,500 mg/kg  
Exploration ID  
MW-1 (3.4)  
Maximum Nickel Concentration (in mg/kg)  
• 1,500 mg/kg = subsurface soil Initial Preliminary Remediation Goal (PRG)  
• Initial PRG is the lowest of applicable human health risk-based screening levels  
• Data qualifier "U" indicates constituent not detected above stated reporting limit, minimum detection limit shown  
Kitsap County Tax Parcel Line  
Former Gas Works Property  
Historical Structures  
Locations and dimensions of historical features are based on historical information of varying accuracy, including maps and sketches not to scale.

**Map Labels:**  
PORT WASHINGTON NARROWS  
Current Shoreline (OHV)  
Sesko Property  
McConkey Property  
Penn Plaza Property  
Thompson Ave  
Pennsylvania Ave  
APPROX TAR PIT  
DRIP TANK  
BGW-RE-HA-01  
BGW-RE-GP-01

**Scale:**  
0 50 100 Feet  
1:600

**Figure Information:**  
FROM: ASPECT  
DRAWN BY: CB / HRL  
FIGURE NO. 7-12

Basemap Layer Credits || Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AEX, Getmapping, Aerogrid, IGN, IGP, swisstopo, and the GIS User Community

GIS Path: I:\Projects\_8\Bremerton\_MGP\Deliverables\Final Scoping Memo\_Nov 2014\7.12 Nickel subsurf soil.mxd || Coordinate System: NAD 1983 StatePlane Washington North FIPS 4601 Feet || Date Saved: 3/2/2015 || User: rpepin || Print Date: 3/2/2015



Sample Location with No Data

< 0.39 ug/L

0.39 - 51 ug/L

51 - 510 ug/L

>510 ug/L

Exploration ID

MW-1

(3.4)

Maximum Benzene Concentration (in ug/L)

• 0.39 ug/L = Groundwater Initial PRG (lowest of applicable drinking water screening level)

• 51 ug/L = Surface Water Initial PRG (lowest of applicable surface water screening level)

• Initial PRG (Preliminary Remediation Goal) is the lowest of applicable ecological and human health risk-based screening levels

• Data qualifier "U" indicates constituent not detected above stated reporting limit, minimum detection limit shown

Kitsap County Tax Parcel Line

Former Gas Works Property

Historical Structures

Locations and dimensions of historical features are based on historical information of varying accuracy, including maps and sketches not to scale.

**Benzene Concentrations**

● Sample Location with No Data

● < 0.39 ug/L

● 0.39 - 51 ug/L

● 51 - 510 ug/L

● >510 ug/L

Exploration ID

**MW-1**  
(3.4)

Maximum Benzene Concentration (in ug/L)

- 0.39 ug/L = Groundwater Initial PRG (lowest of applicable drinking water screening level)
- 51 ug/L = Surface Water Initial PRG (lowest of applicable surface water screening level)
- Initial PRG (Preliminary Remediation Goal) is the lowest of applicable ecological and human health risk-based screening levels
- Data qualifier "U" indicates constituent not detected above stated reporting limit, minimum detection limit shown

Kitsap County Tax Parcel Line

Former Gas Works Property

Historical Structures

Locations and dimensions of historical features are based on historical information of varying accuracy, including maps and sketches not to scale.

**PORT WASHINGTON NARROWS**

**Current Shoreline (OHV)**

**BGW-RE-HA-01** ● **BGW-RE-GP-01**

**MP04**  
(70)

**MW-8**  
(650)

**MW-5**  
(85.1)

**Sesko Property**

● **SP03**

**MW-7**  
(2.23)

**MW-6**  
(950)

**MP03**

**MP02**

**MP01**

**MW-3**  
(826)

**McConkey Property**

**MW-2**  
(18.4)

**MW-4**  
(25.2)

**SP01**

**Penn Plaza Property**

**MW-1**  
(0.2U)

**SP02**  
(0.35U)

**Thompson Ave**

**Pennsylvania Ave**

**APPROX TAR PIT**

**DRIP TANK**

**0** **50** **100**

**Feet**

**1:600**

**N**

**Benzene Concentrations in Groundwater**

**Final Scoping Memorandum**

**Bremerton Gas Works Site**

**Bremerton, Washington**

**Aspect** CONSULTING

**ANCHOR** OEA

**FROM:** ASPECT


**DRAWN BY:** CB / HRL

**FIGURE NO.** **7-13**

Basemap Layer Credits || Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AEX, Getmapping, Aerogrid, IGN, IGP, swisstopo, and the GIS User Community

GIS Path: I:\Projects\_8\Bremerton\_MGP\Delivered\Final Scoping Memo - Nov 2014\7.13 Benzene\_GW.mxd || Coordinate System: NAD 1983 StatePlane Washington North FIPS 4601 Feet || Date Saved: 3/2/2015 || User: trepin || Print Date: 3/2/2015







Exploration ID

MW-1

(3.4)

Maximum Naphthalene Concentration (in ug/L)

• 0.14 ug/L = Groundwater Initial PRG (lowest of applicable drinking water screening level)

• 1.4 ug/L = Surface Water Initial PRG (lowest of applicable surface water screening level)

• Initial PRG (Preliminary Remediation Goal) is the lowest of applicable ecological and human health risk-based screening levels


• Data qualifier "U" indicates constituent not detected above stated reporting limit, minimum detection limit shown

Kitsap County Tax Parcel Line


Former Gas Works Property

Historical Structures

Locations and dimensions of historical features are based on historical information of varying accuracy, including maps and sketches not to scale.









Hexavalent Chromium Concentrations

- Sample Location with No Data
- Constituent not detected, detection limit exceeds screening level
- < 0.031 ug/L
- 0.031 - 50 ug/L
- > 50 ug/L

Exploration ID


**MW-1**  
**(3.4)**

Maximum Hexavalent Chromium Concentration (in ug/L)


- 0.031 ug/L = Groundwater Initial PRG (lowest of applicable drinking water screening level)
- 50 ug/L = Surface Water Initial PRG (lowest of applicable surface water screening level)
- Initial PRG (Preliminary Remediation Goal) is the lowest of applicable ecological and human health risk-based screening levels
- Data qualifier "U" indicates constituent not detected above stated reporting limit, minimum detection limit shown

- Kitsap County Tax Parcel Line
- Former Gas Works Property
- Historical Structures

Locations and dimensions of historical features are based on historical information of varying accuracy, including maps and sketches not to scale.







**NOTES:**  
1. Field duplicates were not included.  
2. Data presented are 2013 Removal Evaluation surface samples (0-4 inches).  
3. BAP – Benzo(a)pyrene

|                                                                                                                                   |                                                                                                                                                                                                                                                                                                    |                                                                                                                                                                                                                                                                           |                                                                                                |                                                                                                                                                  |                                                                                                                                                                                                                                                                       |
|-----------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <p>Benzo(a)pyrene µg/kg dw</p> <ul style="list-style-type: none"><li>0 - 1,600</li><li>1,610 - 3,000</li><li>&gt; 3,000</li></ul> | <ul style="list-style-type: none"><li>2010 TCRA/IA Pipe Plug Location</li><li>Assumed City of Bremerton 12-inch Storm Water Pipe Configuration</li><li>Field-located Sanitary Sewer Line</li><li>Sanitary Sewer (Not Field Located)</li><li>Sewer Line Continues West from this Location</li></ul> | <ul style="list-style-type: none"><li>Field Verified Pipe Location</li><li>Remaining 12-inch Concrete Pipe</li><li>Pipe Removed and Backfilled to Grade</li><li>Cover of Existing Organoclay Mat (10-inch minus rock)</li><li>Extent of Existing Organoclay Mat</li></ul> | <div><div>02550</div><div>Feet</div><div>1:600</div></div> <div><div>↑</div><div>N</div></div> | <p><b>Surface Sediment Benzo(a)pyrene Concentrations</b><br/>Final Scoping Memorandum<br/>Bremerton Gas Works Site<br/>Bremerton, Washington</p> | <div><div><div>Aspect</div><div>CONSULTING</div></div><div><div>ANCHOR</div><div>QEA</div></div><div><div>FIGURE NO.</div><div>7-18</div></div></div> <div><div><div>FIRM:</div><div>ANCHOR QEA</div></div><div><div>DRAWN BY:</div><div>ckiblinger</div></div></div> |
|-----------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

AS QIS PATH: Q:\Jobs\10719\_01 Bremerton\_MGP\MapSeries\14\_07 Scoping\_Memo\Final and BAP\_AirData Maps\_Summary | Coordinate System: NAD 1983 StatePlane Washington North FIPS 4901 Feet | Date Saved: 11/20/2014 | User: cckiblinger | Print Date: 11/20/2014





**NOTES:**  
1. Field duplicates were not included.  
2. Data presented are 2013 Removal Evaluation surface samples (0-4 inches).  
3. LPAH – Low molecular weight PAH.

|                                                                                                                                                                     |                                                                                                                                                                                                                                                                                                    |                                                                                                                                                                                                                                                                           |                                                                                              |                                                                                                                                                                                                                                                         |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <p>Total LPAH (SMS) (U = 0) <math>\mu\text{g/kg dw}</math></p> <ul style="list-style-type: none"><li>0 - 5,200</li><li>5,210 - 13,000</li><li>&gt; 13,000</li></ul> | <ul style="list-style-type: none"><li>2010 TCRA/IA Pipe Plug Location</li><li>Assumed City of Bremerton 12-inch Storm Water Pipe Configuration</li><li>Field-located Sanitary Sewer Line</li><li>Sanitary Sewer (Not Field Located)</li><li>Sewer Line Continues West from this Location</li></ul> | <ul style="list-style-type: none"><li>Field Verified Pipe Location</li><li>Remaining 12-inch Concrete Pipe</li><li>Pipe Removed and Backfilled to Grade</li><li>Cover of Existing Organoclay Mat (10-inch minus rock)</li><li>Extent of Existing Organoclay Mat</li></ul> | <div><div>02550</div><div>Feet</div><div>1:600</div></div> <div><div>North Arrow</div></div> | <div><div>Surface Sediment LPAH Concentrations</div><div>Final Scoping Memorandum</div><div>Bremerton Gas Works Site</div><div>Bremerton, Washington</div></div> <div><div>Aspect CONSULTING</div><div>ANCHOR QEA</div><div>FIGURE NO. 7-19</div></div> |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

AS QIS Path: Q:\Jobs\10719\_01\_Bremerton\_MGP\MapSeries\14\_07\_Scoping\_Memo\PAH and BAP\_Airphoto Maps\_Sat.mxd | Coordinate System: NAD 1983 StatePlane Washington North FIPS 4901 Feet | Date Saved: 11/20/2014 | User: cckibling | Print Date: 11/20/2014







**NOTES:**  
1. Field duplicates were not included.  
2. Data presented are Anchor and Aspect (2013) Removal Evaluation subsurface samples (>4 inches) and E & E (2008) Targeted Brownfields Assessment samples (0 to 1 foot).  
3. HPAH – High molecular weight PAH.

|                                                                                                                                                 |                                                                                                                                                                                                                                                                                                    |                                                                                                                                                                                                                                                                           |                                                                                                |                                                                                                                                        |                                                                                                                                                                                                                                     |
|-------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <p>Total HPAH (SMS) (U = 0) µg/kg dw</p> <ul style="list-style-type: none"><li>0 - 12,000</li><li>12,100 - 17,000</li><li>&gt; 17,000</li></ul> | <ul style="list-style-type: none"><li>2010 TCRA/IA Pipe Plug Location</li><li>Assumed City of Bremerton 12-inch Storm Water Pipe Configuration</li><li>Field-located Sanitary Sewer Line</li><li>Sanitary Sewer (Not Field Located)</li><li>Sewer Line Continues West from this Location</li></ul> | <ul style="list-style-type: none"><li>Field Verified Pipe Location</li><li>Remaining 12-inch Concrete Pipe</li><li>Pipe Removed and Backfilled to Grade</li><li>Cover of Existing Organoclay Mat (10-inch minus rock)</li><li>Extent of Existing Organoclay Mat</li></ul> | <div><div>02550</div><div>Feet</div><div>1:600</div></div> <div><div>↑</div><div>N</div></div> | <p><b>Surface Sediment HPAH Concentrations</b><br/>Final Scoping Memorandum<br/>Bremerton Gas Works Site<br/>Bremerton, Washington</p> | <div><div><div>Aspect</div><div>CONSULTING</div></div><div><div>ANCHOR</div><div>QEA</div></div><div><div>FIRM:<br/>ANCHOR QEA</div><div>DRAWN BY:<br/>ckiblinger</div></div></div> <div><div>FIGURE NO.</div><div>7-20</div></div> |
|-------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|











**NOTES:**  
1. Field duplicates were not included.  
2. Data presented are Anchor and Aspect (2013) Removal Evaluation subsurface samples (>4 inches) and E & E (2008) Targeted Brownfields Assessment samples (0 to 1 foot).  
3. cPAH – Carcinogenic Polycyclic Aromatic Hydrocarbon (EPA 1993).  
4. cPAH Parameters: Benzo(a)pyrene, Benzo(a)anthracene, Benzo(b)fluoranthene, Benzo(k)fluoranthene, Dibenzo(a,h)anthracene, Indeno(1,2,3-cd)pyrene, Chrysene.

- Total cPAH TEQ (U = 1/2) µg/kg dw
- 0 - 80
  - 81 - 800
  - 801 - 8,000
  - 8,001 - 80,000
  - > 80,000
- 2010 TCRA/IA Pipe Plug Location
- Assumed City of Bremerton 12-inch Storm Water Pipe Configuration
- Field-located Sanitary Sewer Line
- Sanitary Sewer (Not Field Located)
- Sewer Line Continues West from this Location
- Field Verified Pipe Location
- Remaining 12-inch Concrete Pipe
- Pipe Removed and Backfilled to Grade
- Cover of Existing Organoclay Mat (10-inch minus rock)
- Extent of Existing Organoclay Mat




**Surface Sediment cPAH TEQ Concentrations**  
Final Scoping Memorandum  
Bremerton Gas Works Site  
Bremerton, Washington









AG GIS Path: G:\Jobs\100719-01\_Bremerton\_MGPMap\2014\_07\_Scoping\_Memo\Regional\_Tiss\_Sed\_Data.mxd | Coordinate System: NAD 1983 StatePlane Washington North FIPS 4601 Feet | Data Saved: 2/12/2015 | User: cklbinger | Print Date: 2/18/2015

ENVVEST Stations

■ Tissue

EIM Stations

● Sediment

■ Tissue

— Dyes Inlet


— Ostrich Bay

— Port Orchard

— Port Washington Narrows

— Rich Passage

— Sinclair Inlet




**Locations of Existing Tissue and Sediment Data**  
Final Scoping Memorandum  
Bremerton Gas Works Site  
Bremerton, Washington



FIRM:  
ANCHOR QEA  
DRAWN BY:  
cklbinger

FIGURE NO.  
**7-24**






## Total Benzo(a)pyrene Concentrations in Existing Sediment Data

Final Scoping Memorandum  
Bremerton Gas Works Site  
Bremerton, Washington



FIRM:  
ANCHOR  
DRAWN BY:  
---

FIGURE NO.  
**7-25**



- Dyes Inlet
- Ostrich Bay
- Port Orchard
- Port Washington Narrows East
- Port Washington Narrows West
- Sinclair Inlet
- PSAMP Long-Term Temporal Monitoring
- ▲ PSAMP Spatial/Temporal Monitoring
- Urban Waters Initiative, Sediment Quality in the Bainbridge Basin

Notes: Negative distances represent waterways west of Bremerton Gasworks site.  
Positive distances represent waterways east of the site.  
PSAMP = Puget Sound Assessment and Monitoring Program.


## Total cPAH Concentrations in Existing Sediment Data

Final Scoping Memorandum  
Bremerton Gas Works Site  
Bremerton, Washington



FIRM:  
ANCHOR  
DRAWN BY:  
---

FIGURE NO.  
**7-26**



## Total LPAH Concentrations in Existing Sediment Data


Final Scoping Memorandum  
Bremerton Gas Works Site  
Bremerton, Washington



FIRM:  
ANCHOR  
DRAWN BY:  
---

FIGURE NO.  
**7-27**





- Dyes Inlet    
 ● Ostrich Bay    
 ● Port Orchard    
 ● Port Washington Narrows East    
 ● Port Washington Narrows West    
 ● Rich Passage    
 ● Sinclair Inlet
- ENVVEST Nacy Tissue Data - mussel    
 ▲ NOAA Mussel Watch Program - mussel
- Dyes Inlet/Port Washington Narrows Shellfish Sampling - clam    
 ◆ Dyes Inlet/Port Washington Narrows Shellfish Sampling - crab

Notes: Negative distances represent waterways west of Bremerton Gasworks site.  
 Positive distances represent waterways east of the site.  
 Detected values plotted with filled symbols. Non-detects plotted with open symbols.


## Total cPAH Concentrations in Existing Tissue Data (Wet Weight Basis)

Final Scoping Memorandum  
 Bremerton Gas Works Site  
 Bremerton, Washington



FROM:  
ANCHOR  
DRAWN BY:  
---

FIGURE NO.  
**7-29**



Notes: Negative distances represent waterways west of Bremerton Gasworks site.  
Positive distances represent waterways east of the site.  
Detected values plotted with filled symbols. Non-detects plotted with open symbols.

## Total cPAH Concentrations in Existing Tissue Data (Lipid-Normalized Basis)

Final Scoping Memorandum  
Bremerton Gas Works Site  
Bremerton, Washington



FROM:  
ANCHOR  
DRAWN BY:  
---

FIGURE NO.  
**7-30**



Soil and Groundwater Exploration Locations

Kitsap County Tax Parcel Line

Proposed Initial Study Area (Upland)

Historical Structures

Former Gas Works Property

Initial Study Area -- Upland

Final Scoping Memorandum

Former Bremerton Gas Works

Bremerton, Washington

Aspect

CONSULTING

ANCHOR

OEA

FIRM:

ASPECT

DRAWN BY:

CB / HRL

FIGURE NO.

8-1

Basemap Layer Credits || Source: Esri, DigitalGlobe, GeoEye, i-cubed, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AEX, Getmapping, Aerogrid, IGN, IGP, swisstopo, and the GIS User Community

GIS Path: I:\projects\_8\Bremerton\_MGP\Delivered\Final Scoping Memo - Nov 2014\8-1 Initial Study Area Upland.mxd || Coordinate System: NAD 1983 StatePlane Washington North FIPS 4601 Feet || Data Served: 11/20/2014 || User: rrandus@snr || Print Date: 11/20/2014



**NOTES:**  
1. Finlayson D.P. (2005) Combined bathymetry and topography of the Puget Lowland, Washington State.  
2. State Aquatic Lands - Managed by DNR  
3. Anchor QEA (2013) Removal Evaluation.  
4. Washington Department of Ecology Environmental Information Management system online database (queried January 2014).  
5. Kitsap County (2013) Anderson Cove Beach Sediment Sampling.  
6. If a paper copy is required, this figure is best printed in color.



Initial Study Area<sup>3</sup>

Former Gas Works Location

Cover of Existing Organoclay Mat (10-inch minus rock)<sup>2</sup>

Extent of Existing Organoclay Mat<sup>2</sup>

Surface Sediment Data Source

● Anchor QEA<sup>3</sup>

▲ EIM<sup>4</sup>

■ Kitsap County<sup>5</sup>

Outfall Size (inches)

⊕ 8 - 12

⊕ 13 - 24

⊕ 25 - 36

⊕ 37 - 48

⊕ 49 - 60

⊕ 61 - 72

⊕ 73 - 84

Outfall Type

● Combined Storm Drain/CSO Outfall

● CSO Outfall

● Storm Drain

PSDEM 2005 10-foot Contours<sup>1</sup>

0

500

1,000

Feet

1:13,327

**Initial Study Area – Sediments**

Final Scoping Memorandum

Bremerton Gas Works Site

Bremerton, Washington

Aspect

CONSULTING

ANCHOR

QEA

FIRM:

ANCHOR QEA

DRAWN BY:

ckiblinger

FIGURE NO.

**8-2**

AO GIS Path: Q:\Jobs\100719\_01 Bremerton\_MGP\Map\2014\_07 Scoping\_Memo\Initial Study Area Sed\_Summary | Coordinates: Summit, NAD 1983 StatePlane Washington North FIPS 4801 Feet | Date Saved: 11/29/2014 | User: cckiblinger | Print Date: 11/29/2014